



pinnacle



Pinnacle Studio™ 20

User Guide

Pinnacle Studio™ 20 User Guide

*Including Pinnacle Studio™ Plus and
Pinnacle Studio™ Ultimate*

Contents

Before you start.	1
Abbreviations and conventions	1
Buttons, menus, dialog boxes and windows	2
Help and Tooltips	3
Finding your version information	4
Upgrading	4
Chapter 1: Using Pinnacle Studio	5
The Importer	5
The Exporter	6
The central tabs	7
The Library	8
The next step	10
The Movie Editor and the Disc Editor	11
The media editors	12
The Player	14
Pinnacle Studio Projects	14
Chapter 2: The Library	17
Adding assets to a project	18
Correcting media files	19
Instant gratification: SmartMovie	19
Understanding the Library	20
The Navigator	23
Project Bins	24
Collections	25

Favorites	27
Managing Library assets	28
The Browser	31
Thumbnails and details	32
Optional indicators and controls	36
The Library preview	40
Choosing what to display in the Library	45
Tags	48
Correcting media	52
Video scene detection	53
SmartMovie	55
Chapter 3: The Movie Editor	59
The compact Library	59
Previewing in the project editors	61
The Project Timeline	64
The timeline toolbar	71
The timeline track header	80
Editing Movies	83
Title Editor, ScoreFitter, voice-over	90
Deleting clips	91
Clip operations	91
Using the Clipboard	106
Speed	108
Movies within movies	110
Picture-in-Picture (PIP)	111
.	113
Track Transparency	113
Transitions	114
Clip effects	121

Clip context menus	122
Chapter 4: Corrections.	125
Media editing overview	128
Photo editing tools	134
Correcting photos	136
Red-eye	142
Correcting video	143
Video tools	144
Video corrections	147
Stabilize	150
Correcting audio	150
Chapter 5: Effects	151
Effects in the media editors	154
Effects on the timeline	158
The Settings panel	160
Working with keyframes	163
Video and photo effects	166
Working with transitions	171
Pan-and-zoom	173
360 Video	177
Motion Tracking	180
Chapter 6: Montage	185
The Montage section of the Library	187
Using montage templates	188
Montage clips on the timeline	190
Anatomy of a template	193
Montage editing	196
Using the Montage Editor	196

Chapter 7: The Title Editor	201
Launching (and leaving) the Title Editor.	203
The Library	205
The Presets Selector.	207
Preset Looks	208
Preset Motions	209
Creating and editing titles.	212
Background settings	214
Look settings	215
The Edit window.	220
Text and text settings	223
Titles and stereoscopic 3D.	229
The Layer List	231
Working with the Layer List.	232
Working with layer groups	237
Chapter 8: Sound and music	243
The Audio Editor.	245
Audio corrections	251
Audio effects	256
Audio on the timeline	259
Timeline audio functions.	259
Audio creation tools	264
ScoreFitter	264
The Voice-over tool.	266
Using Audio Ducking to automatically adjust volume	269
Chapter 9: Disc projects	271
Disc menus	273
Adding disc menus	276
Previewing disc menus	279

Menu editing on the timeline	281
Timeline menu markers	281
Authoring tools.	282
The Chapter Wizard	285
The Menu Editor	289
Menu buttons.	289
The Disc Simulator	292
Chapter 10: The Importer	295
Using the Importer	296
Importer panels.	298
The Import To panel	302
The Mode panel	306
The Compression Options window	310
The Scene Detection Options window	311
The Metadata panel	312
The Filename panel	313
Selecting assets for import	315
Selecting files for Import	316
Customizing the browser	321
Adjusting the import file date and time	323
Scan for assets	323
Import from DV or HDV camera	324
Import from analog sources	330
Import from DVD or Blu-ray Disc	331
Import from digital cameras	333
Stop motion	333
Snapshot	340
Chapter 11: The Exporter.	345
Output to disc or memory card	349

Output to file	352
Output to cloud	360
Output to a device	363
Output to a MyDVD file	364
Chapter 12: Setup	367
Watchfolders	367
Audio device.	368
Event logging	368
Export and Preview	368
Import	372
Keyboard	374
Project settings	376
Storage locations	377
Reset	378
Restore purchase.	378
Chapter 13: Screen capture	379
Starting a screen capture project.	379
Recording your screen.	380
Chapter 14: Multi-Camera Editing	383
The Multi-Camera Editor workspace	384
Basic steps in multi-camera editing	387
Importing video and audio clips into the Multi-Camera Editor . .	388
Synchronizing video and audio clips in multi-camera projects . .	389
Choosing an audio source for your multi-camera project	390
Editing multiple clips to create a multi-camera compilation	392
Adding picture-in-picture (PIP) in the Multi-Camera Editor.	395
Managing multi-camera source files	396
Saving and exporting your multi-camera project	397

Using Smart Proxy for a faster, smoother editing experience . . .	398
Appendix A: Troubleshooting	401
Contacting support	402
Forums	402
Top support issues	402
Capture hardware compatibility	407
Serial number information	408
Error or crash while installing	409
Hangs or crashes while launching	410
Troubleshooting software crashes	412
Case 1: Studio crashes randomly	413
Case 2: Studio crashes after a user action	417
Case 3: Studio crashes repeatably	417
Export problems	418
Disc playback problems	418
Appendix B: Videography	421
Creating a shooting plan	421
Editing	422
Rules of thumb for video editing	426
Soundtrack production	428
Title	429
Appendix C: Glossary	431
Appendix D: Keyboard shortcuts	447
General shortcuts	447
Library	448
Playing and transport	449
Importer	450
Movie interface	450

Media editors	452
Title Editor	452
Appendix E: The installation manager	453
Before you begin.	453
Upgrade Installation	454
Launching the Installation Manager	454
Registration	454
Supporting installations	455
The Welcome Screen.	455
Common controls	455
Installing plugs-ins and bonus content	456
System requirements.	456



Thank you for purchasing Pinnacle Studio™ 20. We hope you enjoy using the software.

If you have not used Pinnacle Studio before, we recommend that you keep the user guide handy for reference even if you don't actually read it all the way through.

Note: *Not all features described in the user guide are included in all versions of Pinnacle Studio. For more information, please visit www.pinnaclesys.com and click **Compare**.*

Abbreviations and conventions

This guide uses the following conventions to help organize the material.

Common terms

AVCHD: A video data format used by some high-definition camcorders, and for creating DVD discs that can be read on Blu-ray players. Successful editing of AVCHD files requires more computing power than other formats supported by Pinnacle Studio.

DV: This term refers to DV and Digital8 camcorders, VCRs and tapes.

HDV: A 'high-definition video' format that allows video in frame sizes of 1280x720 or 1440x1080 to be recorded in MPEG-2 format on DV media.

1394: The term ‘1394’ applies to OHCI-compliant IEEE-1394, FireWire, DV or i.LINK interfaces, ports and cables.

Analog: The term ‘analog’ applies to 8mm, Hi8, VHS, SVHS, VHS-C or SVHS-C camcorders, VCRs and tapes, and to Composite/RCA and S-Video cables and connectors.

Buttons, menus, dialog boxes and windows

Names of buttons, menus and related user interface items are written in **bold** to distinguish them from the surrounding text.

Choosing menu commands

The right arrowhead symbol (>) denotes the path for hierarchical menu items. For example:

- Select **File > Burn Disc Image**.

Context menus

A ‘context menu’ is a pop-up list of commands that appears when you click with the right mouse-button on certain areas of the application interface. Depending where you click, a context menu may pertain either to an editable object (like a clip on an editing timeline), to a window, or to a zone such as a control panel. Once open, context menus behave just like the ones on the main menu bar.

Context menus are available in most parts of the Pinnacle Studio interface. Our documentation generally takes for granted that you know how to open and use them.

Mouse clicks

When a mouse click is required, the default is always a left-click unless otherwise specified, or unless the click is to open a context menu:

Right-click and select *Title Editor*. (Or, one might say, “Select *Title Editor* from the context menu.”)

Key names

Key names are spelled with an initial capital and are underlined. A plus sign denotes a key combination. For example:

Press **Ctrl+A** to select all the clips on the Timeline.


Please refer to *Appendix D: Keyboard shortcuts* for a comprehensive table of available shortcuts.

Help and Tooltips

Immediate help is available while you are working in Pinnacle Studio via the Help menu.

Help

The Help menu lets you access a variety of learning resources. Click the **Help** button > **User Manual** to access the **Learning Center** page with links to video tutorials, the **Pinnacle Studio 20 User Guide** PDF, and other community and support links.



Video tutorials

You can access video tutorials from the Learning Center page (**Help** > **User Manual**) or by visiting the following sites directly:

- YouTube — <http://www.youtube.com/user/pinnaclestudiolife>
- StudioBacklot.tv — <http://www.studiobacklot.tv/studio20>

Get a 21-day, all-access pass to StudioBacklot.tv, featuring brand-new Pinnacle Studio 20 content, loads of other training and a royalty-free stock library. (Training is in English only.)

Tool tips

To find out what a button or other Studio control does, pause your mouse pointer over it. A 'tool tip' pops up to explain the control's function.

Finding your version information

Whether you are considering upgrading your software or looking for support, it's good to know your version information. To check the version of Pinnacle Studio that you have, click the **Help** button > **About**.

Upgrading

There are different versions of Pinnacle Studio and features vary depending on the version you have. For more information, please visit www.pinnaclesys.com and click **Compare**.

For information about upgrading your software, click the **Help** button > **Online Offers & News** > **Software Offers**.



For a simple outline of the digital movie-making process, you don't have to look any further than the central tab group of Pinnacle Studio's main window. The same steps apply to any type of production, from an unpretentious slideshow with dissolves between each frame to a 3D extravaganza containing hundreds of carefully-arranged clips and effects.



Pinnacle Studio's main control bar summarizes the movie-making process.

The Importer


Import on the right, is a preparatory step. It involves procedures like 'capturing' video from your analog or DV camcorder, bringing in photos from a digital camera, and copying media files to your local hard drive from a network location.

The Pinnacle Studio Importer provides tools for these tasks, along with a Snapshot feature for grabbing frames from video files, and a Stop motion tool for building up video frame-by-frame. See "Chapter 10: The Importer" on page 295 for details.

File menu import commands: Choosing **Import** from the file menu has the same effect as clicking the Import tab: it opens the **Importer**. The menu provides three other import-related choices as well. Each of

these opens a Windows file dialog to permit import of files from a hard drive or other local storage.

- **Import previous Pinnacle Studio Projects** lets you load movie projects created with earlier versions of Studio.
- **Import Studio for iPad App Projects** lets you bring in projects exported from Studio's companion app for the iPad.
- **Quick Import** lets you directly select ordinary media files—photo, video, audio and project—for import.




Studio Importer

The Exporter

At the other end of the movie-making process is **Export**. By the time you get to this stage, the hard part of the task is behind you. The

creative energy that went into making your movie has paid off in a production that now lacks only one ingredient—an audience.



Studio Exporter

The Pinnacle Studio **Exporter** helps you over that last hurdle with tools for taking your movie to its viewers, whoever and wherever they might be. Create a digital movie file in the format of your choice, burn a DVD, or upload directly to destinations in the Cloud like YouTube and Vimeo, or to your personal Cloud-based storage area.

Like the Importer, the Exporter opens in a separate window, and returns to the main window after its work is done. See “Chapter 11: The Exporter” on page 345 to learn more.

The central tabs

The three central tabs, **Organize**, **Edit** and **Author**, are where most of your work in Pinnacle Studio takes place. The first of these opens the

main view of the Library, where you can ‘curate’ your media collections.

The other tabs open the two project editors, one for digital movies, and the other for disc projects, which are digital movies enhanced with interactivity in the form of DVD menus.

The Library

The Library is a cataloging and management tool for all the file-based resources – or *assets* – that you can draw on when authoring. Almost all of the materials of your movie – video footage, music and audio files, and many specialized resources such as transitions and effects – originate as assets in the Library. Many Library assets are supplied with Pinnacle Studio, and are available for royalty-free use. These include professionally-designed titles, DVD menus, sound effects and more.

The Library uses project bins to organize assets. Project bins are virtual folders for your assets. They are created automatically during import and you can create them manually to organize your assets according to your needs (for example, by project).


You can also use watchfolders to automatically monitor and import media files that are added to the folders you choose to “watch”. For information about activating watchfolders, see “Watchfolders” on page 367. When you use watchfolders, a **Library Media** branch is added to the Asset Tree in the Library. You will also see a **Library Media** branch if Pinnacle Studio detects a library from a previous version of Pinnacle Studio (you must enable watchfolders if you want to continue populating this branch).

Main view

When you click the **Library** tab, the **Library** takes over the main window. This 'main view' gives you spacious access to a number of cataloging and search tools, including those for categorizing assets by means of ratings and tags, and those for creating user-defined asset collections.

Compact view

The 'compact view' of the Library squeezes virtually the whole functionality of the main view into a panel embedded within certain other windows, such as the **Movie Editor** and the **Disc Editor**. The primary purpose of the compact view is to allow assets to be brought into a movie or disc project from the **Library** by drag-and-drop.




The main view of the Library consists of navigation controls for exploring media assets (left) and a browser for examining and selecting assets (right).

Player

The tools available from within the **Library** include the **Player**, a viewer that works for all media types handled by the application. When used from the main view of the Library, the Player opens in a separate

window. When the compact Library is used, an embedded version of the Player appears in the same window. For more information, see “The Player” on page 14.



Previewing a Library video asset in the resizable Player window, with full transport controls including a shuttle wheel. You can keep working in the main window while the pop-up Player is open.

For comprehensive coverage of the Library and its uses, please see “Chapter 2: The Library” on page 17.

The next step

The next step, once you know your way around the Library and have made any changes needed to the default set-up, is to start creating a movie. There are two ways to go about this.

The usual way

If you want to exert detailed control over the way media assets are used in your production, you will usually start building your movie or disc project from scratch in one of the two project editors.

These are described below.

The easiest way


For ultra-quick results, the Library offers another way. Clicking **SmartMovie** at the bottom of the Library main view opens an extra tray of controls. With either of these you select some visual media assets to serve as the basis of the project, choose music for a soundtrack, and make a handful of other customizations. Then the software takes over, automatically generating a full-scale Pinnacle Studio project containing the media and options requested. You can export the project immediately, or edit it further by hand as you choose. For more information, see “Instant gratification: SmartMovie” on page 19.

The Movie Editor and the Disc Editor

Once you have gathered your materials together and organized them to your satisfaction in the Library, it's time to get to work on a video or a slideshow. If you are working on a disc production specifically, you can immediately start work in the **Disc Editor**, which is just like the **Movie Editor** but has extra tools for creating and setting up DVD menus. For more information, see “Chapter 9: Disc projects” on page 271.

If you aren't planning on creating a disc, or aren't sure, or if disc is only one of the output media you are targeting, the Movie Editor is the right place to start. Once your movie is completed, you can export it to the Disc Editor and add in the menus.

The Movie Editor and the Disc Editor exist side-by-side, but apart from the export feature just mentioned, they do not interact. If you want, you can have a regular movie project and a disc project loaded simultaneously, and switch from one to another at will.



In both the Movie Editor and the Disc Editor, a multitrack timeline occupies the lower part of the display. Most of the 'clips' on the timeline come from the Library; a few types, like automatic background music, are generated with special tools.

Both project editors include embedded versions of the Library and the Player in addition to the timeline display. To build a project, drag assets from the compact Library onto the timeline tracks, where they are known as 'clips'. Both the Movie Editor and the Disc Editor can be used with Stereoscopic 3D as well as 2D material.

The **preview type** control above the Player lets you switch between viewing the current Library asset ('source') and the current timeline clip. In the Disc Editor, an additional preview type ('menu') lets you use the Player as an editor for linking disc menus to points on the project timeline.

Timeline editing, a central activity in project authoring. "Chapter 3: The Movie Editor" on page 59.

The media editors

Additional windows are often needed for working with particular types of media. In general, you can open an editor window appropriate to any asset or clip by double-clicking the item.

Corrections from the Library

The editors for the standard media types of video, photo and audio are particularly important. When invoked from the Library (by double-clicking an asset), each of these editors provides a suite of correction tools appropriate to its media type. These tools can be applied directly to Library assets in order to remove camera shake from video, trim unwanted material from a photo, or suppress audio hiss, to give just a few examples.

When a correction is applied to a Library asset, the media file is not modified. Instead the correction parameters are saved in the Library database. They can be altered at any time, or removed, as your needs dictate. The corrections you make in the Library are brought with the asset when you add it to your project timeline as a clip.

Corrections from the timeline

When you open one of the standard media editors by double-clicking a timeline clip, the correction tools are again available, although in this case they apply only to the clip in the project, not to the underlying Library asset.

Transitions and Effects

When they are invoked from the project timeline, the media editors also offer effects, which cover a wide-range of enhancements in all three media types in the transition in, transition out, and effects groups.

Transitions let you punctuate the passage of one clip to the next with anything from a barely perceptible dissolve to an audience-awakening flare.

Effects range from the practical (**Brightness and contrast**) to the theatrical (**Fractal fire**). Effects can be animated with keyframed parameter changes to any degree of complexity. They provide innumerable ways to add creative interest to your productions. Some effects are particularly designed for 3D material.

Pan-and-zoom

The Photo Editor provides one more tool, pan-and-zoom, of its own. Like the effects just discussed, pan-and-zoom can be animated with keyframes to create any desired combination of simulated pan and zoom camera moves within the boundaries of a single photo.

For more information about Correction tools and the media editors, see “Chapter 4: Corrections” on page 125 and “Chapter 5: Effects” on page 151.

The Player

The **Player** is a preview screen in which you can examine **Library** media, play back your movie project, work on disc menus, and much more. In each window or context in which it is used, the Player exhibits somewhat different controls. For an introduction to the Player and its basic controls, please see “The Library preview” on page 40. For the use of the Player in trim mode on the timeline, see “Clip operations” on page 91. For information on using the Player with Montage, see “Using the Montage Editor” on page 196. For the use of the Player in editing disc menus, see “Previewing disc menus” on page 279.

Pinnacle Studio Projects

The movies and discs that you create in Pinnacle Studio are distilled from the projects that you build on the timeline of the Movie Editor or the Disc Editor.

To manage projects, Studio must keep track of everything that goes onto your timeline, and all the editing decisions you make with regard to trimming, adding effects, and much more. Much of this information is stored in the project file, which is in **axp** (Studio Movie) format. For Stop Motion, projects are saved in the **axps** format.

In order to conserve hard drive space when dealing with files that can be very large, the project file does not include the media items in your movie. For these, only their location in the Library is stored.

The axp project file is the default file format for the **File > Open**, **File > Save** and **File > Save As** menu commands. It may be the only one you need.


Sometimes, however, it is convenient to have all the resources recruited for a project gathered into a single, manageable unit for hassle-free archiving, file transfer or upload. This is the purpose of an alternative file format, the **axx** (Studio Project Package), which contains in a single file all the materials your project uses, including media items. Of necessity, files in this format are considerably larger than standard project files.

Although it is not possible to directly edit a project in the package format, Pinnacle Studio lets you open a project package with **File > Open** by selecting axx in the file extension box. Studio seamlessly unpacks the project, creates a new Library entry for the unpacked version, and opens it for editing.

If you create a multi-camera project in the Multi-Camera Editor, the project is saved as a **mcam** file. When you add an **mcam** file to the timeline, it is added as a single track by default. You can expand it by right-clicking the file in the timeline and choosing Edit Movie.

Chapter 2: The Library

The Pinnacle Studio Library, displayed when you click the **Organize** tab, is a cataloguing and management tool for all the file-based resources you can draw on when authoring. Its purpose is to let you choose and use the video segments, photos, sound bites, transition effects, titles and other ‘assets’ (as they are often called) for your movies as easily, rapidly and intuitively as possible.



The Pinnacle Studio Library

The Library's classification scheme resembles what you might see in a file-system viewer. While the viewer groups files under their physical storage locations such as hard drives, the Library groups assets under their type – video, photo, and so on. In other respects, the tree view concept for accessing subgroups of assets is virtually identical and should feel immediately familiar.


In addition to audio, photo and video files in standard formats, the Library includes specialized auxiliary media like titles and disc menus. They are found, along with transitions, filters and other effects, in the main category called Content.

The Library can easily manage large media holdings such as are often found nowadays even on a home system. All of the dozens of media file types usable in Pinnacle Studio can be browsed, organized and previewed within its integrated interface.

Assets are displayed either as icons or text records within collapsible folders that stack up in the Library Browser. The folders may correspond either to real directories in your computer's file system, or to virtual groupings based on ratings, file type, creation date, or membership in a user-defined Collection.

Adding assets to a project

Two views of the Library are found in Pinnacle Studio. The Main view takes over the application window when you click the Organize tab. It uses the full available space to provide as much information as possible.



To open the Main Library view, click the Organize tab at the top of the Pinnacle Studio application window.

The Compact view of the Library is a panel, either docked (as in the Movie and Disc project editors) or floating (as in the Title Editor). The Compact view retains the full functionality of the Library. Its primary

purpose is to allow you to bring Library assets into a movie or disc project with drag and drop.

The current set of Library tabs, and the contents of the Browser, are common to all views of the Library. For instance, if you are browsing in a particular folder of disc menus in the Main view, that same folder will be open in the Compact view if you now switch to the Movie Editor.

Correcting media files

With regard to technical quality, media files are not all created equal. Occasionally, you do come across the perfect photo, clip, or sound effect. More often, though, the photo needs cropping, the video is shaky, or the sound starts with an annoying hiss. Pinnacle Studio's media correction tools let you fix these and similar issues by applying correction filters to a problem clip after you have placed it on the timeline of your project.

Often, however, an even better solution is to apply the correction to the Library asset itself, before adding it to a project. That way, any production using the asset will start with the corrected version, not the unsatisfactory original. Such corrections can quickly be made by opening media editors from the Library. The file underlying the corrected asset is not modified: instead, the correction parameters are stored in the Library database and reapplied whenever the item is displayed or used.

Instant gratification: SmartMovie

In addition to the core functions mentioned so far, the Library offers a matching pair of tools for automatically constructing a complete project using media resources you specify. Just select some photos or video sequences, enter a few settings, and start. You can output the

project Studio generates without further modification, or refine it with manual editing as you prefer. For more information, see “SmartMovie” on page 55.

Understanding the Library

The Studio Library lets you manage and efficiently use the entire pool of media and other assets available for use in your productions.

What exactly does the Library contain?

The full range of assets that you can draw on for your projects is summarized by the four main branches of the Asset Tree. Each branch is further divided into more specialized subsections.

The **Project Bins** branch organizes your imported media in virtual folders. By default, the folders are labelled according to import date, but you can right-click a folder to rename it and you can click the **Create new project bin** button to add a new bin.


The **Library Media** branch appears only if you enable Watchfolders or if your current version of Pinnacle Studio detects a previous library (see “Watchfolders” on page 367). In most cases, Project Bins can be used instead of the Library Media branch.

The Library Media branch contains the standard media files on your system in subsections named **Photos**, **Video**, and **Audio**. Many standard file types are supported. The purpose of the fourth subsection, **Missing media**, is described below.

The **Projects** branch of the Asset Tree contains your own Pinnacle Studio movie and disc projects. You can open a project right from the Library and begin editing it, or you can add it to the timeline of another project to serve as an ordinary clip.

Collections are custom groupings of Library media. The more time you spend on media management, the more you will probably use Collections. They can serve as temporary holding places while you work, or for classifying and setting aside media for later use. Collections may be automatically generated, but most are user defined. Hierarchically-organized Collections are also supported. The top-level Collections in the hierarchy are used as subsections of the Collections branch.

The **Content** branch is either a type of special effect (Effects and Transitions), or a special media type. Ready-to-use, royalty-free collections of all seven types are included with Pinnacle Studio.



Storage of Library assets

Every asset in the Library – every clip, sound, transition, and so on – corresponds to a file somewhere in the local storage of your computer system. The Library doesn't 'own' these files, and never modifies them unless specifically requested to do so. Rather, it keeps track of their names, locations and properties in an internal database. The information stored also includes any tags and ratings with which you have annotated particular items, and the parameters of any correction filters you have applied.

The database

The files that make up the Library database are stored in a folder with single-user rather than shared access rights under Microsoft Windows. If Pinnacle Studio is used on your computer by multiple users with individual log-ins, a separate Library will be created for each.

Missing media

Operations like adding, removing and renaming a Library asset are database operations that have no effect on the media file itself. When you remove an asset from the Library, an option on the confirmation dialog box does let you go one step further and delete the actual file as well, but the option is off by default – you have to specifically request the action.

By the same token, when you delete or move an asset file in Windows Explorer or another application outside of Pinnacle Studio, the database record of the file continues to exist. Since the Library can't actually access the file, however, an error graphic is added to the file's listing. If the file still exists, but has simply been moved to another folder or device, relinking it to the Library is easy. Double-click the item to pop up a standard **File Open** dialog with which you can point the way to the file's new location.




Incidentally, to check if there are missing media anywhere in the Library, look in the special subsection **All media > Missing media** of the Asset Tree.

Location tabs

Editing a video project involves coordinating the various media and other assets at your disposal. As you proceed, it's likely that you'll find yourself browsing repeatedly in various parts of the Library that are relevant to the project. No doubt you will also change your viewing and filtering options from time to time, depending on the material you're reviewing.

Like a web browser that uses a row of tabs to allow flipping effortlessly amongst multiple open web sites, the Library lets you create and configure location tabs as you work. The tabs provide direct access to each of the various locations in which you are currently working.





Here three tabs give access to media required by different parts of a disc project. The mouse pointer is poised to create a new tab. To close a tab, click the x icon to the right of the tab caption.

To set the location of the current tab, click a name in the Asset Tree. Changes you make to viewing and filtering options while the tab is active are retained between accesses.

The Navigator

The entire gamut of Library assets is organized into an asset tree whose folder-style structure and general usage should be familiar from file-system tools like Windows Explorer. When you select a location in the Navigator, the folder name appears on the caption of the active location tab, and its contents are displayed in the neighboring Browser.



In the Main Library (top), the Navigator occupies the left-hand pane of the workspace. In the compact view (bottom), used by Studio's project and media editing tools, the Navigator is presented instead as a dropdown list on the active tab.

Project Bins

Project bins are virtual folders for your assets. They are created automatically during import and you can create them manually to organize your assets according to your needs (for example, by project).

To create a project bin

- 1 In the **Project Bins** branch of the Library Asset tree, click the **Create a new project bin** button 

- 2 Type a name for you bin and click **OK**.

The bin is added to the end of the project bin list.

To rename a project bin

- 1 In the **Project Bins** branch of the Library Asset tree, right-click a project bin, and choose **Rename**.

The current name appears highlighted

- 2 Type a new name for the bin.

To remove a bin

- In the **Project Bins** branch of the Library Asset tree, right-click a project bin, and choose **Remove Project Bin**.

Collections

From the Library's point of view, a Collection is just an arbitrary grouping of assets – a set of Library items with no organizing principle. You may well have a good reason for gathering certain files into a particular collection, but the Library doesn't have to know what it is. Inside a Collection, any asset can rub shoulders with any other.

One special Collection, with the name **Latest import**, is automatically updated after each import operation to display the media added. Immediately after importing, you can turn to this Collection and start working with the new material.

Another automatically-generated Collection is **Latest Smart Creation**, which stores the media you selected for your most recent **SmartMovie** production.

To create a new collection

- 1 Click the icon in the header line of the **Collections** branch and enter a name in the provided text field.
- 2 Complete the process by pressing **Enter**.

Tip: Alternatively, choose **Add to collection > Create new collection** from any asset's context menu.

To manage collections

- 1 Right-click a collection and choose a command for renaming or deleting the collection, or for creating a subcollection that has the current Collection as its parent 'folder'.

To organize a collection

- Drag and drop a collection in the **Navigator** with the mouse. A dragged Collection becomes a subcollection when dropped upon another.

Displaying collected assets

Clicking the name of a Collection causes it to be displayed in the Browser. As your mouse pointer passes over any listed asset, the Collections to which the asset belongs 'light up' in the Navigator.

Operations on collected assets

These operations can be performed from the context menu of any Collection item. To act on a group of items, first select them with the mouse (using Ctrl-click and Shift-click for multiple selections as needed) or by dragging out a frame around the items. Then right-click within the selection to access the context menu.

To add to a collection

- Choose a target Collection on the **Add to collection** submenu to add the selected item or items.

Tip: Alternatively, drag the selection onto the target Collection.

To remove items from a collection

- Click the **Remove** command to remove the item (or items) from the Collection. As usual with the Library, the underlying media items involved are not affected, so removing a video or other item from a Collection in the Library does not delete it from other Library locations.


Favorites

Using Favorites is a quick way to mark and find your preferred content, such as your favorite effects, transitions, and titles.

To mark content as Favorite

- 1 In the Navigation panel of the Library, open the **Content** branch, and click a content type.
- 2 In the browser area of the Library, right-click a thumbnail and choose **Add to Favorites**.

Content marked as Favorites appears at the top of the Library in a **Favorites** folder (when the content is organized by folder). Each type of content has its own **Favorites** folder that can be accessed from the corresponding **Content** category in the Navigator panel.



Favorites in the Library

Managing Library assets

Media and other assets find their way into the Library in several ways. For instance, the original contents of the Content branch of the Library are installed with Pinnacle Studio.

The Library automatically discovers some assets on your system by regularly scanning Windows-standard media locations. These are set up on Pinnacle Studio installation as watchfolders. Media files in these locations will automatically be brought into the Library. You can add

your own watchfolders (see below), and they will be automatically updated, too.

Finally, you can import media manually by any of several methods.


Watchfolders


You can turn on Watchfolders to monitor directories on your computer. If you add media files such as video clips to a watchfolder, or one of its subfolders, the files automatically become part of a Media Library branch in the Asset Tree. Updating occurs each time the application is launched and while the application is running.

Watchfolders are set up on the Watchfolders page of the Setup control panel. For each folder that you add, you can specify that either one particular supported media type will be ‘watched for’, or all of them. Please see “Chapter 12: Setup” on page 367 for more information.

Importing

If you need to import a large amount or variety of media, or to import from analog media such as VHS tape, click the Import button near the top of the application window to open the Importer. See “Chapter 10: The Importer” on page 295 for full information.

Quick import: The Quick Import button  at the top left of the Library opens a Windows file dialog for fast import of files from a hard drive or other local storage. New folders in the corresponding media categories (photos, video, audio and projects) are created for the files specified. In addition, the imported items are included in the Last Import Collection.



Direct import via drag and drop: To select and import items in one step, use drag-and-drop from Windows Explorer or the desktop into the Browser. The new items are immediately displayed in the Collection 'Latest Import', which is created for the occasion if necessary.

Exporting directly from the Library

Any photo, video, audio file or project in the Main Library can be directly exported "as is", using the context menu commands described below, to either a Cloud-based storage service or a disc. For other exporting options, use the Exporter instead, by selecting the asset and clicking the Export tab at the top of the window. See "Chapter 11: The Exporter" on page 345 for full information.

To store a Library asset on a disc, select **Burn Disc** on the context menu. You can burn just the file, or a disc image if you have made one. If you select multiple assets, and then select **Burn Disc**, all of the assets will appear on the Burn files to disc dialog. More assets can be added by clicking the File icon and browsing. You can also delete files from the list before burning.

Removing items from the Library

To remove an item from the Library, or a selection containing multiple items, choose **Delete** selected from the context menu or press the **Delete** key. A confirmation dialog lets you approve the list of media files to be removed from the Library database. By default, the files themselves will not be affected, but the Remove from library and delete option lets you delete the files too, if desired. Be careful, as this command works on all kinds of Library assets, including your Pinnacle Studio projects if any of those are selected.

When all the files in a folder are removed, the Library hides the folder as well.

You may also remove a folder and all the assets it contains from the Library when removing the folder from the watchfolders list. However, this is not automatic and you will be asked if you want to keep your current assets listed in the Library, but still stop monitoring the location.

The Browser

This is the area in which the Library displays its media assets – the videos, photos, audio, projects, collections and ‘content’ that are available for you to use in your movie and disc projects. The items are displayed either as a list of text records or as a grid of icons. Visual asset types use thumbnail images for their icons; other types use graphic symbols.

The Library would not be much help if the Browser displayed all its assets at once. It therefore has several controls that help you screen out items that aren’t relevant to your purpose. See “Choosing what to display” below for details.

Controlling the Browser display

A group of controls in the Library’s footer bar provides general functions for managing the way assets are presented in the Browser.



The **info** button, available in the main Library only, toggles the display of a panel across the bottom of the Browser pane where details about the current asset are displayed, such as its caption, file name, rating, and any tags or comments associated with it. The information may be edited, and for some assets, you can also open the corrections tools by clicking the gear icon on the top left corner of the pane.

The **scenes view** button applies to video assets only. While this button is active, items in the Browser represent the individual scenes in a particular video, not the entire asset as usual. See “The Library preview” on page 40 for more information.



In the main Library, this and the next two buttons are grouped at right between the info button and the zoom slider. In the compact Library, the three buttons are placed at left.

The **thumbnails view** button switches to viewing assets as thumbnails rather than as text lines. A pop-up checklist associated with the button lets you select the readouts and controls that will appear beside thumbnails in the Browser.



The **details view** button switches to the alternative viewing mode, in which each asset appears as a text listing. The pop-up checklist with this button selects the text fields to be displayed.



The **zoom** slider lets you magnify the thumbnails to get a closer look, or pull back for a wider view. This slider is always found at the right-hand end of the footer bar.

Thumbnails and details


Each asset is displayed in the Library Browser in one of two formats, depending on the view selected.

Because the icons of thumbnails view and the text records of details view represent the same assets, they have certain features in common. For instance, the context menu for assets is the same regardless of which representation is used.

Similarly, standard media assets (video, photo and audio), along with Sound effects in the Content branch, open an appropriate media editor for corrections when double-clicked in either view. The corrections tools are also available when a media editor is invoked from the timeline, but when applied to a Library asset the corrections are carried forward into any future project that includes it. See “Correcting media files” on page 19 for more information.

Details


In **details view**, each asset is presented as one line in a list of text records. In **thumbnails view**, it appears as a thumbnail image (for visual media types) or graphic icon.


To switch the Browser to details view, click the icon on the **details view** button  at the bottom of the Library. The arrow beside the button pops up a panel listing the optional columns available to be included in the text records (one column, Caption, is always present). Check the boxes beside any of these – File size, File type, Date, Tags, Rating and Duration – you wish to be shown.

	Name	File size	File type	Tags	Rating	Duration
▼	Animals					
	Koalas	156	.jpg	mammal	★★★★★	00:00
	Shoebill	217	.jpg	bird	★★★★★	00:00
	Zorse	207	.jpg	mammal	★★★★★	00:00
▶	Garden					
▼	Scenery					
	Daybreak	1001	.jpg	dawn;sky	★★★★★	00:00
	Distant hills.jpg	4296	.jpg		★★★☆☆	00:00
	Foliage.jpg	1669	.jpg		★★★★★	00:00


In Details view, each asset is displayed as a one-line text record. A pop-up checklist beside the Details view button lets you select which columns to show.

Thumbnails

The **thumbnails view** button  to the left of the details view button selects thumbnails view, in which assets are represented in the Browser by icons rather than text. The arrow alongside the button opens a pop-up checklist on which you can choose additional data to be shown with each icon. The options are **Rating**, **Stereoscopic**, **Information**, **Correction**, **Collection**, **Tag**, **Used Media**, **Caption** and **Shortcut**.



At the bottom center of most asset icons a preview button, a standard triangular play icon enclosed in a square, is displayed when the mouse pointer is over the asset. In the compact version of the Library (as seen in the project editors and some media editors), the preview is shown on the Source tab of the embedded Player. In the Main Library, the Player occupies a floating, resizable window. See “The Library preview” on page 40 for more information.



In either version of the Library, Alt-clicking the preview button will give you a mini-preview on the asset icon itself. With video and audio media, you can control the mini-preview manually by means of a scrubber that appears below the thumbnail whenever the mouse is over the icon.

If the asset is a photo, a pop-up preview button replaces the standard play symbol. Clicking it will display the photo in the pop-up Player.

When the Browser is in thumbnails view, a slider is available to control the size of the icons. You will find the slider in the bottom right corner of the Library. The icons can also be resized with the scroll wheel when Ctrl is pressed and the mouse pointer is positioned over the Browser pane.

Locked content indicator: Some of the Disc Menus, Titles, Montages, and other creative elements in the Library are locked to indicate that you do not own a license to distribute them freely. This status is indicated by the lock indicator.



Even though locked, the content can still be handled as usual. You can edit it in the Library, and add it to a timeline. A project containing locked content can be saved, put on a disc and exported.

However, a translucent 'watermark' logo will appear on the locked content.




The locked content watermark.

To purchase and unlock the content, use one of the following options:

- In the Library, click the lock symbol on the icon.


- During export of a project with locked content, a dialog will appear prompting you to click the lock symbol.
- When editing effects in one of the media editors, click the lock symbol on the Settings panel. For more information, see “The Settings panel” on page 177.



Optional indicators and controls


The optional indicators and buttons on an asset icon in the Library Browser let you access and in some cases modify information about the asset without having to burrow deeper. Use the pop-up checklist on the thumbnails view button to determine which indicators and buttons are displayed.

Caption: The caption below the icon is the Library alias for the asset, which you can set with the Edit caption context menu command for any asset. It is not necessarily the name of the underlying asset file (which is shown in the tooltip).



Shortcut: The presence of this indicator in the extreme upper left of a thumbnail shows that the asset is a shortcut rather than an independent media file. Shortcuts, which consist of a reference to an existing media item along with a package of Corrections settings, can be created from the File menu of the media editor for any Library asset. Thereafter, they behave like ordinary assets, and are available for use in your productions.

Tag indicator: The bottommost of the three symbols at the right of the thumbnail is shown if the asset has any tags assigned to it. Hover the mouse pointer over the indicator to bring up a menu on which the existing tags for the asset are shown. As you pass the pointer over a tag name on this menu, a remove button appears. Click it to unset the tag. Click remove all at the bottom of the menu to clear all tags from the asset. The creation and application of tags is discussed in “Tags” on page 48.




Collection indicator: Just above the tag indicator, the presence of this symbol indicates that you have included the asset in one or more Collections. To see which ones, hover the mouse over the symbol. As with the tag indicator menu, a remove button is shown as you position the mouse on each Collection name; click it to remove the asset from the Collection. The remove all command removes the asset from all Collections of which it is a member.



Corrections indicator: The Library allows you to apply image and audio correction filters ‘non-destructively’ on Library media assets, meaning that the original file remains intact. The types of corrections that have been applied to an asset, and the parameters that were used to control them, are stored in the Library database. If corrections have been applied to an asset, the corrections indicator appears just above the collection indicator. Click the indicator to open the applicable media editor and update corrections settings. See “Correcting media files” on page 19 for information about applying corrections to Library assets.

Ratings: The row of stars above the top left of the icon lets you set the asset rating. If no stars are lit, the asset is said to be unrated. To set the rating of one asset or a selection of assets, either click the corresponding star on the indicator (click the first star twice to make the asset unrated again) or choose the setting on the Apply rating context submenu.



The Ratings control appears at the left above the asset thumbnail. At top right is the Info button. The Corrections indicator is also at upper right, just above the Collection indicator.

3D indicator: Assets whose content is designed for stereoscopic 3D viewing carry a 3D indicator. The indicator appears when video and

photo assets are automatically detected as stereoscopic while importing them the Library, and when an asset has been manually set as stereoscopic in corrections.




Used media indicator: A check mark is displayed to the right of the ratings indicator if the asset represented by the thumbnail is currently to be found in an open timeline within your project. The check mark is rendered in green if the asset is used in the currently visible project; otherwise it is gray. The used media indicator applies only to photo, video and audio assets, not to items like transitions and titles that come from the Content branch.



Information indicator: Clicking the information indicator opens the information panel in the pop-up Player, where you can edit the asset's rating, title, and tags as well as view all its properties. Like most of the other indicators, the information indicator can be turned on and off using the thumbnails view pop-up.



Multi-Camera indicator: Projects created in the Multi-Camera Editor have a four-pane square icon in the upper right corner of the thumbnail.



The Library preview

Most types of Library asset support previewing in the Browser. The capability is indicated by a preview button on the asset icon, and the presence of a Show preview command on its context menu. Remember too that most asset types can be previewed on the icon itself with an Alt-click on the play button.

The Library Player

Clicking the preview button in the center of the asset icon loads the item into the Library Player for viewing.



Previewing a video clip in the Library Player window. The transport controls are at the bottom, starting with a Loop button at the far left and a shuttle wheel. The third in the group of five arrow buttons starts playback. The two buttons on each side of it are for navigating from asset to asset in the Library folder.

Along the top of the Player, the current viewing position is displayed. At the bottom is a toolbar of transport controls and function buttons.

Transport controls

First among the transport controls is the loop button, which causes playback in a continuous loop from the start of the media. Next is a shuttle wheel with which you can sensitively control the speed of playback by dragging backwards and forwards on the control.

The center play button in the cluster of five arrow controls begins preview of the video or audio asset. The two buttons on either side of it are for navigating from the viewed asset to others in its folder. When previewing a photo the play button does not appear; only the navigation buttons remain.

Click the mute button to the right of the transport controls to toggle the audio associated with the clip. A volume slider appears next to the mute button when the mouse is over it.

Function buttons

Some buttons in the final group at the bottom of the Player appear only with particular asset types. A video file uses all four types, in the order shown and described here.



Scenes view: This button activates a mode in which the Browser displays a separate icon or text record for each scene in the video file. (As explained under Video scene detection, a scene in the most general sense is just any portion of a video file.)

When Scenes view is active, the neighboring Open in corrections editor button is removed, and a Split scene button takes its place. This allows you to define your own scenes instead of, or as well as, relying on the automatic scene detection feature.

For more information about video scenes in the Library see “Video scene detection” on page 53.

Open in media editor: The media file is opened for editing in the applicable media editor so that corrections settings can be adjusted.

Full-screen: The preview is shown in a special full-screen window, with its own basic set of transport controls. To close the full-screen display, click the close button in the top right corner of the window, or press **Esc**.

Info: This button switches between the Player’s information and playback views. The information view can be opened directly by

clicking the info button on a media asset icon in the Browser. Audio assets have no separate playback view; instead, full scrubbing controls are shown in the information view.

In the information view, the properties that can be edited are **Rating**, **Title**, **Tags** and **Comment**.



Here, data regarding a Library asset, a video, is displayed in the Information view of the Player. Click the highlighted Info button to return to the Playback view of the asset.

3D viewing mode switcher

When stereoscopic 3D content is being shown, the 3D viewing mode switcher will appear. On opening the Player, the default mode from the preview settings in the Control Panel is used for photos, videos, and

projects. The icon for the current mode is displayed beside a dropdown arrow used for switching modes. The available modes are:



Left eye, Right eye: The preview for stereoscopic content can be set to show only its left or right eye view. This helps keep things simple at times when a stereoscopic preview is unnecessary. Editing in these views is carried out as for a 2D movie.



Side by side: This mode displays the frames for both eyes horizontally adjacent to each other, with the left eye on the left and the right eye on right. When editing, no stereoscopic equipment is needed.



Differential: Differential mode is good for detecting the 'depth' of an image more easily, and especially for revealing areas of 'zero depth'. Differential mode show a 50% gray for areas where identical information is being presented to both eyes; a color difference is shown if the areas are not identical. If 2D material is added to a stereoscopic 3D timeline in differential mode, since the same content is shown to both eyes, the image will be a uniform gray.



Checkerboard: Checkerboard mode breaks the image up into a 16 x 9 checkerboard pattern. The 'white' squares of the checkerboard contain the view from one eye, the 'black' squares the other. Checkerboard mode provides a quick check on the ways the left and right frames differ across the whole image.



3D TV (Side by Side): Use this mode to preview stereoscopic content on a 3D TV display or with a 3D projector by connecting it as a second monitor. This obviates the need for a special graphics card or additional hardware. Configure the second display to operate in its native resolution, and to extend your desktop, not just mirror it. Make sure the input format is side- by-side.

In the Control Panel Preview settings, choose Second Monitor from the “Show external preview on” dropdown menu. Set up Studio with a 16x9 stereoscopic timeline. Finally, on the Player, click the Full Screen button. Please see “Export and Preview” on page 368, and “Timeline settings” on page 72 for help with these configurations.



Anaglyph: An Anaglyph stereoscopic preview is suitable for viewing with red-cyan stereoscopic glasses, with no additional hardware support required. Pinnacle Studio’s anaglyphic display works well even for images with a lot of red, thanks to a method very similar to the ‘optimized anaglyphs’ technique.



3D Vision: This stereoscopic mode is available with many NVidia graphics cards after the 3D Vision feature has been enabled in your NVidia configuration utility. The type of 3D display offered depends on the hardware available. At the basic ‘Discover’ level, the 3D Vision display is anaglyphic.

Choosing what to display in the Library

The Library is much more than a passive storehouse of material for your Pinnacle Studio productions.

The Library Browser has several features for decluttering your view by hiding assets that aren’t relevant to your purpose. No matter how numerous your media files, the combined power of these techniques can greatly speed your browsing.

Location tabs

Most importantly, each location tab corresponds to a different selection on the Navigator. Like web browser tabs, location tabs are

readily defined (click the ‘+’ icon at the right end of the tab list), and come in handy for keeping track of multiple things simultaneously.


Clicking within the Navigator sets the location for the current tab; conversely, clicking another tab transfers you to its saved location on the tree. Only the assets within the chosen location are displayed in the Browser. If the location has subfolders, however, their contents will be included. To keep things simple, choose a location as near the bottom of the folder hierarchy as possible.

Other controls let you restrict the display further by filtering out some of the assets in the chosen location. Each location tab maintains its own set of filters, so any change of filtering settings affects the current tab only.

Filter by rating

The Filter by rating control at the top of the Library hides all assets that don’t have at least the specified rating from one to five stars (zero stars means ‘unrated’). To use the filter, simply click on the star that represents the minimum rating you want to bother with. The default filter setting is to show all assets regardless of rating.

See “Inadvertent filtering” on page 48 for instructions on switching off all filters at once. To deactivate just the rating filter click the last selected star or double-click any star.



In this close-up, three stars are highlighted, meaning that only assets with ratings of three stars or better are on display. Here

the mouse pointer is poised to click the fifth star, which would set the rating filter to hide all but five-star assets.

Filter by stereoscopic 3D


To display only stereoscopic 3D content, click 3D at the top of the Library. To return to viewing 2D assets as well, click 3D again.

Filter by tags


Another way to narrow the field of displayed assets is with filtering by tags. Tags are keywords that you can assign to assets as you work. Once tags have been defined, you can use them in several ways to control which assets are displayed by the Browser. See “Tags” on page 48 for detailed information.

Search

At the top right of the Library is a search field that gives one further way to filter the display. As you begin entering your search term, the Browser continually updates the view to include only those assets with text that matches your search term.




Even when multiple terms are separated by spaces, partial-word as well as whole-word matches are allowed in each term. A dropdown list lets you choose whether the search will be satisfied if even a single search term matches the asset text, or if all terms must match for the asset to be accepted.



Inadvertent filtering

The various filtering methods can be combined at will. Should you leave any of the filtering types switched on when you don't need it, it's likely that some assets will be hidden that should be displayed. When an item is unexpectedly missing in the Browser, verify that filters are inactive.

The Browser guards against the possibility of inadvertent filtering by displaying a 'filter alert' that remains visible as long as any filter is in use.



A filter alert (orange bar) like the one shown here is displayed at the top of the Browser whenever filtering is in force. Click the x icon at the right-hand end to clear all filtering at once.


Tags

The Library is capable of handling a great number of asset files, sometimes far more in even a single folder than can be viewed conveniently. The Browser therefore provides a number of methods of winnowing out irrelevant assets from the display.

One method of streamlining the display of assets in the Browser is filtering by tags. A tag is simply a word or short phrase that you think would be useful as a search term. It is up to you whether you assign tags to your media, but if you do, they provide a powerful way of selecting assets to display.

Tag management and filtering

Management of tags, and filtering by tags, are handled in a panel that appears when the Tags button at the top of the Library is clicked. The panel can also be invoked by choosing **Apply tag > Create new tag** from any asset's context menu.



The tags panel, with existing tags listed alphabetically.

At the top of the tags panel is a text box for entering new tag names. The panel also lists all the tags you have defined so far, lets you delete or rename them, and lets you choose which assets you want displayed in the Library.

Creating, renaming and deleting tags

To create a new tag, click in the text box at the top of the tags panel and type in your tag. Select the media that you want to tag, make sure the Apply the tag to selected media box is checked, and click the Create new tag button beside the text box. There is no limit to the number of tags you can create. However, if you try to apply a name that isn't new, you will be notified that the name already exists, and it will not be added to the selected media.

To apply an existing tag to all currently-selected assets in the Browser, click the tag name. Selecting multiple assets to tag makes the process much more efficient than if you could tag only one item at a time.



Hovering over a tag reveals the Rename and Delete buttons. Clicking the tag itself applies it to any currently-selected assets.

Hovering the mouse over a tag reveals the controls for renaming or deleting the tag. To rename, click the Rename icon, type in the new name, and press Enter. Click the Trashcan icon to delete the tag. To delete all tags at once, use the Delete all tags button at the bottom of the panel. If you are deleting a tag that is in use, you will be given a chance to back out of the operation.

Sorting tags

In the middle of the tags panel is the Sort by dropdown, offering just two choices: 'Abc', in which the tags are sorted alphabetically, or 'Relevance', which sorts them in descending order of their popularity in the set of assets currently on display. Under the second choice, you will see the tags being resorted each time one is checked or unchecked.

Filtering with tags

Beside each tag name listed in the panel is a Filter icon that you can use to narrow the set of items displayed in the Browser. As you check and uncheck the tags, the view updates automatically.

The exact effect of your selections depends on another control, the Match dropdown just above the tags. The list provides three options.

None displays only assets that have none of your checkmarked tags. In a tagged set of animal photos, checking both the 'dog' and 'cat' tags, then selecting 'None', should hide most of the pet pictures.

Partial selects assets with any of your tags, which happens to be exactly those hidden by 'No match'. If you leave 'dog' and 'cat' checked, but switch to 'Partial', all the dogs and cats will be displayed, including the handful of photos in which both animals appear. Photos with neither tag will be hidden.

Full selects only the assets that have all your tags. Now with the same boxes checked you should see only those photos in which at least one cat and one dog appear. Notice that under 'Partial' you will see more assets displayed as you check more tags, but with 'Full' you will see fewer.

Turning off tag filtering

When tags are set to filter the contents of the Library, an orange bar at the top of the Browser lists which tags are being used. To turn off filtering by an individual tag, bring up the tag panel and uncheck the tag's Filter icon. To turn off all filtering at once, click the x button at the right hand end of the orange bar.

The art of tagging

There is no prescribed way of using tags. The best way to use them – if you do – is the way that works best for you. Consistency is important, however. The more faithful and systematic you are about assigning tags to your media, the more useful they will be.

Since the idea is to locate an asset quickly when you need it, tags should be chosen to work well as search terms. With family photos, your tags might include the names of the people in each shot. For vacation video scenes, tags naming the locations visited would probably be useful.

Videographic terms (‘two-shot’, ‘silhouette’, ‘exterior’) can also serve as good tags by making it easier to find assets that fulfill particular structural or creative requirements.

Correcting media

You can apply the media correction tools in the Video, Photo and Audio editors directly to Library assets. This kind of editing does not change the underlying files. Instead, the editing parameters are stored in the Library database and are reapplied whenever the asset is recalled. See “Chapter 4: Corrections” on page 125 for details.

An important purpose of the media correction tools is to allow you to make ‘adjustments’ on material that is not correctly identified automatically. With video footage, for example, the Adjustments group of tools allows you to override the Library-assigned aspect ratio, interlace mode and stereoscopic 3D format.

Video scene detection

Using the Library's automatic scene detection function, video footage can be split into multiple scenes either automatically or manually. Dividing raw files into scene-length portions can make some editing tasks much less cumbersome than they would be otherwise.


The time required for scene detection varies depending on the length of the clip and the detection method selected. A progress bar keeps you informed of the status.

To initiate scene detection, select one of the methods on the Detect scenes context menu command for video assets.


By date and time: This option often results in logical scene boundaries that reflect your intention while shooting. In many digital recording formats, such as DV and HDV, a discontinuity in the recorded timecode data occurs whenever the camera is restarted after being stopped. These shooting breaks are treated as scene breaks under the option.

By content: Under this option, the scene detection tool analyzes the image content of the material frame by frame, and establishes a new scene whenever there is an abrupt change in content. However, a quick pan or rapid movement across the frame may produce some unneeded breaks.


By time interval: In this variant you define the length of the scenes to be created. A small editing window opens for entering the desired value in hours, minutes, seconds and milliseconds. The scene duration has a one second minimum. Press Enter to confirm your input.



Show the scenes

To show the catalog of scenes for a particular video file, either select Show scenes from its context menu; or select the clip, then click the **Scenes view** button  that appears at the bottom right of the Library.

Scene view is a temporary viewing mode. The orange bar at the top of the Browser alerts you that scene view is active. At the right hand end of the bar is an x button you can use to terminate the mode. Clicking the Scenes view button again has the same effect.



A single video file can contain many scenes. This makes the footage easier to manipulate during editing than if it were treated as a single segment.

During editing, scene clips behave identically to other video clips.

Manually creating scenes

If you want to manually divide a video file into individual scenes, select Show scenes from the asset's context menu, or click the Scenes view button. If you haven't previously subdivided the file, it will now appear in the Browser as a single scene.

In the Library Player, navigate within the clip to each frame where a scene break should occur, then click the Split scene button. See "Function buttons" on page 42 for further information.

Removing scenes

To empty the entire list of scenes for a video file, select **Scene detection** > **Remove scenes** on the asset's context menu.

To remove individual scenes, select one or more scenes then press **Delete**.

SmartMovie

SmartMovie is a built-in project generator that allows you to create a slideshow or movie production automatically based on media you supply. The production will include animated transitions, a full music soundtrack and eye-catching image effects.



At the bottom of the Library, just click SmartMovie.

To begin, select from the Library a series of photos or video files. Your music might come from digital audio assets already in the Library, or you can cook up a soundtrack on the spot with the **ScoreFitter** tool.


That might be all it takes, though you can work on the project further with manual editing if you wish. Once you have a final product you like, it takes only a few clicks to burn it onto a disc or save it as a file for other uses, such as upload to the web.

The **SmartMovie** panel that slides up into the window from below contains three subpanels. The leftmost of these presents information about SmartMovie, and advice on how many files to include. The center subpanel is a storage area with bins for photos and other

images (top) and audio. The right subpanel contains controls for customizing the show.

Adding media

To add media to the production, drag them from the Browser into the upper bin in the storage area. Drag thumbnails within the storage area to get the order you want. Continue adding further images until you are satisfied.


To add music, drag one or more sound files to the lower bin in the storage area. Alternatively you can click the clef button  in the bottom left corner of the audio bin to create a music soundtrack in ScoreFitter.

As media are added, the total running time of the source material is displayed in the top-left corner of the bin. This is not necessarily the length of the resulting movie.

Preview, edit and export


Once your media are in place, click the **Preview** button on the footer bar below the tool. The project is created and presented in a preview window. If necessary, you can return to the settings to modify your media selections.

When you click the **Preview** button, the media you have chosen are automatically saved in a Collection named **Latest Smart Creation**. If you expect to make further use of this grouping of assets, rename the Collection to prevent it being overwritten the next time you look at a SmartMovie preview.



The analysis phase of generating a SmartMovie may take some time to complete the first time the material is analyzed. Full rendering of the project, with progress indicated by shading on the time-ruler of the Player, may introduce an additional delay before a fully-detailed preview is available.

The **Edit** button brings your production to the Movie Editor timeline for detailed editing. It's a good idea to check that the timeline video settings match your requirements for the show. The video settings button on the settings panel provides access to these. Also see "The Project Timeline" on page 64.



When the presentation is the way you want it, click **Export** to burn a disc or create a file for upload.

The storage area


The photos in the upper bin are displayed as icons, while the music and sound files in the lower bin appear as text lines giving the file name and duration of each asset. Both bins support multiple selection, drag-and-drop reordering, and a context menu with just two commands:

Delete selected: The selected media are removed from the SmartMovie production. They remain available in the Library for other uses. (Shortcut: **Delete**.)

Open editor: This command opens the Corrections tool of the Photo or Audio Editor. Any modifications you make to the media apply only within this SmartMovie production. (Shortcut: double-click.)

SmartMovie Settings

The settings on this subpanel customize the SmartMovie production.



The settings entered will be used the next time the production is generated. The video settings button lets you set up the timeline options that will apply if you take the production into the Movie Editor. The clear project button removes all media from the project and returns to default settings.

Title: Enter a caption to be used as the main title of the movie.

Clip lengths: The visual tempo of your movie increases as the clip length is shortened. Maximum uses the original length of the asset.

Pan and zoom: Checking this option enlivens your presentation with simulated camera moves.

Fit image: Check this option to enlarge material that is too small for the frame format of your project.

Video Track Volume: Set the volume of the original audio in the video segments. For a soundtrack of background music only, set to zero.



The Movie Editor is Pinnacle Studio's main editing screen for digital movie creation. The editor brings together three main components:

The **Library**, in its compact view, provides the assets available to your project.

The **Timeline** lets you organize the assets as clips within a schematic representation of your production.


The **Player** lets you preview Library assets before adding them to your project. It also lets you view – on a frame-by-frame basis if you like – how any part of the production will actually appear to your audience when you export it, whether you save it as a file, burn it to a disc, transfer it to a device, or upload it to the Internet.

Along with the Library, the timeline of your project, and the Player, the **Movie Editor** window provides a variety of tools and panels for creating and editing titles, adding effects, and other purposes.

The compact Library

The compact view of the Library, which uses the top left of the Movie Editor screen, is a core feature of the editing environment. If you switch back and forth between the Library and the Movie Editor, you will see that the same location tab is selected in both views, and that the same Library assets are on display.


To make navigation easier in the compact view of the Library, the location tabs across the top bear icons that indicate the type of content that will appear in the Browser when the tab is clicked. To display a different part of the Library, click the expand-collapse triangle beside the icon. This opens the folder tree through which you can access any Library asset.



Finding Library assets using the expandable Navigator in the compact Library.

With the compact Library and the timeline together in the same window, adding assets to your movie becomes a breeze: just drag the items you want from the Library Browser onto the timeline.

Previewing in the project editors

You can operate the Player either in single or dual preview mode. Click the **Preview Mode** button  in the upper right corner of the Player to toggle between them.




The Player in single mode. You can choose to view either 'Source' (Library) or timeline material.

Single mode conserves screen space by providing only one Player preview. The Source and Timeline tabs above the Player indicate whether Library or timeline material is being viewed, and allow you to switch from one to the other.



The player in dual mode. The side-by-side previews let you browse the Library while keeping your current movie frame in view.

In dual mode, Source (Library) material is shown in the left-hand preview, and timeline material in the right-hand preview, each with its own set of transport controls. The dual view makes it easier to locate Library assets that fit well with your movie by making both the existing and the prospective material visible simultaneously.



A portion of the Movie Editor display, with the compact view of the Library at upper left, the Player at upper right (partly visible), and at bottom the timeline.

Disc editing

If you plan ultimately to release your movie on DVD with interactive menus, you will at some point need the special features of the Disc Editor. It provides all the same timeline editing features as the Movie Editor, but also lets you create and work on the disc menus with which users will navigate your production.

Pinnacle Studio lets you smoothly transition a movie to a disc project at any time during development, so it's all right to start in the Movie Editor even if you end up targeting DVD for output instead of or as well as the other options. Please turn to Chapter 9: Disc projects for information about the special features provided for disc authoring. The

other aspects of timeline editing are covered in this and subsequent chapters.

Slideshow productions

In addition to all types of video productions – ‘movies’ – the Movie Editor (and the Disc Editor) can be used for authoring complex slideshows and presentations from still images. The same editing techniques apply in both cases.


The Project Timeline

The timeline is where you create your movie, by adding video, photo and audio assets from the Library, by editing and trimming these core media, and by enlivening them with transitions, effects, and other enhancements.

Timeline fundamentals

The timeline consists of multiple tracks – as many as you require – in a vertical stack. Tracks nearer the top of the stack are positioned towards the front when viewed, their opaque parts obscuring the tracks below.

The basic action of movie authoring is to drag an asset from the Library to a timeline track, where it is called a clip. With a little practice, you can lay out a rough edit of a movie very quickly just by adding its main media assets at their approximate timeline positions.



At the left end of the timeline are track headers with several controls per track: a lock button, the track name, and monitoring buttons for the track's video and audio. Here the current default track is 'Main'.

The track header: To the left of each track is a header area that provides access to functions such as disabling video or audio monitoring for the track.

The default track: One track is highlighted with lighter background color, and is also marked with an orange bar to the left of the track header. This is the default track. It has a special role in certain editing procedures; for instance, it is the target track for pastes. To make another track the default track, click in its header.

Your current position on the timeline corresponds to the video frame shown in the Player when it is in Timeline mode. The current position is indicated by a vertical red line, at the bottom of which is a draggable scrubber handle. Another vertical line marks the same position in the Navigator.



The toolbar

Above the tracks, the timeline toolbar provides several clusters of editing-related tools. (In the Disc Editor, the toolbar also includes tools specifically for disc authoring.)

The Navigator

The Navigator is an auxiliary navigation panel that can be revealed or hidden by clicking its icon on the Navigation tool selector near the left end of the timeline toolbar.



The full-width strip appears just below the toolbar. It gives a bird's-eye view of your whole project at a reduced scale. In the Navigator, the bars representing clips have the same colors as they do on the timeline, except that the bar representing the selected clip is drawn in orange. Clicking in the Navigator allows you to speedily access any timeline location.



A portion of the Navigator strip, showing the current position (vertical line, left) and the translucent draggable view window.

The gray rectangle that encloses a portion of the Navigator display – the view window – indicates the section of your movie currently visible on the timeline tracks.

To change which part of the movie is in view, click and drag horizontally within the view window. The timeline scrolls in parallel as you drag. Since your timeline position does not change, this may take the scrubber out of view.

Zoom


To change the zoom level of the timeline, either click and drag horizontally in the time-ruler along the bottom of the timeline, or drag the sides of the view window. The first method has the advantage that it always leaves the screen position of the playhead undisturbed, which may make it easier to orient yourself after the zoom.

To change the zoom of the Navigator itself, use the plus and minus buttons immediately to its right.

Double-clicking on the view window adjusts the zoom of both the Navigator and the timeline such that your entire movie fits within the Movie Editor window.


The Storyboard

Assembling a movie can involve juggling a large number of photos and video clips, as well as deciding where to place titles, Montages and the like. In the Storyboard, the clips on one track of your movie are presented as a sequence of icons, so you can see at a glance what is included and where. To choose which track to view in the Storyboard, use the Storyboard link button in the track header.



Any of the photos, video, audio, projects, Montages and titles in the Library can be added to your movie by dragging and dropping them onto the Storyboard. Once there they can be rearranged, or removed altogether if you change your mind.

Different types of clips are represented in the Storyboard with different colors. For example, photos and videos have a blue frame, and projects have a gray frame. As in the timeline, clips that have had effects applied appear with a magenta line on the top, and clips with corrections have a green line. A colored band connects the Storyboard icon with the position of its clip on the timeline; a gap in the timeline is reflected in a gap in the Storyboard. Once you become familiar with the color coding, it will help you quickly visualize the structure of your movie.



The Storyboard displays a sequence of icons representing the contents of one track. Effects (magenta) and corrections (green) are indicated on the top edge of the icon; the length of the clip is shown on the bottom.

The space just below the toolbar where the Storyboard appears is also used by the Navigator (and in the Disc Editor by the Menu List). Which tools is visible, if any, is controlled by the Navigation tool selector near the left end of the timeline toolbar.

Navigating in the Storyboard

To scroll to a part of the Storyboard that is not in view, hover with the mouse over the Storyboard until a hand cursor appears. Now click the left button and drag the Storyboard. If you drag the mouse quickly and release the mouse button, the Storyboard will briefly continue scrolling, thus creating a 'swiping' behavior.


Alternatively you can hover over the Storyboard and use the mouse wheel to scroll, or use the arrows at each end of the Storyboard.

Editing with the Storyboard

Although most editing takes place on the timeline tracks, the Storyboard has some editing capability. For instance, effects can be added directly to a clip on the Storyboard by dragging and dropping

the effect onto the clip. The clip's context menu offers the same set of commands here as on the timeline. Any editing that takes place on the Storyboard is immediately reflected in the timeline, and vice versa.

Adding clips: Any photo, video, audio clip, project, Montage or title can be added to your project by simply dragging it from the Library to the Storyboard. An insertion line appears to indicate where the new clip will be placed. You can select multiple clips to add them all at once.



Inserting or replacing clips: If you are inserting material between clips already on the Storyboard, drag the new clip so that it overlaps the right side of the clip that will precede it. When the insertion line appears and a space opens up, drop the new clip into the gap.

To replace a clip, drag the new one onto the clip to be replaced. The insertion line will appear, and the old clip will highlight to indicate proper placement. The new clip must be the same type as the old. A video clip cannot be replaced by a photo or audio clip, for example.

Selecting clips: To select a clip, click on its icon; an orange frame around the clip indicates selection. The timeline scrubber will jump to the beginning of the selected clip, and a connecting band of color will link the Storyboard clip with its timeline counterpart. If the timeline position of the selected clip is currently off-screen, it will be brought into view.

You can select multiple clips using the Shift and Ctrl keys according to the usual Windows conventions.

Reordering clips: To pick up a clip and move it, click on it until it is selected, and then drag it to its new location. If necessary, the Storyboard will scroll until you reach the desired position.

Resizing

The height of the timeline, along with the relative proportions of the Library and the Player, can be adjusted with the sizing grip in the form of an inverted T in the middle of the screen.


To adjust the height of individual timeline tracks, grab and adjust the separator lines between the track headers on the left. If the vertical size of all tracks exceeds the available viewing area, a scroll bar at the right will allow you to select which tracks are in view.


Set the height of the Storyboard (when it is visible) by vertically dragging the horizontal separator along the Storyboard's bottom edge. For more information, see "Navigation tool selector" on page 73.

The timeline toolbar

The toolbar above the Movie Editor timeline offers various settings, tools and functions that apply to the timeline and timeline editing. These are described in order from left to right.

Customizing the toolbar

The timeline toolbar can accommodate numerous buttons to help editing go more smoothly. One set of buttons is available for the Movie Editor and a somewhat larger set for the Disc Editor. The Customize toolbar button  at the far left of the toolbar lets you choose which subset of the available buttons you wish to display.




The Customize toolbar panel, with all available buttons selected for display.

Clicking the button brings up a panel upon which all the other toolbar buttons can be individually set as visible or hidden. The gray check marks beside the Timeline settings button and a few others indicate that these buttons are not optional and will be displayed as a matter of course. Check or uncheck the boxes for the optional buttons until the toolbar has been configured to your liking, or check the Select all box to display all of the buttons.

Some of the commands invoked by buttons also have keyboard shortcuts. These work whether the button is displayed or not. (See “Appendix D: Keyboard shortcuts” on page 447 for more information.)

Timeline settings

By default your timeline settings are copied from the first video clip you add to the timeline. If that will give the right result, you won’t have to alter them.

If you do need to change these basic image properties of your project, click the **Gear** button  to open the timeline settings panel and configure the four settings provided.

Aspect: Choose between a 4x3 and a 16x9 display.

Imaging: Choose between Regular (2D) and Stereoscopic (3D).

Size: Choose amongst the HD and SD pixel resolutions available for the given aspect ratio.

Frame rate: Choose from a selection of frame rates consistent with the other settings.

These settings can be changed at any time during the development of your movie, but you should be aware that a change of the frame rate can cause a slight shifting of clips on the timeline as they adjust to new frame boundaries.

Video material that is not in compliance with the chosen project settings will be converted automatically on being added to the timeline. If you are making a stereoscopic movie, 2D material may be used but it will still look two dimensional, as both the right eye and left eye views will be the same. 3D material can be used on a 2D timeline, but only the left eye channel will be shown.

If you want to choose a video standard for your projects explicitly, rather than relying on inheriting the format from the first clip added, open the Project settings page of the application settings. See “Project settings” on page 376.

Navigation tool selector

The space just under the toolbar can be occupied by the Navigator or the Storyboard, or by neither. (In the Disc Editor there is a third possibility – the Menu List.) The Navigation tool selector includes a dropdown that lets you select which tool you want displayed in that area.



Clicking on the selector icon toggles the visibility of the area itself.

See “The Navigator” on page 66 and “The Storyboard” on page 68 for more about these navigation tools.

Audio mixer



This button opens the enhanced audio control area with volume adjustment tools and access to the Panner, a surround panning control.

ScoreFitter



ScoreFitter is the integrated music generator of Pinnacle Studio, providing you with custom-composed, royalty-free music exactly adjusted to the duration required for your movie. See “ScoreFitter” on page 264.

Title



The Title button opens the Title Editor. If none of the many supplied titles answers your need, why not author one of your own? See “Chapter 7: The Title Editor” on page 201.

Voice-over



The voice-over tool lets you record commentary or other audio content live while viewing your movie. See “The Voice-over tool” on page 266.

Audio Ducking



Audio Ducking is used to automatically lower the volume of one track so that you can hear another track better. For more information, see “Using Audio Ducking to automatically adjust volume” on page 269.

Track Transparency



Track Transparency provides precise transparency control in the Timeline by opening a mode that makes it easy to set keyframes and adjust transparency level by keyframe.

Multi-Camera Editor



The **Multi-Camera Editor** is a workspace that lets you create professional-looking video compilations from footage of events that have been captured on different cameras, from different angles. For more information, see “Chapter 14: Multi-Camera Editing” on page 383.

Razor blade



To split one or more clips at the playhead position, click the razor blade button. No material is deleted by this operation, but each affected clip becomes two clips that can be

handled separately with respect to trimming, moving, adding effects and so on.

If there are selected clips at the playhead on any track, only those clips will be split. Both parts of those clips remain selected after the split.

If there are no selected clips at the playhead line, all clips intersected by it will be split and the right-hand parts will be selected to facilitate easy removal in case that is desired.

Locked tracks are exempt from the split operation.

Trashcan



Click the trashcan button to delete all selected items from the timeline. “Deleting clips” on page 91 for details on how other timeline clips may be affected by the deletion.

Snapshot



If, while previewing video on the timeline, you see a frame that you would like to capture as a still image, click the Snapshot button. This creates a photo of the image currently being previewed, and puts it in the Snapshot folder under Photos in the Library.

Using the Snapshot button on the timeline is a quick way to grab a frame; for more control, use the Snapshot tool in the Video Editor. Please see “Snapshot” on page 149 for more about the Snapshot tool.

Markers



The marker functions available here are identical to those provided in the media editors for video and audio. Please see “Markers” on page 146.

Instead of being attached to a particular clip, however, timeline markers are considered to belong to the video composite at the marked point. Only if there is a clip selection embracing all tracks at the marked point, and only if no track is locked, will the markers change positions during timeline editing.

Trim mode



To open a trim point, place the timeline scrubber near the cut to be trimmed and click the trim mode button. Click it again to close trim mode. Please see “Trimming” on page 94 for more details.

Dynamic length transitions



Ordinarily when a transition is added to the timeline, it is given the default length you have configured in Setup. Click this button if you would like to override the default length. When the button is highlighted, the transition durations can be set by dragging the mouse to the right or left while placing the transition onto a clip. For more about transitions, please see “Transitions” on page 114.

Magnetic snapping



Magnet mode simplifies the insertion of clips during dragging. While the mode is active, clips are ‘magnetically’ drawn to other items on the timeline when they approach within a critical distance. This makes it easy to avoid the unnecessary – though often indiscernibly small – gaps between items that are otherwise apt to arise during editing. If you want to deliberately create such a gap, however, simply turn off the mode to allow the preferred placement.

Volume keyframe editing



The volume keyframe editing button toggles keyframe-based editing of clip audio. While the button is engaged, the green volume contour on each timeline clip becomes editable. In this mode you can add control points to the contour, drag contour sections, and other operations. While the button is off, the volume keyframes are protected against modification.

Opening the Audio Mixer automatically activates the button.

Audio scrubbing



By default, the audio portion of a project can be heard only during playback in the preview. The audio scrubbing button on the timeline toolbar provides an audio preview even while just ‘scrubbing’ through your movie by dragging the timeline scrubber control.

The shuttle wheel of the Player also provides audio scrubbing.

Editing mode

The editing mode selector at the right- hand end of the timeline toolbar determines the behavior of other clips when editing changes are made. Material to the left of the edit point is never affected in timeline editing, so this applies only to clips that extend rightward from the edit point.

Three choices of editing mode are available: smart, insert and overwrite. The default is smart, in which Pinnacle Studio selects from insert, overwrite and sometimes more complex strategies in the context of each editing operation.



Smart mode is designed to maintain synchronization between timeline tracks as far as possible. In a multitrack editing situation, clips typically have vertical as well as horizontal relationships. When you have carefully placed your cuts to coincide with the beats of a music track, for example, you don't want to disrupt everything when you make additional edits.

Insert mode is always non-destructive: it moves other clips on the track out of the way before inserting new material. It will also automatically close gaps created by removing material. Only the target track is affected. Any prior synchronization with other tracks from the edit point rightwards is lost.

Insert is most useful in the early stages of a project, when you are collecting and arranging clips on the timeline. It ensures that no material will be lost, and makes it very easy to reorder clips and sequences of clips.

In the later stages, when the structure of your project is approaching its final state and you have started carefully synchronizing material on different tracks, insert mode is less helpful. The very properties that favor its use for the early stages (the 'ripple' behavior) count against it when finalizing. This is where overwrite comes into play.

Overwrite directly affects only the clips you select. Changing the length or position of a clip in overwrite mode will overwrite neighboring clips (if you lengthen) or leave gaps (if you shorten). It will never affect the synchronization between tracks.

Alternative mode

The smart editing mode works by predicting what you're trying to do and determining whether insert, overwrite or even some more complex strategy would be best to apply. You'll find it usually does what you want, but there are sure to be other times when you have something else in mind.

Many actions support both insert and overwrite, but no other possibilities. Smart mode will use sometimes one and sometimes the other, but if insert isn't what you want, overwrite usually is, and vice versa. All you need, therefore, is a method of overriding smart mode's default behavior.

To change insert to overwrite behavior, or overwrite to insert, hold down the Alt key while carrying out your edit as usual. You can press (or release) Alt as you please while setting up the edit: what counts is the state of the key at the instant the operation is finally enacted, such as when you drop dragged items onto the timeline.

The trick works in all editing modes, so it's always available when you need it. If you are not satisfied with the default behavior, just cancel or undo as needed, then try again with **Alt**.

In one timeline editing operation – that of replacing one clip by another while retaining its duration, effects and other properties – the Shift key takes on a similar role. See “Replacing a clip” on page 89 for details.

The timeline track header

In the header area of the timeline are a number of controls affecting the arrangement and organization of the timeline tracks. These are covered here, while the audio functions controlled from the timeline

header, such as track volume, are described in the topic “Audio on the timeline” on page 259.

The all tracks area above the track headers offers controls similar to those found on each track header but with global effect: they apply to all tracks simultaneously, overruling the individual settings.

Default track

The orange vertical line to the left of the track header, together with a lighter background shade, identifies the default track. It provides a destination track for certain functions, including send to and paste. Newly-created titles and ScoreFitter songs are also added on this track. For more information see “Sending to the timeline” on page 89, “Using the Clipboard” on page 106, “Chapter 7: The Title Editor” on page 201 and “ScoreFitter” on page 264.

To make another track the default track, simply click anywhere within the track header other than on a button or other control.

Locking

Click the padlock buttons to protect a track from unintended edits. The same button in the all tracks area confers this protection on the whole project.

Storyboard link

The Storyboard is an alternative representation of a timeline track. A small storyboard link button appears beneath the padlock button on all track headers when the Storyboard is open. Click the button to select a given track as the one linked to the Storyboard display.

Track name

To edit the name of a track, click the name once to access the in- place editor, or select Edit track name from the track header context menu. Confirm your edit with **Enter**, or cancel it with **Esc**.

Video and audio monitoring

The video and audio buttons in the track header control whether this track contributes its video and audio to the composite output of the project. They support the many editing situations in which it is advantageous to block the output of one or more tracks in order to simplify the preview. The same buttons in the all tracks area toggle audio and video monitoring for the entire project.

Additional track functions

The following functions are available in the track-header context menu:

New track: You can insert a new track either above or below the existing track.

Delete track: Delete a track and all clips on it.

Move track: Drag the track header up or down to a new layer position. As you drag, a bright horizontal line appears at valid placements.

Copy track: Keeping the **Ctrl** key pressed while moving a track will copy the track instead of move it.

Track size: The context menu contains four fixed track sizes (Small, Medium, Large, Very large). For custom sizing, drag the separator line between the track headers to seamlessly adjust the height.

View waveforms: Toggle the waveform view for audio clips.

Please see “Audio on the timeline” on page 259 for coverage of Timeline audio functions.


Editing Movies

The first step in any movie editing session is to bring your project into the **Movie Editor** to begin work.

To launch a new production: Choose **File > New > Movie** from the main menu. Before adding your first clip, make sure that the timeline video format will be right for the project (see below).

To edit an existing movie: Select a recent project from the **File > Recent** menu; click **File > Open** to browse for a movie project to open; or locate the movie you want to open in the **Projects** folder of the Library, and double-click the thumbnail.

If your movie has been stored as a project package, it must be unpacked before editing. Find your project in the Studio Projects group in the Library, and use the **Unpack project package** command on the thumbnail’s context menu.



A project package thumbnail in the Library, with the context menu open. After unpacking, the movie will appear on the project's timeline, ready for editing.

Alternatively, you can click **File > Open** and find the project package in Explorer by choosing **Studio Project Package (axx)** in the file extension box.

When unpacking is finished, the unpacked project is added to the Library and opened on the project editor timeline, where it can be edited as usual.

To open a Studio project: Choose **File > Import previous Pinnacle Studio projects**. Please note that some features of projects created with a previous version of Studio may not be supported in the current version.

To import a Studio for iPad project: Choose **File > Import Studio for iPad App projects**.

Timeline settings

To start editing a new project, verify that the video format settings of your project – aspect ratio, 2D or 3D, frame-size and playback speed – are as you want them. You can choose in the Project settings tab of the application settings to set the values of these properties automatically by matching the first clip added to the project. You can also set them manually. See “Project settings” on page 376 for configuring the automatic feature, and “The timeline toolbar” on page 71 for instructions on entering project settings manually.

Depending on your timeline settings, clips in some formats might not be instantly playable. Such content will automatically be rendered in an appropriate format.

Establishing tracks

With only minor exceptions, timeline tracks in Pinnacle Studio do not have specialized roles. Any clip can be placed on any track. As your projects become more complex, however, you will find it increasingly helpful to give some thought to the organization of tracks, and rename them according to their function in the movie. For information on track properties and how to edit them, please see “The timeline track header” on page 80.

Adding clips to the timeline

Most types of Library asset can be brought onto the timeline as independent clips. The types include video and audio clips, photos, graphics, ScoreFitter songs, Montage and titles. You can even add your other movie projects as container clips that work just like video clips in your project. Disc projects, however, cannot be added as container clips to a timeline, since they require a capability – user interactivity – that timeline clips don’t have.

Drag-and-drop

Drag-and-drop is the commonest and usually the most convenient method of adding material to a project. Click any asset in the Movie Editor's compact view of the Library and drag it wherever you like on the timeline.

When crossing into the timeline area during the drag and continuing to the target track, watch for the appearance of a vertical line under the mouse pointer. The line indicates where the first frame of the clip would be inserted if dropped immediately. The line is drawn in green if the drop would be valid, and red if it would not be possible to insert a clip where indicated (because the track is protected, for example).

It is possible to insert multiple clips into the timeline at the same time. Simply select the desired Library assets, then drag any one of them to the timeline. The sequence in which the clips appear on the track corresponds to their ordering in the Library (not the order in which you selected them).

Magnet mode: By default, magnet mode is switched on. This makes it easier to insert clips so that their edges meet exactly. The new clip snaps to certain positions, like the ends of clips or the positions of markers, as if drawn by a magnet once the mouse pointer gets close to the potential target.

On the other hand, don't worry about whether the first clip is right at the start of the timeline. Not every movie starts with a hard cut to the first scene!

Live editing preview

In order to eliminate the confusion created by complex editing situations, Pinnacle Studio provides a full dynamic preview of the

results of editing operations as you drag clips around on the timeline. If things seem to jump around a bit more than you're used to during timeline editing, this is the cause. Don't worry: you will quickly get used to and learn to take advantage of the extra information provided. Take it slowly at first. Watch the changes on the timeline as you hover the dragged item over various possible landing places, and complete the drop when you see the result you want.

If it turns out that drag-and-drop isn't working the way you want, either press **Esc** or move the mouse pointer out of the timeline area and release the button. Either of these abandons the drag-and-drop operation. To call back a drag-and-drop after it's complete, press **Ctrl+Z** or click the undo button.

Don't forget that you can vary many timeline editing operations with alternative mode: just press and hold **Alt** while dragging or trimming. In a one-for-one clip replacement, **Shift** is also significant.

Advanced drag-and-drop

After you have assembled an assortment of clips on a timeline track, it's only matter of time before you want to start changing things around. For instance, you might want to:

- Fill a gap with clips.
- Insert some clips before a specific clip.
- Replace a clip already on the timeline with a different one.

The smart editing mode helps you achieve these goals with ease.

Filling a gap

Smart mode makes it simple to fill a particular timeline gap with new material, for example. Rather than having to painstakingly pre-trim the

new material to the space available, you simply drag items into the gap. Any clips that are not needed for filling the gap will be dropped, and the last clip used will automatically be trimmed to the appropriate length. No clips already on the timeline are affected, so no synchronization problems can result.

Inserting clips

Suppose that your goal is to add new material to the timeline at a point where there is an existing clip. You don't want the clip already there to be overwritten, however; you just want it (and any clips to its right) to move rightwards far enough to make room for the new material.

Here again, smart editing provides a painless answer. Simply drag the new material to the start of the clip that is in the way, rather than into a gap. The clip moves aside exactly as far as necessary.

Inserting with split

If you drop an item onto the middle of an existing clip, rather than at a cut, the clip will be split. The new material is inserted at the point you specified, and is followed immediately by the displaced portion of the original clip.

In smart mode, synchronization of the target track with all other tracks is maintained by inserting in each of them a gap of length equal to the new clip. To avoid affecting the other tracks in this way, use insert instead of smart mode. Alternatively, pressing Alt as you drop the new material will cause it to overwrite a portion of the existing clip. A third approach is to lock any track that should not be modified, although this will affect the synchronization of clips on locked tracks with those on unlocked tracks.

Replacing a clip

To replace a clip, drag a single Library asset onto the clip you want to replace while holding down Shift. The replacement clip will inherit any effects and transitions that were applied to the original clip.

Corrections are not inherited, however, since they are usually meant to address the issues of a particular media item.

In smart mode, the replace operation will succeed only if the Library clip is long enough to cover the full length of the clip being replaced. In other modes a Library clip of insufficient length will be extended using over-trimming. The direction and amount of the extension is based on your mouse position as you drag. For information on over-trimming, please see “Over-trimming” on page 93.

If the Library asset is longer than needed, it will be truncated to the same length as the clip being replaced.

Sending to the timeline

In addition to dragging a clip to the timeline, you can ‘send’ it to the default track at the position of the playhead. The operation is equivalent to drag-and-drop, so smart mode is applied accordingly when deciding how other clips will be affected. The **Send to timeline** command is found on the context menu of an individual asset or multiple selection in the compact view of the Library.

Sending from the Player

There is also a second ‘send’ method that provides greater control.

If you click on a Library asset when working in the Movie Editor, the Player switches to Source mode for previewing. For trimmable media

(video and audio), the Player also provides trim calipers for cutting out a starting or ending portion of the asset.



Clicking the Send To Timeline button in the Player after trimming a Library video asset.

After previewing the asset and trimming it if required, use the send to timeline button at the bottom left of the Player. As usual, the asset is added to the project on the default track and at the playhead. A useful variation is to click anywhere within the Player screen and drag the asset onto any desired timeline track. The asset is added at the drop point rather than at the playhead.

Title Editor, ScoreFitter, voice-over

These three functions add new clips to the project's timeline, clips that are not underpinned by any Library asset. Instead, they are created from settings and other actions you take during editing.



Once your editing is complete, both titles and ScoreFitter clips will be sent to the default track on the timeline using the Send to timeline function, while voice-over clips will go to the special voice-over track instead. For details please see "Chapter 7: The Title Editor" on page 201, "ScoreFitter" on page 264 and "The Voice-over tool" on page 266.

Deleting clips

To delete one or more clips, first select them, then press **Delete**. Alternatively, click the trashcan icon  on the timeline toolbar, or choose Delete from the selection's context menu.

In smart mode, if the deletion produces a gap that spans all tracks, it is closed by shifting material to the right of the gap leftwards. This lets you avoid accidentally creating empty sections in your movie, while still ensuring that synchronization between tracks is maintained.

If the **Alt** key is held down when deleting, any gaps produced will be left unclosed.

In insert mode, gaps on the tracks from which clips are deleted will also be closed, but other tracks will be unaffected. No effort is made to preserve synchronization to the right of the deletion.

With regard to synchronization, the safest editing mode for deletion is overwrite, which will simply remove the clips and leave everything else unchanged.

Clip operations

The timeline of your project provides comprehensive support for selecting, adjusting, trimming, moving and copying clips.

Selecting

Select clips in preparation for performing editing operations upon them. A selected clip receives an orange frame in the timeline and in the Storyboard, and is displayed as solid orange in the Navigator.

To select one clip, click it with the mouse. Any previous selections are removed. For a fast multiple selection, click in an open timeline area

then drag out a selection frame that intersects the clips of interest. To select all clips with one command, press **Ctrl+A**.

To clear a selection click into any gap area of the timeline.

Multiple selection with keyboard and mouse

To create more complex multiple selections, left-click while pressing **Shift**, **Ctrl** or both together.

To select a series of clips: Click on the first and **Shift**-click on the last. The two clips together define a bounding rectangle, or selection frame, within which all clips are selected.

Toggle selection of one clip: Use **Ctrl**-click to reverse the selection state of a single clip without affecting any of the others.

Select rest of track: Press **Ctrl+Shift**-click to select all clips that start at or after the start position of the clicked clip. This function is particularly useful if you quickly want to get the rest of your timeline 'out-of-the way' for inserting new material, or to manually ripple left to close timeline gaps.

Grouping and ungrouping clips

You can select and group multiple clips so that you can move the clips together. **To group or ungroup clips:**

- 1 In the timeline, select two or more clips.
- 2 Right-click one of the selected clips and choose **Group > Group**.
To ungroup the selection, right-click a group and choose **Group > Ungroup**.

Adjusting

As you move your mouse pointer slowly over the clips on your timeline, you will notice that it changes to an arrow symbol while crossing the sides of each clip, an indication that you can click and drag to adjust the clip boundary.

Adjusting changes the length of a single clip on the timeline in overwrite mode (since insert mode would cause synchronization issues). If you drag the start of a clip to the right, a gap will be opened on the left side. If there is a clip to the immediate left of the clip being adjusted, dragging to the left overwrites it.

The adjustment pointer also appears when the mouse hovers at the ends of a gap – an empty space on a timeline track with at least one clip to its right.


It turns out that adjusting gaps in overwrite mode, as we do for clips, is not especially helpful. However, gaps do come in handy when you're editing in smart mode if you want to ripple an individual track left or right, ignoring any resulting synchronization issues. Adjusting gaps therefore occurs in insert mode.

Even if no gap is available, incidentally, you can get the same result by holding **Alt** while adjusting the sides of a clip.

Over-trimming

Over-trimming occurs when you try to extend the duration of a clip beyond the limits of its source material, a situation you typically want to avoid.

Notice that if you have over-trimmed your clip the invalid parts are shown in pink.



Overtrimmed clip: The first and last frames will be frozen in the over-trimmed sections.

Over-trimming is not a crisis situation. You do not need to take action immediately. Pinnacle Studio will simply extend the clip as specified by ‘freezing’ the first and last frames of the clip into the over-trimmed areas.

Depending on the duration of the over-trim, and the context, this simple approach may be all you need. A brief freeze-frame can even be visually effective in its own right.


The freeze-frame method will probably not give satisfactory results if it happens during a sequence involving rapid motion, however. In such exacting cases you might consider supplementing or replacing the clip, or prolonging it with the Speed function. (See “Speed” on page 108.)

Trimming

Changing the length of clips or gaps on the timeline is called ‘trimming’.

Multitrack trimming is a valuable editing skill. By trimming multiple tracks at once, you can assure that the clips coming later on the timeline maintain their relative synchronization.

Trimming clips without consideration for content later on the timeline can disrupt the synchronization of your project. Soundtracks that don’t match the action and badly-timed titles are the kinds of problem that may result.




Multiple track trimming

A rule for staying in sync

Pinnacle Studio has powerful trimming tools to allow you to perform multitrack trimming without risk. Fortunately, there is a simple rule for safeguarding synchronization even on a complex timeline: open exactly one trim point on every track. Whether the trim point is attached to a clip or a gap, and at which end, are up to you.


Opening trim points

To open a trim point on the active timeline track, position the timeline scrubber near the cut you want to trim, then click the trim mode button  on the timeline toolbar. To open one trim point on each non-empty track simultaneously, Shift-click the trim mode button.

Once in trim mode, you can open trim points with the mouse pointer at the beginning or end of a clip. Notice that the trim pointer faces left at the start of the clip and right at the end. While the trim pointer is

showing, click once at the point you want to trim. Then continue to open trim points on other tracks if required.

You can open two trim points per track by holding down the **Ctrl** key to create the second point. This feature is useful for the trim both, slip trim, and slide trim operations, all described below.



The Trim Editor in dual mode. The yellow rectangle shows the currently selected trim point at the start of a clip; the left side shows the final frame of the outgoing clip.


When a trim point is opened several things happen:

- The left or right edge of the clip is highlighted with a yellow bar, showing that it is currently selected. Trim points that are not currently selected are shown with an orange bar.
- The Trim Editor opens, with the Player in dual preview mode.

- The transport controls under the Player become trim adjustment tools.
- The preview with the currently active trim point is outlined in yellow.

The Trim Editor


In dual preview mode, the Trim Editor shows two frames from the timeline. The currently selected trim point is always shown and has a yellow rectangle around it. If the trim point is at the beginning of the clip, the first frame of the clip is shown; at the end of the clip, the last frame. You can switch the selected trim point by clicking in the other preview window, or by pressing **Tab**.




The Trim Editor in a slip trim operation. The left preview shows the currently selected trim point; the right preview shows the second trim point.


Which frame is shown in the second preview window depends on which trim mode is being used. In a slip or slide trim, the second trim point of the operation is displayed, surrounded by an orange rectangle. In other cases, the second preview window shows the frame on the other side of the cut at the selected trim point.


Above each preview window, the number of frames that have been trimmed is displayed. If you think of the original cut point position as zero, the number indicates how many frames the new position of the cut point has moved.

The Trim Editor is by default in solo mode. The clip that has the trim point is shown without the tracks above it and without any transitions applied to it. This preview mode is most suitable for determining the exact frame to trim. The default display of adjacent frames are a complete composition of all the timeline tracks. You can toggle the display behavior with the **Solo** button  in the lower right corner of the Trim Editor. When solo mode is deactivated, the preview shows trim points in their timeline context.



The Trim Editor in single preview mode.

The Trim Editor opens in dual preview mode. To switch to single preview, click the preview mode button  in the upper right corner of the preview area.

Closing trim mode: Trim mode can be closed by clicking the trim mode button .

Editing modes

The current editing mode – smart, overwrite or insert – determines how trimming will affect other clips on the timeline. Select the mode from the dropdown list at the far right of the timeline toolbar.



Insert mode: Clips to the right of a trimmed clip and on the same track will shift left or right to accommodate the new length of the clip. Synchronization with other tracks may be lost, but no clips are overwritten.

Overwrite mode: Only the clips you are trimming, and any neighboring clips they happen to overwrite, are altered in this mode. Synchronization across tracks is not affected.


Smart mode: For trimming, smart mode is equivalent to insert mode.

Trimming the beginning of a clip

Prepare to trim the beginning of a clip (the 'mark-in' point) by clicking at the left-hand edge of the clip while the trim pointer is visible. With a trim point thus established, you can add or remove frames from the beginning of the clip.

To trim on the clip, drag the trim point to the left or right.

To trim on the Player, use the trim buttons to trim one or ten frames either forwards or backwards. Click the loop play button for a looping preview of the trim region.



The position of the playhead relative to the trim point helps distinguish the in-point of a clip (left) from the out-point of the previous clip (right).

Trimming the end of the clip

To trim the end of the clip (or ‘mark-out’ point), open a trim point by clicking at the right-hand edge of a clip when the mouse pointer changes to a rightward-pointing arrow. Now you can add or remove frames from the end of your clip.


Once again you can trim directly on the clip by dragging the trim point, or on the Player while it remains in trim mode.

Trimming gaps

The project’s timeline lets you trim not just the clips upon it but also the gaps between them. Trimming gaps might not sound terribly useful at first, but is in fact handy. For instance, the easiest way to insert or delete space on a single timeline track is to trim the right-hand edge of a gap. All clips to the right of the gap are shifted as a block when this is done.

Also, when you need to open a trim point on each track in order to maintain synchronization while trimming, you may often choose to trim the duration of a gap rather than that of a clip. (Remember the rule: one trim point on every track is required for keeping in sync.)

Trimming a gap, whether at the start or the end, is accomplished in exactly the same way described above for trimming a clip.




Two gaps and an audio out point have been selected for trimming. Because one trip point has been created on each track, the entire production stays in sync when trimmed.

Trim both

In this operation, two adjacent clips (or a clip and an adjacent gap) are trimmed simultaneously. Any frames added to the left-hand item are taken away from the one on the right, and vice versa, as long as space and material are available. All you are moving is the cut-point where the items meet. One application for this technique is adjusting visual cuts to the beat of a music soundtrack.

To start, click at the end of the left-hand clip to open the first trim point, then **Ctrl-click** at the beginning of the right-hand clip to open the second.

When positioned over the adjacent trim points you just opened, the mouse pointer should be a horizontal two-headed arrow. Drag left or right to move the clip boundary, or use the Player in trim mode.




Trim both: Adjacent out and in trim points have been selected. Dragging the trim points affects the timing of the hand-off from the outgoing clip to the incoming one, but does not disrupt the timeline.

Slip trim

To change the starting frame of a clip within the source material, but leave its duration unchanged, open one trim point at the start of a clip, and another at the end of either the same clip or one later on its timeline track.


Drag either trim point horizontally or use the Player trim controls to reposition the clip within its source.



Slide trim: With the in and out trim-points of a clip selected, dragging the clip changes its in and out points relative to the original material, but doesn't affect its start time or duration on the timeline.

Slide trim

A slide trim is an extended version of the trim both technique described above. In this case you open trim-points at the end of one clip and the beginning of another later on the timeline. Instead of sliding a single clip boundary along the timeline, as in trim both, you are sliding two that move together. All clips between the two trim points are repositioned earlier or later on the timeline.



Slide trim: An out-point has been opened for trimming on the first clip, and an in-point on the third. Dragging either point moves the center clip – or multiple clips, if more are present – along the track while other clips remain stationary.

Both slip trimming and slide trimming can be useful for synchronizing clip contents to material on other tracks.

Monitoring trim points

When you are trimming with multiple trim points, it is helpful to switch the preview from one trim location to another to make sure that each is properly set. Selecting a trim point for monitoring makes it the source for audio and video during preview.

Monitoring is enabled for a trim point when it is created. When multiple trim points are created in succession, you can fine tune each one as you go. To select an existing trim point for monitoring, Ctrl- click it. While trim mode is active, use **Tab** or **Shift+Tab** to cycle through the open points.

After using **Ctrl**-click to monitor a trim point, trimming can be controlled with the Left and Right arrow keys. Trim one frame using the keys unshifted; add the **Shift** key to trim in 10-frame steps.

Moving and copying

To move a selection of one or more clips, place the mouse pointer on any selected clip and watch for it to change to a hand symbol. When it does, start dragging the clip to the desired position.

Move can be thought of as a two-step process. First, the selection is deleted from the current timeline, according to the rules of the current edit mode. Second, the selection is moved to the desired end position, where it is inserted in a left-to-right fashion per track. The relative position of all selected clips on all tracks is retained.

Moving a 'sparse selection' (a selection in which some clips per track are selected while others in the same region are not) is possible, but may be confusing unless executed in overwrite mode. Moving either single clips or a complete timeline cross-section is more straightforward and should be preferred when possible.

Holding down the **Alt** key while moving clips allows you to toggle between insert and overwrite modes. Standard smart operation is the same as insert, since the most frequent use of horizontal moves is to reorder the playback sequence.

Copying clips: Holding down the Ctrl key while moving a selection of clips will copy the clips instead of moving them.

Using the Clipboard

Although drag-and-drop operations provide somewhat greater power when dealing with clips, the timeline does support the standard Clipboard operations cut, copy and paste, with the usual shortcut keys. The Clipboard also provides the only method for moving and copying transitions and effects between clips.

From the Library

After selecting one or more clips in the Library, select **Copy** from the selection's context menu or press **Ctrl+C** to put the selection on the application's Clipboard. (Cut, the other usual command for adding to the Clipboard, is not available in the Library.)

On the timeline, position the playhead at the point where the paste operation should begin, and select the desired track by clicking in its header.

Now press **Ctrl+V** to insert the clips from the Clipboard onto the given track, starting at the playhead.

If you select **Paste** from the timeline's context menu rather than pressing **Ctrl+V**, the clips will be pasted at the mouse pointer position on the default track, not at the playhead.

You can repeat the paste operation with the same set of clips as often as desired.

From the timeline

Select one or more clips on the timeline, then click either **Copy** or **Cut** on the selection's context menu, or press **Ctrl+C** (copy) or **Ctrl+X** (cut). Both commands add the clips to the Clipboard; Cut removes the original clips from the project, while Copy leaves them in place.

Paste the Clipboard contents onto the timeline as described above. The clips paste onto the same tracks as they originally occupied; and with the same horizontal spacing. Unlike drag-and-drop, the Clipboard does not support moving clips between tracks.

Effects on the Clipboard

Clips to which effects have been added have a magenta line along the upper edge. Right-click on the clip, or right-click the line, to access the **Effect** context menu, which provides **Cut all** and **Copy all** commands for transferring or sharing a set of effects between clips. Select one or more target clips, then press **Ctrl+V** or click **Paste** on the timeline context menu.

The effects stack will be pasted to all selected clips. The target clips retain any effects they may already have had. The pasted effects stack will be placed on top of the existing effects.


Transitions on the Clipboard

Right-click in the transition area in the upper corner at the start or end of a clip to access the Transition context menu. Select **Cut** or **Copy** to put the transition on the Clipboard.

As with effects, transitions can be pasted to one or more target clips, but any existing transition of the type (start or end) being pasted will be overwritten. The paste fails if the duration of the transition on the Clipboard is longer than the target clip.

Speed

The Speed Control window is launched by selecting **Speed > Add** or **Speed > Edit** in the context menu of a timeline video or audio clip. You can adjust the settings to produce any degree of slow motion or fast motion over a wide range. A clip to which Speed Control has been applied is marked by a broken yellow line.



The Speed Control window

The actual playback speed of your project always remains the same. It is set once and for all by the frames per second rate in your project settings. To achieve slow motion, new frames are interpolated between the original ones; for fast motion, some source frames are suppressed.

The options provided on the dialog are divided into several groups.

Constant

Select the clip playback speed as a value from 10 to 500 percent relative to the original material. Anything under 100 percent is slow motion.

Anchor: When Constant is selected, the clip is anchored to the timeline by a specified frame during trimming operations. You can choose the first or last frame of the clip, or the frame indicated by the current

position of the playhead, to serve as the anchor. This can be useful for coordinating action between the speed-affected clip and material such as background music on other tracks.

Stretch

Under this option, the first and last frames of the clip as currently trimmed will remain locked when the clip is trimmed on the timeline. Shortening the clip, instead of trimming material from the end, speeds it up just enough so that it finishes at the same frame as before. Lengthening the clip by trimming its end rightwards slows it down rather than exposing any trimmed material.

Video

Reverse reverses the direction of playback without affecting the speed. Synchronous audio, if any, is suppressed with this option, since it is generally undesirable to play sound backwards.

Smooth motion: This option applies a special transition technique to achieve maximum fluidity of movement from frame to frame.

Audio

Hold pitch: This option maintains the original pitch of the recorded audio even when it is played back accelerated or slowed. The function becomes less effective the more the speed is changed. Beyond certain limits, it is switched off completely.

Movies within movies

All the movie projects that you create in Pinnacle Studio appear as assets in the Projects branch of the Library. But the purpose of Library

assets is to serve as the ingredients of movies. What will happen if you try to drag Movie Project A onto the timeline of Movie Project B?

The answer is simple enough: As with most types of assets, Project A becomes a single clip on Project B's timeline. From the standpoint of timeline editing, it behaves just like any of your other video assets. You can trim it, move it around, apply effects and transitions, and so on. (The same is not true of disc projects. These cannot be used as clips in another project.)


Nevertheless, a copy of the internal structure of Project A remains intact inside this container clip, along with all of the project's clips, effects, titles and other components. What's more, if you double-click the container clip or select Edit movie from its context menu, a subsidiary Movie Editor opens in a new window to let you work on the 'sub-movie'. Any modifications you make affect only the copy of the project inside the container clip, not the original.

The length of the container clip on the timeline of the main project is not tied to the length of the sub-movie on its own timeline. Extending or shortening the sub-movie in the nested editor does not alter the length of the container clip in the parent movie. You need to manually trim the container clip if you want it to match the duration of the sub-movie.


Picture-in-Picture (PIP)


You can easily create a picture-in-picture (PIP) effect with media that you have added to the Timeline. PIP lets you play a video in one area of the screen while the main video plays in the background. You can also use PIP with images. You can adjust the PIP media by resizing, rotating, or cropping it, and then positioning it where you want it to display on the background.

To create a picture-in-picture (PIP) effect

- 1 In the **Edit** workspace, ensure that the clip you want to use for **PIP** is added to the Timeline in the track above your background video.
- 2 Select the clip, and choose one of the following **PIP** options below the Player preview window:
 - **Scale mode**  — lets you resize the selected clip by dragging the sizing nodes that appear in the preview window. To rotate the clip, drag the rotation handle (node that extends above the sizing rectangle).




- **Crop mode**  — lets you crop the selected clip by dragging the orange cropping handles that appear along the edges of the clip




Track Transparency

You can use the **Track Transparency** mode to precisely control the transparency of a track. Keyframes let you vary track transparency to achieve the effect you want. For example, you can adjust the transparency of a track to create a superimposed effect or to create a fade in and fade out effect.




You can use keyframes in Track Transparency mode to vary the transparency from 100% opacity (top) to 0% opacity (bottom).


To use Track Transparency mode

- 1 In the **Edit** workspace, select a track in the Timeline, and click the **Track Transparency** button .
- 2 Do one of the following
 - To adjust the transparency for the entire track, drag the **Transparency** slider to set the value you want.



- To vary the transparency throughout the track, click the **Keyframing** button  to open the keyframing mode, and click the yellow transparency line to add as many keyframe nodes as you need. Drag the nodes down to increase transparency.

If you want to delete keyframes, right-click a keyframe node and choose the corresponding command.

To exit keyframing mode, click the close button  in the upper-right corner of the Timeline.

- 3 Click the **Track Transparency** button to exit Track Transparency mode.

Transitions

A transition is a specialized animated effect for easing – or emphasizing – the passage from one clip to the next. Fades, wipes and dissolves are common types of transition. Others are more exotic, and many employ sophisticated 3D geometry to calculate the animated sequences.



Creating a default fade-in transition by 'folding back' a clip's upper left corner.

Two transitions can be assigned to any clip, one at each end. A clip newly created on the timeline has neither. When a new clip starts, it

does so with a hard cut to the first frame. When it ends, it switches to the next clip (or black) with equal abruptness.


Pinnacle Studio offers a wide variety of transitions for softening, dressing up or dramatizing the change from one clip to another.

Creating a transition

The most straightforward method of creating a transition is to click in the top left corner of the clip on the timeline and 'fold back' the corner. This creates a dissolve from the previous clip, if there is one, or a fade-in if there is not. The wider you make the fold, the longer it will take the transition to complete. Folding back the top right corner of the clip results in either a dissolve to the following clip or a fade-out.


More elaborate transitions can be added to the timeline from their section of the Library (under **Content**). When you find one you want, drag it onto one end or the other of a timeline clip. The length of the transition will be determined by the default duration defined in the Pinnacle Studio Control Panel Project settings (one second by default). If the clip already has a transition at the chosen end, the new one replaces it. See "Project settings" on page 376 for details.

If you are trying to add the transition to a clip which is shorter than the default transition length, the transition will not be applied. One way to avoid this problem is by making sure the dynamic length transitions button on the timeline toolbar is active. While it is, you can control the length of a new transition by dragging to the left or right as you place it on the clip. You will see the corner of the clip fold back as you drag. If the time-ruler is zoomed out enough, you will see the duration of the transition numerically displayed; clicking in this readout lets you edit it directly.



A transition dragged to a project's timeline.

Another way to apply a transition uses the Send to timeline context menu command for assets in the Movie Editor's compact Library view, or the Send-to timeline button in the Player when in Source mode. The transition is added to the clip on the default track at the cut nearest the playhead.



Transitions can be added at the start or end of any clip.

The context menu of a clip on the timeline lets you add a transition by choosing either **In transition > Add** or **Out transition > Add**.

Finally, transitions can also be created in the applicable media editor, which opens when you double-click the timeline clip. The media editor provides editing controls similar to those for other types of special effect. Please see "Working with transitions" on page 171 for full information.

A fade-out transition is applied in ripple (or insert) mode, which creates an overlap by shifting the right-hand clip and all its neighbors somewhat to the left. This behavior saves the left-hand clip from having to be extended rightwards to create the transition, which might

produce over-trimming. However, shifting the rightward clips causes a break in the synchronization with other tracks that may have to be worked around.

A fade-in transition is added in overwrite fashion. No synchronization issue will result, but over-trimming may be produced in the left-hand clip.

To invert the fade-in and fade-out behaviors, press the **Alt** key during dragging and trimming.

To apply a transition to multiple selected clips, hold down the **Shift** key while dragging a transition from the Library onto one of the selected clips. The position at which you drop the transition on that clip determines whether it will be placed at the beginning of each selected clip, or the end. The transition will not be applied to any clips that are shorter than the transition's duration.

When the Dynamic length transition button is activated, the duration you drag out for the transition on the target clip is used for all the transitions created.

To keep tracks synchronized when inserting transitions in the out position, use this multiple-apply feature to add the same transition once on each track. Since each track will be affected in the same way, they will all remain synchronized.

When a fade-in follows a fade-out, the result is termed a 'fade through black'. The left-hand clip fades all the way out, then the right-hand clip fades all the way in. It is not necessary to leave a one-frame gap between the clips.

Rippling transitions

The ripple transition command is especially useful for creating a quick slideshow from a set of still images, or a video pictorial from a set of short clips. Such a presentation is more interesting if you connect each pair of clips with a transition, which can be done quickly and easily by using ripple transition.

Begin with a set of clips on the timeline, then add a transition of the desired type to one of the clips. Select all the clips in the set, bring up the context menu on the clip with the transition, and choose the ripple transition command. This will apply the original transition to all the selected clips. If the original clip had both an In transition and an Out transition, you can choose either one to be rippled.

Any of the selected clips that already have a transition in place, or that are too short for the new transition, will not be altered.

Removing multiple transitions

To remove transitions from several clips at once, select the clips, right-click on one of them, and use the remove transitions command in the context menu. All the transitions, both in and out will be removed from the selected clips.

Replacing a transition

Select the transition you want and simply drag it onto an existing transition. This replaces the transition animation while retaining the original type (in or out) and duration.

Alternatively, you can choose **Replace by** on either the transition's context menu or the clip's context menu. You will be offered a selection of transitions to use.

Adjusting transitions

The durations of transitions can be adjusted just like those of clips. Notice the adjustment pointer when the mouse is positioned near the vertical side of the transition rectangle. Use this to change the duration of your transition.

As usual, fade-out transitions use insert mode during adjustment, whereas fade-in is done in overwrite mode. Hold down **Alt** while adjusting to invert this behavior.

You can adjust a transition so that its duration is zero, effectively deleting it. Alternatively, use **Transition > Remove** on the transition's context menu. Once again, ripple mode is used for fade-out, and overwrite for fade-in, with the **Alt** key available to reverse the default.

To set the duration of a transition numerically, click the duration field that appears when the mouse pointer is above the transition rectangle. (Zoom the timeline in to enlarge the screen width of the transition 'fold' if the field does not appear.) Clicking the field activates in-place editing, allowing you to enter a duration via the keyboard.


Transition context menu

Find in Library: This command opens the Library Browser at the folder containing the transition.

Edit: This command invokes a pop-up window, the basic transition editor, where the transition duration can be set.

If the transition is one that offers a custom editor for configuring special properties, the Edit button in the basic transition editor provides access.


A **Reverse** check box is available with some transitions for reversing the transition animation.



Basic transition editor

Copy: This command puts the transition on the Clipboard, together with its type (fade-in, fade-out) and its duration. These properties will be retained by the transition when pasted. It is therefore not possible to paste a fade-in as a fade-out or vice versa.

To paste the transition to a particular clip, select **Paste** on its context menu. To paste it to all selected clips, select **Paste** from the context menu of an empty timeline area or any selected clip; or press **Ctrl+V**.



The Replace By submenu on the context menu for a transition pops up a convenient palette of standard, recently-used and

5-star transitions. This pop-up is also seen when transitions are added or replaced via a clip's context menu.

Ripple: This command appears if more than one clip is selected. For more information, see “Rippling transitions” on page 118.

Remove: This command deletes a transition. Fade-in transitions are removed without further ado. Removing a fade-out transition causes clips to the right to be rippled rightwards by the duration of the transition. This can cause loss of synchronization with other tracks.

Replace by: A selection of transitions is offered: two standard dissolves, the six transitions most recently used, and all transitions with a 5-star rating.

Clip effects

Clip effects (also called filters or video effects) operate on one clip at a time. Effects are of many kinds, and vary widely in purpose. With keyframing, effect parameters can be arbitrarily varied throughout the clip.

To apply a specific effect to a clip, either locate it in the Effects section of the Library and drag it to the clip you want to enhance, or double-click the clip and select the effect from those offered under the Effects tab of the clip's media editor.

Multiple effects can be applied to a clip using either or both of these methods. By default, multiple effects are processed for playback in the order they were added.

On the timeline, the upper border of any clip to which an effect has been applied is drawn in magenta. This clip effect indicator has its own context menu, which provides the Clipboard commands for cutting

and copying effects between clips. See “Using the Clipboard” on page 106 for more information.

Double-clicking any clip opens it in its media editor, where effects may be added, removed or configured. Please see “Chapter 5: Effects” on page 151 for detailed information.

Clip context menus

Right-clicking a clip opens a context menu with commands appropriate to the item type. A video clip has a different menu than a title clip, for example. Some commands are shared between most or all types however. Differences of applicability are noted in the following descriptions.

Edit movie: Available only for movie (container) clips, this command opens the container in its own movie editor. The nested editor offers the same functions and areas as the primary one.

Edit title: For titles only, this opens the **Title Editor**. (See “Chapter 7: The Title Editor” on page 201.)

Edit music: This command is for editing ScoreFitter clips. (See “ScoreFitter” on page 264.)

Edit Montage: Edit a Montage clip in the Montage Editor. (See “Using the Montage Editor” on page 196.)

Open effects editor: Opens the media editor for the clip, whatever its type, with the **Effects** tab selected. Montage, title and container clips are treated in the same manner as ordinary video clips.

Speed: This command opens the Speed Control dialog, where you can apply fast and slow motion effects to selected clips. This option is not available for containers. See “Speed” on page 108.

Scaling: The first two options affect the treatment of clips that are not in conformance with the current timeline format when brought into the project. See “The timeline toolbar” on page 71.

- Fit displays the image at its correct aspect ratio, and scaled as large as possible without cropping. Unused parts of the frame are treated as transparent.
- Fill also maintains the aspect ratio of the image, but scales it such that there are no unused parts of the screen. Portions of the image will be cropped if the aspect ratios do not match.

To further fine-tune the scaling behavior of a clip, try pan-and-zoom.

- **Keep alpha, Remove alpha, Generate alpha:** These commands apply to content with an alpha channel (specifying transparency pixel by pixel). Such alpha information can conflict with Pinnacle Studio effects. The command isn’t available for pure audio clips.

Active streams: This command is available for disabling individual streams in clips containing both video and audio. It is typically used as an easy way to discard unneeded camera audio.

Adjust duration: Enter a duration numerically in the pop-up window. All selected clips will be trimmed to the duration requested by adjusting their out points.

Detach audio: In clips with both video and audio, this command detaches the audio stream into a separate clip on a separate track, allowing advanced editing operations like L-cuts.

Find in Library: This command opens the Library Browser at the folder containing the asset that is the source of the video, photo or audio clip.

Cut, Copy, Paste: Move or copy a selection of clips using Clipboard commands instead of drag-and-drop.

Group: You can group multiple clips so that you can move the clips together. When you no longer need the group or want to create a different grouping, you can **Ungroup** the clips.

In Transition, Out Transition: These provide access to a set of operations for managing transitions, including **Add, Replace, Edit, Copy,** and **Remove**. For more information, see “Transitions” on page 114.


Delete: Delete the selected clip or clips.

Display information: Display properties of the clip and underlying media files in textual form.



Pinnacle Studio provides media editors for each of the three main media types: video, photos (and other images), and audio. The usual way to access one of these editors is by double-clicking either a media asset in the Library or a media clip on your project's timeline.

All three editors provide two main families of tools, called Corrections and Effects. These are presented as tabs at the top of the editor window. (The Photo Editor has a third tab, for the Pan-and- zoom tool.)



The four groups under the Corrections family in the Video Editor. When an editor is invoked from the Library, the Effects tab does not appear.

The tools in the Corrections family are designed to fix imperfections in the video, photos and other media that you use in your projects. The defects addressed by the tools are those most frequently encountered in recorded media. You can straighten a photo with a tilted horizon, improve the clarity of a muffled music track, or correct the 'white balance' of a video scene, to name just a few possibilities.

The application of Corrections does not modify your media files themselves. Instead, the parameters you set are stored either in the Library database (associated with a particular asset) or in a project


(associated with a particular clip).

Correcting Library assets

Just one tool-family tab – Corrections – is available for use when you bring Library assets into a media editor. The **Effects** tab, and **Pan-and-zoom** for photos, appear only when the editor was opened to work on a timeline clip.

Using corrected assets: When you apply Corrections to a Library asset, the correction settings ride along with the asset when you add it to a project. All future projects get the benefit of the correction. You can make further corrections on the timeline, if you want, but they will have no effect on the Library asset.

Save alternative corrections: Corrected Library assets can optionally be saved (with **File > Make new shortcut**) as separate assets. This lets you have two (or more) variations of a particular asset under different captions, each incorporating a different set of corrections.



Working with the Enhance group of corrections in the Video Editor.

Removing corrections: The context menu for Library assets that have corrections includes a Revert to original command for restoring the uncorrected state.

Corrections under direct export: If you choose to export Library media directly, rather than build a project on the movie or disc timelines, the correction settings are applied to the output.

Correcting timeline clips

When a clip from the Movie Editor or the Disc Editor timeline is opened in one of the media editors, you can use the Corrections family of tools to change it in any way you like without affecting either Library assets or other clips. Such changes to the clip become part of your project.

If you want to remove corrections from a clip on the timeline, select the context menu command **Open Effects Editor**, then switch to the Corrections tool. The settings panels indicate with highlighting which settings have been modified. Use this to locate and reset the corrections.

For details on using a particular media editor, please see “Correcting photos” on page 136; “Correcting video” on page 143; or “Correcting audio” on page 150.


Media editing overview

The media editors can be opened to access the available tools in a number of ways from both the Library and a project’s timeline.

To open from the Library:

- Do one of the following:
 - Double-click the icon or text record of a video, photo or audio asset.
 - Select the **Open in corrections** command from the asset’s context menu.

To open from the Library Player:

- After clicking the play button on a Library item to open the Library Player, click the gear wheel icon  at bottom right.

To open from the timeline:

- Do one of the following:
 - Double-click the clip in the timeline.
 - Select the **Open effects editor** command from the clip’s context menu

- Use the context menu **Effect > Edit** on the colored strip that appears along the upper edge of clips to which any effects have been applied.

To close the media editor window:

- Do one of the following:
 - Click the **Cancel** button; leaving the clip unchanged.
 - Click the close (X) button in the upper right corner. If you have made changes, you will be given a chance to save them.
 - Click the **OK** button, confirming your changes.

Previewing

The central panel in each of the media editors is either a visual preview of media showing the result of applying corrections and effects, or an audio visualization.

When video media with an integral soundtrack is being edited, both the Audio Editor and the Video Editor are available via tabs at the top left of the window.



Previewing stereoscopic 3D images

Stereoscopic 3D images are edited in the same way as 2D images, but there is an additional Preview window, which is shown only for 3D images. The window shows the edited picture in stereoscopic 3D, whereas the working area is shown in 2D. The Preview window also has a switcher for changing the stereoscopic 3D preview mode.

Title bar

File and Edit menus: If you invoked the media editor from the Library, the File menu offers the ability to save a new copy (or 'Shortcut') of the currently-loaded asset. A Shortcut is a special type of asset that has its own parameters and settings but applies them to a media file that is already associated with an existing asset. This lets you have multiple versions of the same asset without having the overhead of storing a separate media file for each one. Shortcuts are stored to the Library as the original name plus a sequence number.

The **Edit** menu offers five standard editing commands: **Undo**, **Redo**, **Cut**, **Copy**, and **Paste**.

Undo/Redo: As seen throughout Studio, the graphical undo and redo buttons at the upper left of the media editor window step forward and back through your editing history.




The Navigator

The Navigator strip at the bottom of all media editor windows gives you an opportunity to load other Library items or other timeline clips.




When called from the Library, the Navigator at the bottom of the media editor accesses other assets displayed in the Library Browser.

The current item is highlighted. You can switch to editing a different item by clicking a different element in the Navigator, using the arrows at right and left to assist scrolling if required. When you do so, any changes made to the currently-loaded item are automatically saved, as though you had clicked the **OK** button.

You can hide the Navigator by clicking its button  at the bottom of the media editor window.

View options

Sharing the bottom toolbar with the Navigator button is a series of view-related buttons.



The Solo button gives access to a menu of options for previewing underlying tracks in the media editor as well as the current one, and for including the clip's transitions, if any, in the preview.



Solo: This button is available only if the media editor is selected from the timeline. While it is highlighted, the current clip in the Navigator is shown in isolation when previewed, without taking into account the effect of any clips either above or below it on the timeline. While the button is not highlighted, all timeline tracks can contribute to the preview.



Before-and-after view: This button appears for photo media only. For details, see "Before-and-after" on page 135.



Full screen: When active, this button scales the preview image to the size of the current monitor and removes other tools from view. To exit the full screen mode, press **Esc**, or use the close (X) button at the top right of the window. The full-screen view includes its own small overlay panel of transport controls.



Preview zoom options: Fit window adjusts the size of the preview so that the height and width of the image do not exceed the available space even when all tools are open. Set to actual size displays the image at the original size of the source.


Zoom: The scroll bar at the far right of the toolbar provides continuous scaling of the preview image.

Moving the preview in the window

The preview image can be dragged with the mouse anywhere within the working area. This is useful for scanning the image while it is zoomed in. The wave visualization in the Audio Editor is not draggable, however.

Info and captions

The Info button at the bottom left of any media editor opens a window with information about the current file.



The Caption field, which is available only when you invoke the media editor from the Library, allows you to rename the current asset.

The settings panel


When you select an effect or tool that has adjustable settings, a panel appears in the upper-right section of the window. Named presets are

available in the Select preset dropdown menu near the top of the panel; these provide prepared combinations of settings that you can adapt or use directly.

Setting numeric values: Numeric settings fields have a gray slider bar within a darker gray field. Click once within this field to put it into numeric input mode, where you can type the desired value for the parameter. Alternatively, drag the slider bar to the left or right using the mouse. Double-clicking restores the default value.

Comparing parameter sets: A highlighted (orange) dot appears to the right of the field when the value of a setting is changed from the default. Thereafter, clicking the dot toggles between the default and the most recent non-default values. The dot to the right of the effect or correction name toggles between the default and custom values of all parameters.

Linked parameters: Some parameters are configured to change in lock-step. The presence of a lock symbol indicates this. Click the symbol to toggle the link.



The settings panel lets you adjust the available settings for a correction or effect. Here the settings for the Enhance group of photo corrections are displayed.

Photo editing tools

These tools are located on the bottom bar of the Photo Editor. They are available for photos and other graphic images loaded from the Library only. Images opened from the timeline do not have access to them.

For information about opening the Photo Editor to access the correction tools, along with general functions of the media editors, please see “Media editing overview” on page 128.

Image rotation

Two rotary arrow icons are located to the left below the image preview. Click the icons to rotate a Library image either clockwise or counterclockwise in 90-degree increments.



Rotation is only available in the Photo Editor when a photo is opened from the Library. Clips opened from a project’s timeline can be rotated using the 2D Editor effect.

Before-and-after

When editing photos you can directly compare the original against the corrected version. The three available views can be accessed by the arrow at the right of the button.



Split image: The lower half of the preview displays the corrections. You can adjust the vertical position of the dividing line by dragging the center portion of the line up or down with the mouse. You can also divide the image diagonally by grabbing the line on either side and rotating.

Full image side-by-side: The right image shows the corrections.

Full image above and below: The lower image shows the corrections.

Correcting photos

The five corrections available within the Photo Editor are **Enhance**, **Adjustments**, **Crop**, **Straighten** and **Red-Eye**. The first two are controlled by means of panels that open in the upper-right corner of the Photo Editor; the other three are controlled interactively on the image preview.

Enhance (photos)

This correction opens the Image Correction CPU panel of tools for fixing problems to do with color and illumination. The tools can also be used creatively to achieve custom looks or stylistic effects that extend, not just repair, the original material. They are presented in the groups described below.

Automatics

The two special tools in this group adjust the image automatically after analyzing its brightness spectrum. You can change the tool settings further by hand to customize the adjustment if required.

White Balance: When you check the White Balance box, a color temperature setting for the image is computed, and the Temperature bias slider is displayed. Use the slider to customize the setting interactively as you preview.

Levels: Checking this box activates an automatic illumination adjustment, and opens a set of three controls. The first is Optimization, a dropdown list that lets you set the overall behavior of the tool by choosing either “Contrast” (optimization of contrast only) or “Full” (general lighting optimization).

The **Brightness** and **Vibrance** sliders can take on values ranging from –10 to +10. A zero setting represents no change to the automatically-chosen value. Brightness provides a general boost or cut in brightness that is applied equally across the whole image. Vibrance, which is designed primarily for use with images of people, is similar to a saturation control, but minimizes the unnatural appearance characteristic of oversaturated skin tones.

Fundamentals

This group of controls allows you to adjust the general lighting properties of your image.

Brightness: This control provides an overall brightness adjustment that impacts the light and dark areas of the image equally. For finer control in brightness editing, use the Selective Brightness tool instead (see below).

Contrast: This control increases the difference between the light and dark areas of an image. Boosting the contrast may enliven a dull photograph, although at the risk of losing definition in areas that are already very bright or very dark.

Temperature: The **color temperature** control changes the color composition of an image to make it seem ‘warmer’ or ‘cooler’. Indoor lighting such as a tungsten bulb or candlelight is perceived as warm, while daylight, especially shade, is perceived as cold. Using the temperature control primarily changes the yellow and blue values in an image, with little effect on green and magenta.

Saturation: This control regulates the color intensity of an image. Increasing the value pumps up the colors, making them more vivid, or even lurid. Decreasing the value drains the image of color until at zero only shades of gray remain. For finer control of saturation, use **Selective**

Saturation instead. A related adjustment is **Vibrance**, which is often preferred in portraits because it preserves skin tones.

Clarity: Increasing **Clarity** boosts contrast in the midtones, tending to sharpen edges in an image. A small increase in **Clarity** often improves a picture's overall appearance.

Haze: Increasing **Haze** lightens the image by compressing its dynamic range upwards. What was originally black becomes gray; lighter tones are also brightened, but to a diminishing degree. This produces a simultaneous lightening and softening effect. The opposite result, darkening and detailing, is achieved by setting negative values of **Haze**. This drops the brightness floor of the image, sharpening the highlights and midtones by a downward expansion of the dynamic range.

White balance

If the white or gray areas of an image bear a slight tint or color cast, the controls in this group can help restore a natural appearance.

Gray-scale picker: Activate the picker then click in a nominally white or gray area of the image, where no coloration ought to be present. The image white balance will be automatically adjusted so as to remove the unwanted tint.

Color circle: Browse the color field by moving the control point away from the center until a natural image appearance is achieved.

Selective brightness

To enable you to edit particular brightness zones in an image without impacting others, five separate brightness controls are provided:

Blacks: This slider affects only the darkest areas in the image. For best results, leave editing both Blacks and Whites until last.

Fill light: Increasing this slider may produce better detail in shadowy (but not black) areas of a full-contrast photograph.

MidRange: The zone impacted by this slider includes the entire medium range of illumination.

Highlights: This slider affects the bright locations in the image. It can be used to mute areas overexposed due to flashes, reflections or brilliant sunshine.

Whites: This slider impacts the parts of the image that are considered 'white'. Edit Whites and Blacks last.

Selective saturation

Whereas the standard **Saturation** correction increases color saturation equally across the entire spectrum, **Selective saturation** allows for individually boosting or suppressing the primary and secondary colors. For example, if blue appears to be too strong, it can be turned down while other colors retain their intensity.

Adjustments

During import, Studio automatically detects certain parameters, but a variety of factors can lead to the occasional incorrect identification. Adjustments allows any of these basic image properties to be changed, if needed.

Alpha

Your photo may have an Alpha channel, an 8-bit grayscale image plane that defines the transparency level of each pixel in your photo. If you wish to remove the alpha channel, choose the Ignore Alpha option.

Interlacing

If the Interlacing options on the image were misidentified on import, use this dropdown to impose the correct setting.

Stereoscopic 3D

If the format of a 3D image file was wrongly identified on import, set the correct stereoscopic layout with this dropdown list.

Crop

Use this tool to emphasize a specific section in an image, or to remove undesired components.



Cropping an image.

Bounding box (cropping frame): After you select the cropping tool, a resizable frame is placed over the image. Drag the sides and corners of the frame to crop the image, or drag the center of the bounding box after cropping to adjust its position.

Aspect ratio: The **Aspect ratio** dropdown on the control bar can be used to ensure that the crop rectangle maintains a desired standard

proportion while being resized. Standard (4:3) and wide (16:9) frame aspect ratios are supported.

Preview: This function displays the cropped image without the surrounding material. Press **Esc** or click the image to return to the editing view.

Clear, Cancel and Apply: **Clear** returns the bounding box to its original dimensions; **Cancel** closes without saving any edits made; **Apply** saves the changed image without exiting the editor.

Straighten

This correction enables you to straighten an image in which elements that should be exactly horizontal or vertical are visibly tilted. Unless you have cropped the image, it dynamically resizes as you rotate to keep the corners from being visibly cut off. With a cropped image, no resizing takes place as long as there is sufficient excess material to fill in the empty corners.



Ready to straighten an image (with crosshairs).

Several functions pertaining to Straighten are provided on the toolbar below the preview.

Guide line options: The two buttons at the far left of the toolbar set the mode for the lines that are superimposed on the preview as a guide to straightening. Selecting either button deselects the other. The

Crosshairs (leftmost) button adds a pair of crossed lines that can be dragged with the mouse to serve as a reference for true vertical and horizontal alignment anywhere in the image. The **Grid** button produces a fixed, repeating grid pattern over the entire image.

Set angle: To set the degree of rotation you can either use the slider on the toolbar below the image, or click and hold the left mouse button while dragging over the image. Rotations up to 20 degrees in either direction are supported.

Clear, Cancel and Apply: **Clear** sets the image back to its original state; **Cancel** closes without saving any edits made; **Apply** saves the changed image without exiting the editor.

Red-eye

This tool corrects the red-eye effect that often occurs in flash photography when the subject's gaze is towards the camera. Mark the area around both red eyes with the mouse. Extreme precision shouldn't be necessary, but you can experiment with changing the area slightly if you are dissatisfied with the correction.

Clear, Cancel and Apply: **Clear** sets the image back to its original state; **Cancel** closes without saving any edits made; **Apply** saves the changed image without exiting the editor.

Correcting video

Like the other media editors, the Video Editor has a central preview display, and an area at right for correction and effect settings. If the video includes an audio track, floating panels for audio management will also appear. These are positioned originally at upper left, but you can drag them to new docking positions on either side of the window.

For information about opening the Video Editor to access the correction tools, along with general functions of the media editors, please see “Media editing overview” on page 128.

For details on the controls available when the Audio tab is selected, please see “The Audio Editor” on page 245.


Video / audio switch

If an audio track is present, a tab is provided at the top left of the screen for switching to the Audio Editor.



Waveform display

This floating panel shows a section of the audio volume graph over the span of the video. The region of the waveform that is shown is centered on the current playback position.



When you switch to the Audio Editor, you will see a video preview panel at the same screen location.

Video tools

These tools are located on the toolbar below the Video Editor preview. Just below the tools is a time-ruler with a scrubber for moving through the video. At the left are the marker controls. For more information, see “Markers” on page 146.

The remaining controls are devoted to previewing and trimming the media. Many of the controls are also to be found in the Audio Editor. Unless otherwise noted, the descriptions here apply to both. (Please see “The Audio Editor” on page 245, for further information.)

Stereoscopic 3D: The icon and dropdown arrow to the left of the loop play button let you choose amongst several modes for viewing 3D material. The icon has a different appearance for each mode.

If your video is in 3D, but the dropdown arrow does not appear, go to **Adjustments** to choose the correct 3D setting. See “Adjustments” on page 139 for more information.



Shuttle: The shuttle wheel provides smooth, bidirectional control over a range of speeds when browsing video or audio. Both media types can be viewed at a reduced speed. Shortcuts **J** (reverse), **K** (pause), **L** (forward), and each of these in combination with the **Shift** key (for slow play), allow easy scrubbing and shuttling from the keyboard also.

Transport controls: The oval arrow icon activates looping playback. The remaining controls are (from left to right): **Jump backward**, **Frame backward**, **Play**, **Frame forward**, **Jump forward**.

Audio monitor: The **loudspeaker** icon sets the system playback volume but does not affect the recorded audio level. Click once on the loudspeaker to mute, or click on the slider to the right of the icon to adjust monitoring volume. To set the playback level of the clip itself, use the channel mixer. See “Channel mixer” on page 247.

Time-code displays: The left field indicates the duration of the media as trimmed. The right field displays the current play position. For a Library asset, the play position is relative to the start of the media. For a timeline clip, the play position within the project is given.

Setting the position numerically: Click the right-hand time-code field for the position and enter a position in ‘hh:mm:ss.xxx’ format. When you press **Enter**, the playhead jumps to the specified location if that position is present on the clip. Press **Esc** to undo the change and exit the input mode.

Asset trimming: For Library assets, the orange calipers at either end of the time-ruler let you choose your own entry and exit points for playback. Doing so establishes the clip endpoints when the asset is used in a project.

Ruler: The time-ruler displays a scale whose gradations depend on the current zoom factor. If you click anywhere on this ruler, the playhead (see below) jumps to this position.


Playhead: This red line, with its handle the scrubber, is synchronized with the image currently displayed (for video) and also with the red line shown on the waveform display (for audio). You can position it

arbitrarily by clicking and dragging the scrubber, or by dragging within the waveform.

Scroll bar and zoom: By dragging the double lines at the end of the scroll bar to the right and left, you change the zoom level of the display. When the bar becomes smaller, the scroll bar can be moved back and forth as a whole, enabling you to zoom into an audio clip's waveform or scrub with extra precision. Double-click the scroll bar to return it to the full width of the clip. You can also zoom in and out by dragging left and right on the ruler area.

Markers

Markers are visual reference points that can be set on the time-ruler to identify changes of scene or other editing cues.



The Marker Panel

Setting and moving markers: Position the playhead at the location where the marker should be set. Click the toggle marker button at the left of the toolbar, or press **M**. Only one marker may be set per frame.

To move a marker: Ctrl-click and drag left or right.

Deleting the marker: Click the marker to move the playhead to that position, then either press **M** or click the toggle marker button.

You can also delete markers using the list on the Marker Panel, which opens when you double-click a marker on the ruler, or click the down-arrow next to the toggle marker button.

The Marker Panel shows the markers that have been set within the media currently on view, in ascending order, with color code, name, and position. Most of the available commands apply to the currently-selected marker. The exception is the Delete all markers button at the bottom of the panel.

Clicking a marker in the list selects it for editing. At the same time, the playhead jumps to the marker position.

Edit name: The name field lets you enter a distinctive name for the currently-selected marker if desired. The left and right arrows beside the name provide another way of moving through the marker list.

Position: Edit the position of a marker directly here as time-code.

Marker color: Set the color of the current marker (and markers subsequently created), by clicking one of the available color buttons.

Trashcan: The trashcan icon on each row of the marker list lets you delete individual markers.

Video corrections

The correction tools within the Video Editor are **Enhance**, **Adjustments**, **Snapshot** and **Stabilize**.

Enhance (videos)

The Enhance corrections for video are the same as those for photos and other images. See “Enhance (photos)” on page 136.

Adjustments

During import, Studio automatically detects certain parameters, but a variety of factors can lead to the occasional incorrect identification. Adjustments allows any of these basic image properties to be changed, if needed.

Alpha

If your video has an Alpha channel and you wish to remove it, choose the **Ignore Alpha** option.

Aspect ratio

If the aspect ratio of a video asset was not recognized correctly on import, or if the frame proportions must be manually changed for another reason, use this dropdown menu to select the desired setting. The adjustment does not change the amount of the image on display. Instead, visible area is stretched (or shrunk) independently in width and height to make it fit the desired frame boundaries.

Interlacing

If the Interlacing options on the image were misidentified on import, use this dropdown to impose the correct setting.


Stereoscopic 3D

If the format of a 3D image file was wrongly identified on import, set the correct stereoscopic layout with this dropdown list.

Snapshot

The snapshot tool enables you to acquire a single frame from a video, crop it, and save it as a photo. Its controls are similar to those for the Crop correction for photos.

Selection Frame and Aspect Ratio: The frame for selecting an image cutout can be resized by grabbing its sides and corners, or dragged within the preview by grabbing it in the center.



Correcting the stereoscopic 3D properties of a Library asset.

Preview: Preview shows the selected cropped image without the snapshot tools. Press **Esc** or click once on the image to view the tools again.

Apply: This command exports the cropped image as a JPEG file, and switches off the snapshot editing mode in the preview. Snapshots are stored in the library under **My Pictures > Images**. Locate the new item by returning to the Library and clicking the special find added item button that is displayed temporarily on the Library footer bar. The new media file itself is created in:

[Registered User] \My Documents \My Pictures \Images

Clear and Cancel: **Clear** sets the selection frame back to its original setting (whole image), while **Cancel** exits snapshot editing without creating any new media.

Stabilize

Similar to the electronic stabilization in digital camcorders, this tool minimizes shake and jitter caused by inadvertent camera movement. When using this effect, the outer areas of the image are removed and a varying portion of the image is enlarged up to 20 percent in order to fill the frame.

After Stabilize has been applied, the video must be rendered to preview accurately. Instead of using the **Play** control on the toolbar, click the **Render & Play** button on the **Stabilize** panel to preview.

Correcting audio

The Audio Editor can be used both for audio-only media such as .wav files and for video with an included ('original' or 'synchronous') audio track.

For information about opening the Audio Editor to access the correction tools, along with general functions of the media editors, please see "Media editing overview" on page 128.

For an overview of audio-related information, please see "Chapter 8: Sound and music" on page 243. For coverage of the Audio Editor, see "The Audio Editor" on page 245. Please see "Audio corrections" on page 251 for descriptions of the individual correction tools.



Pinnacle Studio has three media editors, one each for video, photos and audio. Their general operation is described in “Media editing overview” on page 128.

One of the main functions of the three media editors is to provide applicable add-on tools in three families – Transitions, Corrections and Effects – along with the specialized Pan-and-zoom function.



Working with visual effects in the Photo Editor. At top, several groups of effects are listed. In the center a preview shows the image with effects applied; parameters to customize them are available at right. At bottom, transport controls and a timeline support animating the effects with keyframing.

Only the Corrections family is provided when the media editors are opened from the Library. When they are opened from the timeline of a movie or disc project, however, the full range of tools becomes available. This chapter provides a general introduction to effects editing, then focuses on the visual effects in the Photo and Video editors, as well as Pan-and-zoom. Audio corrections and effects are described in “Chapter 8: Sound and music” on page 243.

Corrections vs. effects

The tools in the Corrections family are meant primarily for remedying the imperfections that are often encountered in actual media files – poor white balance in photos, wind noise in soundtracks, and so on. Unlike effects, the correction tools can be applied to Library assets, not just to clips on the timeline. When corrections have been applied in the Library, their benefit is passed on to any project that uses the improved assets. Please see “Chapter 4: Corrections” on page 125 for details about Corrections and how to use them.

About effects


‘Effects’ is an umbrella term taking in a wide range of software tools for manipulating your media. It includes presentational tools like **2D Editor**, **360 Video**, **Motion Tracking**, atmospheric transformations like **Old film**, and some theatrical touches like **Fractal fire** that you may find are too much fun not to use.

Like Corrections, you can apply effects to clips on the timeline of a project. Just double-click the clip to open the appropriate media editor with its **Effects** tab already open.

Effect compositions

Achieving a desired look, behavior or sound can take a combination of several effects, applied in a particular order. Both video and audio effects may be needed. For each effect, parameters must be adjusted to get the results you are looking for. Once you have found the right combination, the set of effects can be saved as a special type of asset—an effect composition. With effect compositions, even complex manipulations of your media can be readily achieved.

Effect compositions can be created in the media editor (using the save button at the top of the **Effects** setting panel) or on the timeline (using the **Effect > Save As FX Composition** context menu command).



Along with the seven other groups under the Effects family, a group named My FX Compositions (right) appears as soon as any compositions are added to the Library.

They are stored in the Effects section of the Library under **My FX Compositions** and can be used in the same way as ordinary effects.

Pan-and-zoom

The Photo Editor provides a third tab, **Pan-and-zoom**, to go along with **Corrections** and **Effects**. The pan-and-zoom tool is a versatile accessory with which you can add motion and drama to any high-resolution photograph, among other uses. See “Pan-and-zoom” on page 173 for details.

Effects in the media editors

Like other resources for your project, effects are stored in the Library. You'll find them in the Navigator under **Effects** in the **Content** branch. As with other types of Library resource, you can use all the usual features – Collections, ratings, tags, and so on – to help you organize the many effects available.

You can apply an effect from the Library directly to a clip on the timeline of a project with drag-and-drop. Clips to which an effect has been added are indicated by a brightly-colored upper border.

When you double-click a timeline clip, its media editor opens automatically with the **Effects** tab preselected. Up to eight groups of effects are available, depending on which version of Pinnacle Studio you are working with. Click the name of the group to see the effects it contains.



The Camera group of Effects is open in the Photo Editor. The mouse pointer is positioned over the thumbnail for the Invert effect (left side), causing it to be automatically demonstrated on the preview.

The thumbnail icons for the effects in the currently-selected group are shown in a full-width tray at the top of the work area. With visual effects, as your mouse pointer hovers over the effect icons, the preview shows how the clip you are editing would appear if each effect were applied. When you have made your choice, click the effect's thumbnail to apply it.

Customizing an effect

Once you have applied an effect to a clip, by either of the methods mentioned above, you can return to the media editor at any time to manipulate the effect's settings. Double-click the clip on the timeline,

or select **Open effects editor** if you wish to customize the effect. See “The Settings panel” on page 160 for further information.


To save your modifications and return to the timeline, click **OK**. To cancel modifications and return to the timeline press **Cancel**.

Creating Effect Compositions


The set of effects used by a clip, and their settings, can be saved as an Effect Composition by clicking the Save button in the upper right corner of the Settings panel. Enter a name for your Composition in the dialog box that appears, and clear the checkmark for any effect you don’t want included. See “The Settings panel” on page 160 for further information.

Switching to a new clip

Even without leaving a media editor you can switch from one timeline clip to another by means of the Navigator, a schematic representation of your project that is optionally shown in the space just above the footer bar of the editor window.

To toggle the visibility of the Navigator, click the **compass rose** icon  at the bottom right of the window.

Each clip in your project is represented in the Navigator by a colored bar. The layout of the bars on a horizontal time axis with vertically-arranged tracks exactly matches the timeline. The bar representing the clip now being edited is highlighted in orange.




Here the mouse pointer is poised over the compass-rose button to turn off the Navigator panel immediately above, where project clips are represented by horizontal bars.

If you click on one of the other bars, any changes you've made to the current clip will be automatically saved; the clip corresponding to the bar you clicked on will then be loaded. If the new clip is of a different media type, the appropriate editor will switch in automatically.

Solo mode

Sometimes while editing an effect, it is useful to see the other timeline layers – those above and below the current layer containing the clip you are working on. On other occasions, you can simplify a complex editing situation by turning off the other track.

Solo mode is started or stopped with the **Solo** button  and its accompanying dropdown menu in the lower right area of the media editor. Three configurations are possible:

- **Off:** When soloing is on, clicking once on the button will turn it off. All layers from the timeline are then used in the preview. Sometimes the current layer may be obscured by a layer above it on the timeline.
- **Show media and the tracks below:** Under this option, the current layer and all layers below it are previewed, but the clips on layers above the current layer are hidden.

- **Show media only:** This option allows only the layer you are currently working on to appear in the preview.


Previewing effects

In the Content section of the Library you can preview a sample of each effect either directly on the icons in thumbnails view, or in the separate Player window. These samples will give you some idea about the look of the effect, but can often do no more than hint at the possibilities that will be available once customization, keyframing, and combination with other effects are considered.

As mentioned earlier, you can see the effect previewed on your own media – without actually applying it – by hovering over the effect icon in a timeline clip’s media editor. Then to apply the effect, simply click on the thumbnail.

Effects on the timeline

To check whether a timeline clip has had any effects applied to it, look for a magenta stripe along the clip’s upper edge. Both this clip effect indicator and the clip itself provide useful context menu commands for effect management.



The clip effect indicator is a contrasting stripe along the top edge of any clip to which an effect has been applied.

A clip with corrections displays a green stripe along the upper edge, but there are no relevant context menu commands.

Clip context menu

Open effects editor: This opens the media editor appropriate for the clip, with the **Effects** tab preselected. There you can apply new effects to the clip, or modify existing ones.

Paste: Effects can be cut or copied to the Clipboard using commands on the **Effect** submenu. The **Paste** command lets you apply the effect to one or more other clips.

Clip context menu: Effect

The context menu of any clip to which at least one effect has been applied will include an **Effect** submenu that provides a number of ways of manipulating the effects that are present. The clip effect indicator has a reduced context menu containing only the **Effect** submenu.

Cut all, Copy all: With these functions, effects assigned to a clip can be cut or copied to the Clipboard, from which they can be pasted to one or more other clips as described above.

Delete all, Delete: Remove all the effects at once from a clip with **Delete all**, or delete a particular effect by selecting it on the **Delete** submenu.

Save as FX Composition: Save the effects applied to the clip, or a subset of them, as an Effect Composition. In the dialog that opens, click on the **FX Composition Name** box and enter the caption that will identify the Composition in the Library and elsewhere. Uncheck any of the applied effects that you don't want included in the Composition.

Edit: From this submenu of applied effects choose one to open for configuration in the clip's media editor.

Find in Library: Open to the page of the Library Browser that contains a particular effect, with its thumbnail already selected.

Real-time vs. rendered

Adding effects to a clip increases the amount of computation Pinnacle Studio must do to give you a smooth preview. Depending on your computer's hardware, the 'rendering' process for a clip can easily require more computing time than can be managed in real time; that is, while the preview is actually running.

In this circumstance, some 'pre-rendering' will be required before the clip can preview acceptably. Rendering progress is shown on the time-ruler by yellow ('to be rendered') and green ('now being rendered') shading. The shading is removed as soon as pre-rendering is complete.

Options for rendering are set in the **Preview** page of the Pinnacle Studio Control Panel. (See "Export and Preview" on page 368).

If effects are not playing back smoothly, try increasing the **Optimization Threshold** value. This will increase the amount of pre-rendering time while improving the preview quality. If rendering is taking too long, on the other hand, the **Optimization Threshold** value can be decreased, or rendering can be turned off by altogether by setting it to zero. Other factors that affect playback and rendering time are the format, size and frame rate selected for the project. These can be changed in Timeline settings. Please see "Timeline settings" on page 72.

The Settings panel

The Settings panel provides a list of the effects that have been assigned to the current clip (whose name is given at the top). Click an effect name in the list to select it; this causes its settings to be displayed for inspection and editing in the parameters area below the list. Most effects also offer a dropdown list of preset parameter combinations.

Though a clip might have transitions, Corrections and Pan-and-zoom in addition to effects, the Settings panel on the **Effects** tab does not list these. Turn to the other tabs to access the settings information for their tools.

When a clip has multiple effects, they are applied in the order they were added, which is the reverse of the order in which they are listed (new effects are added at the top of the list, not the bottom). To change the order, drag the effect header up or down in the list.

The right-hand end of the effect header has four buttons for operations related to that effect. From left to right they are:


Diamond: Toggle keyframing for parameters of the effect. See “Working with keyframes” on page 163.

Expand All Settings: All the groups of settings for the effect can be expanded for editing or closed with one click.

Trashcan: Remove the effect from the clip.

Dot: Toggle the effect on and off. You can switch the effect off for comparison purposes without deleting it and losing your settings.

Drag handle: Use either this zone or the name area for dragging the effect up or down in the effect list when the clip uses multiple effects. As mentioned above, effects are applied in bottom-up order. In some cases, changing the order can dramatically affect the cumulative result.



The Settings panel: Here, two effects (Water drop, 2D Editor Advanced) have been applied to the current clip. A preset for the 2D Editor Advanced effect is being selected (highlighted box).

Modifying parameters

Parameters are organized into named groups of related controls. Click the expand/collapse triangle on the group header to open the group and access its parameters, or close it and conserve screen space. The currently selected element is highlighted with an orange frame. To move forward to the next element, use **Tab**; use **Shift+Tab** to move backward.

Numeric parameters are controlled by horizontal sliders, with a gray bar that you can drag horizontally to change the value. For more

precise control, use the Left or Right arrow. Double-click the bar to reset a particular parameter to its default value.

Most effects furnish a dropdown list of preset parameter combinations for fast selection of variants. Once a preset has been selected, you can customize it by editing the parameters if desired.

When you are finished with a media editor, and are ready to return to the timeline, click **OK** at the bottom of the window to approve your changes, or **Cancel** to abandon them.

Working with keyframes

The normal use of some types of effect is to transform the source material in a uniform way from beginning to end. Atmospheric effects like **Old film**, and effects that change only the coloration of the clip, are among those in this category. Their parameters are generally set once and for all at the start of the clip. This is the static use of an effect.

Other effects, such as **Water drop**, depend on a sense of motion. They are likely to be effective only when their parameters are allowed to vary throughout the clip. The easiest way to this animated use of an effect is to use a preset that has animation built in, like most of those for **Water drop**. In this kind of keyframe animation, one or more parameters of the effect has a different value at the end of the clip than it did at the beginning. On playback, the parameters are updated after every frame to move smoothly from the start value to the end value.

Keyframing isn't limited to just the start and end frames of a clip. Keyframes can be defined with particular values of effect parameters at any point in the clip to produce effect animations of arbitrary complexity. If, for example, you would like an image to reduce to half-size by the middle of the clip and return to full size by the end, you would need to add at least a third keyframe.

Basic keyframing

Here's an outline of how to use keyframing to program the changes in an effect parameter during the playback of a clip.

- 1 Double-click a clip on the timeline to load it into its media editor.
- 2 Add an effect, then activate keyframing by clicking the diamond icon on the effect header if it is not already highlighted.
- 3 A keyframe line appears below the time-ruler. Any keyframes that have been added to the clip for the current effect to date are displayed as gray diamonds.

A keyframe is added automatically at the beginning of the clip. This keyframe cannot be moved or deleted. If the effect and preset combination you chose is animated rather than static, there will be a keyframe generated at the end as well. You can delete or move the end keyframe; if you do so, all parameter values are sustained from the last remaining keyframe to the end of the clip.

- 4 Set the playhead to the position in the clip at which you want to establish a change of some effect parameter such as size, position or transparency.
- 5 Modify the parameter using the **Settings** panel. If keyframe editing is turned on, a new keyframe will be automatically added at the playhead position. If a keyframe already exists, the parameter data it represents will be modified.

Keyframe operations

For each effect, only one keyframe can be attached to any frame of the clip. The keyframe defines the instantaneous value of every clip parameter for the frame where it is set.

Add or delete a keyframe: To add a keyframe at the playhead position without adjusting any parameters, or to delete an existing keyframe at

the position, click the toggle keyframe button on the far left of the transport toolbar.



Move a keyframe: To move a keyframe along the keyframe line (and thus along the timeline), click it and drag.

Jump to a keyframe: Use the arrow buttons to the left and right of the keyframe button, or click directly on the keyframe in the keyframe line, to move the playhead to that position. The keyframe should highlight, indicating that it is now the target keyframe for deletion or parameter editing.

Keyframing multiple parameters

Sometimes it is desired to keyframe multiple parameters of the same effect on separate schedules.

For example, suppose you wish to change the Size parameter of an effect smoothly over the whole clip, while changing another, let us say Rotation, at several points along the way. Here are two ways of approaching this:

Method 1: Set up the Size keyframes first, then add the more numerous Rotation frames where needed. At each of these, a correct Size value will be calculated.

Method 2: Add the effect twice: once to adjust the keyframes for overall changes (Size, in the example), then another time to make multiple keyframe changes (Rotation).

Video and photo effects

The effects provided for use with video also work with photos, and vice versa. Only Pinnacle Studio-supplied effects are described here. For third-party plug-in effects, please consult the manufacturers' documentation.

Blur: Adding **Blur** to your video produces a result similar to shooting out of focus. The **Blur** effect allows you to add separate intensities of horizontal and vertical blurring over the whole frame or any rectangular region within it. You can easily blur out only a selected portion of the image, such as a person's face, an effect familiar from TV news coverage.

Emboss: This specialized effect simulates the look of an embossed or bas-relief sculpture. The strength of the effect is controlled by the **Amount** slider.

Old film: Old movies have a number of traits that are usually considered undesirable: grainy images caused by early photographic development processes, spots and streaks from dust and lint adhering to the film, and intermittent vertical lines where the film has been scratched during projection. The effect lets you simulate these 'blemishes' to give your footage an antique look.

Soften: The **Soften** effect applies a gentle blurring to your video. This can be helpful for anything from adding a romantic haze to minimizing wrinkles. A slider controls the strength of the effect.

Bevel crystal: This effect simulates viewing the video through a pane of irregular polygons arranged into a mosaic. Sliders let you control the average dimensions of the polygonal 'tiles' in the image and the width of the dark edging between neighboring tiles from zero (no edging) to the maximum value.

2D Editor: Use this effect to enlarge the image and set which portion of it will be displayed, or to shrink the image and optionally add a border and shadow.

Earthquake: The Pinnacle Studio **Earthquake** effect jiggles the video frame to simulate a seismic event, whose severity you control with sliders for speed and intensity.

Lens flare: This effect simulates the flaring seen when direct bright light overexposes an area of a film or video image. You can set the orientation, size and glow-type of the main light.

Magnify: This effect lets you apply a virtual magnifying lens to a selected portion of the video frame. You can position the lens in three dimensions, moving it horizontally and vertically within the frame, and nearer to or further from the image.

Motion blur: This effect simulates the blurring that results when a camera is moved rapidly during exposure. Both the angle and the amount of blurring can be set.

Water drop: This effect simulates the impact of a drop falling onto the surface of water, producing expanding, concentric ripples.

Water wave: This effect adds distortion to simulate a series of ocean waves passing across the video frame as the clip progresses. Parameters allow you to adjust the number, spacing, direction and depth of the waves.

Black and white: This effect subtracts some or all of the color information from the source video, with results ranging from partly desaturated (the 'Faded' preset) to fully monochrome ('Black and white'). The **Amount** slider controls the strength of the effect.

Color correction: The four sliders in the parameters panel for this effect control the coloration of the current clip in terms of:

- **Brightness:** The intensity of light.
- **Contrast:** The range of light and dark values.
- **Hue:** The location of light on the spectrum.
- **Saturation:** The quantity of pure color, from gray to fully saturated.

Color map: This effect colorizes an image using a pair of blend ramps, or color maps. Stylize your footage with bold color treatments, add duotone and tritone style colorization, or create striking editorial transitions. The effect can be used for anything from fine control of monochrome images to psychedelic color transformations.

Invert: Despite its name, the Invert effect doesn't turn the display upside-down. Rather than the image itself, it is the color values in the image that are inverted: each pixel is redrawn in its complementary light intensity and/or color, producing a readily recognizable but recolored image.

This effect uses the YCrCb color model, which has one channel for luminance (brightness information) and two channels for chrominance (color information). The YCrCb model is often used in digital video applications.

Lighting: The Lighting tool enables correction and enhancement of existing video that was shot with poor or insufficient lighting. It is particularly suitable for fixing backlit outdoor sequences in which the subject's features are in shadow.

Posterize: This Pinnacle Studio effect lets you control the number of colors used to render each frame of the clip, all the way from the full original palette down to two colors (black and white) as you drag the

Amount slider from left to right. Regions of similar color are coalesced into larger flat areas as the palette shrinks.

RGB color balance: **RGB Color Balance** serves a dual role in PPinnacle Studio. On the one hand, you can use it to correct video that suffers from unwanted coloration. On the other, it allows you to apply a color bias to achieve a particular effect. For example, a night scene can often be heightened by adding blue and slightly reducing overall brightness. You can even make video shot in daylight look like a night scene.

Sepia: This Pinnacle Studio effect imparts the appearance of antique photography to the clip by rendering it in sepia tones rather than full color. The strength of the effect is controlled by the **Amount** slider.

White balance: Most video cameras have a ‘white balance’ option for automatically adjusting their color response to ambient lighting conditions. If this option is switched off or not fully effective, the coloration of the video image will suffer.


The **White balance** effect corrects the problem by allowing you to specify which color should be taken as ‘white’ in this image. The adjustment needed to make that reference color white is then applied to every pixel of the image. If the reference white is well chosen, this can make the coloration seem more natural.

Effects and stereoscopic 3D

Some video and photo effects have features designed for 3D media. For instance, some of the provided effects offer a stereoscopic mode that is activated by a check box in the effect parameters. Meanwhile, the effects in the **Stereoscopic** group itself let you modify the 3D properties of your material. The group includes:

The S3D Depth Control: This effect allows you to adjust the parallax of stereoscopic footage. By default, the effect is presented in Standard mode, in which a single **Depth** slider lets you control the amount of divergence between the left and right frames, whether to correct or match source material, or as a special effect.

The advanced mode offers separate **Shift** and **Zoom** control groups, each containing a **Horizontal** and a **Vertical** slider. The **Shift** sliders let you control the divergence between the left and right frames, while the **Zoom** sliders control their magnification. Both properties can be controlled independently in the horizontal and vertical dimensions, but by default the **Zoom** aspect ratio is locked. Click the lock icon to adjust the horizontal and vertical zoom independently.



The Shift settings in the S3D Depth Control effect allow you to change the relative position of the left and right eyes horizontally and vertically.


S3D Eye Selector: The **Eye Selector** effect is presented in two variations; one for left eye, and the other for right; it is used for uniting left and right eye video streams on a 3D timeline.

A pair of clips at the same timeline index, one for left eye and the other for right eye, can be combined to produce stereoscopic output by applying the eye selector effect to the upper clip.

The effect can also be employed to extract either the left or right stream from a 3D clip by setting the **Source** to Left Eye or Right Eye, and direct it to either eye using the **Mapping** dropdown.

Working with transitions

The **Transition In** tab to the left of **Corrections**, and the **Transition Out** tab on the right of **Effects**, offer access to all the transitions in the Library, grouped as you find them there. Some transitions may offer settings for properties like reverse motion, color and softness that can't be edited on the timeline. The media editors also provide transport controls and a time-ruler to help in previewing the transition and adjusting its duration.




Choosing a transition in the media editor. The same transitions and controls apply to both in and out transitions.

When you have chosen a transition at the top of the screen, its settings panel will open on the right side of the media editor. Select a preset from the dropdown list, if one meets your need, or edit the parameters of the transition directly using the controls provided.

When you are offered a choice of colors, click in the color box to open a color selector, or click the color picker icon beside the box to choose a color from anywhere on the screen using a special mouse pointer.



A white fade bar on the time-ruler below the media editor preview controls the duration of an incoming transition at the left end of the scale, or an outgoing one at the right. Only a transition currently being edited is active, as determined by whether the **Transition In** or the **Transition Out** tab is selected. Click the **Play** button to preview the selected transition, or grab the scrubber to preview the transition at your own speed.



Pan-and-zoom

The pan-and-zoom tool is available for videos and images when they are opened from the timeline.

With pan-and-zoom, an area from within the image or video is used to fill the whole video frame. The area can be of any size and shape. On playback, it will be enlarged sufficiently to fill the video frame without empty areas.


If you define two or more areas, pan-and-zoom animates your presentation of the image by zooming in and out while traversing it

with simulated camera movements as it moves smoothly from one area to another. You can also rotate while panning and zooming.

The pan-and-zoom tool utilizes the full available resolution so you will not forfeit detail by zooming in.

Adding pan-and-zoom

To apply pan-and-zoom to a clip on the timeline, right-click the image or video, and choose **Pan-and-Zoom**.




In this illustration the Pan-and-zoom tab has been selected and remains set to the default Static mode. The selection frame, which we see is being resized with the mouse, defines a region of the image that will be magnified to fill the entire frame, as shown in the floating preview panel (bottom right).

Pan-and-zoom has two alternative operating modes, which are selected with buttons just above the preview. In the **Static** mode, a single unchanging image region is shown throughout duration of the clip. In the **Animated** mode, separate regions are defined for the first and last frame of the clip; on playback, a smooth 'camera move' from one to the other is shown. **Animated** mode also allows keyframing, in which any number of additional defined regions can be added to the pan-and-zoom camera path.

Static mode

In **Static** mode, a gray selection frame with round control points is displayed over the image. You can enlarge, reduce, and move this frame, but you cannot change its proportions (aspect ratio). A small floating preview window displays the currently-defined selection.

The zoom and position can also be controlled numerically using sliders in the **Attributes** panel. Double-click the sliders to reset the values, or single click to enter a numeric value.



Animated mode

When **Animated** mode is set, the image is automatically analyzed and an initial size and position both for the start and end is automatically set. The generated animation begins zoomed in slightly, then pulls back to the full size available. If an image has a different aspect ratio than the video frame, enough zoom is applied throughout to prevent blank areas from appearing.

To support the extra functionality of **Animated** mode, the color of the selection frame is used to indicate its place in the animated sequence. The start frame is green, and the end frame is red. Frames at any intermediate point are drawn in white.

When multiple frames are visible, you can drag the frames as needed by positioning your mouse over either the edge of the frame or the center dot. Moving the white frame will automatically add a keyframe at the current position.

Keyframing pan-and-zoom

With keyframing, you can create a customized pan-and-zoom animation of arbitrary complexity, though simple sequences of a few steps may be all you ever need.

Switch to **Animated** mode as described above, and note that two frames have been added to the preview. These special start and end keyframes, which as mentioned above are drawn in green and red respectively.

If you don't require intermediate keyframes, positioning the start and end frames completes your session.

For a more complex animation, however, position the scrubber where a change of camera motion should occur. To create a new keyframe, simply set the white selection frame to the desired size and position. The new keyframe is represented by a lozenge-shaped gray icon in the keyframe line below the clip timeline.

Add as many keyframes as necessary. When you are finished, click **OK** to return to the timeline of your project.

Manually adding a keyframe: To add an explicit keyframe at the playhead position without altering the current animation path, click the toggle keyframe button on the far left of the transport toolbar.



Moving a keyframe: You can drag a keyframe along the timeline to reposition it in time.

Jumping to a keyframe: To jump to a keyframe in order to modify or delete it, use the arrow buttons to the left and right of the keyframe button, or click directly on the keyframe in the keyframe line. When the playhead is directly over a keyframe, the keyframe will highlight.

Deleting a keyframe: To delete a keyframe, click its icon on the keyframe line to navigate to the right frame, then click the Delete keyframe button on the far left of the transport toolbar.

The Settings panel

The Settings panel provides a number of controls for configuring the pan-and-zoom tool.

- **Smooth** provides gentle braking when approaching a direction change in the keyframe animation path.
- **Select preset:** Choose from a number of static and animated presets.
- **Zoom, Horizontal, and Vertical** display the numerical values of the current frame. Double-click the sliders to reset the values.
- **Low pass** filters out small-scale movements to achieve a smooth, optimized animation.

360 Video

360 video is an interactive type of video that lets the viewer look in any direction by changing the viewing angle during playback. The viewing angle can be controlled by using a touchscreen, onscreen controls, or by moving the viewing device, such as a smartphone or tablet, in different directions. 360 video requires a special 360 video player (for example, YouTube and Facebook have 360 video players).

Editing 360 video

Pinnacle Studio lets you edit monoscopic equirectangular 360 video footage (check the instructions for your 360 video camera for more information). For example, you can trim the video or add titles or objects. Please note that not all effects can be applied to 360 videos.

Converting 360 video to standard video


You can also convert 360 video to standard video in Pinnacle Studio. As you play the 360 video, you can set the viewing angle for your audience, similar in effect to a person turning their head to look in different directions. You can then export the edited video as a standard file—no special player is required for the video (not interactive).



View tracker

When converting a 360 video source to a standard video, the dual preview window makes it easy to select and adjust the view by adjusting the View Tracker.

To edit and export a 360 video

- 1 In the **Edit** workspace, drag a 360 video from the Library to the Timeline.
- 2 In the Timeline, click the **Timeline Settings** button , and set the following:

- **Aspect** — choose **360 Video (2:1)**
 - **Size** — for best results, choose the highest resolution possible
- 3 Edit the video in Pinnacle Studio. For example, you can do the following:
 - Trim the video
 - Add a title or object

Note: When you apply a title or object to a 360 video, right-click the item in the Timeline, and choose **360 Video > Insert as 360** to convert the media to 360.
 - 4 When you are finished editing, save your file and click **Export**.
 - 5 In the **Studio Exporter** window, ensure that the **Same as Timeline** check box is marked (check mark appears) in the **Settings** area.
 - 6 Click **Start Export**.


To edit a 360 video and convert it to a standard video

- 1 In the **Edit** workspace, drag an imported 360 video from the Library to the Timeline.
- 2 In the Timeline, right-click the video and choose **360 Video > 360 to Standard**.

A dual preview mode opens with the **360 Source** video on the left and the **360 Preview** on the right.

- 3 In the **360 Source** pane, adjust the View Tracker to select a direction. The **360 Preview** pane updates to display the view.
- 4 Click **Play** to start the video playback. At any time, you can adjust the angle of the view by dragging the View Tracker to a new position.

Keyframes are added when you adjust the View Tracker. You can fine-tune the keyframes with the controls in the lower-left corner of the pane.



Keyframes appear below the preview panes just below the scrubber. Keyframe controls let you go to the previous keyframe, delete a keyframe, go to the next keyframe, and adjust the settings for the transition between keyframes

- 5 Make any additional edits to the video project, and save.
- 6 Click **Export**, and choose the settings you want in the **Studio Exporter**, and click **Start Export**.

Tip: You can also adjust 360 video in the **Effects Editor** manually by choosing **360 Video** and choosing **360 to Standard** or **Insert as 360**.


Motion Tracking

You can track the motion of elements in your videos and add masks or objects that follow the same motion. For example, you can apply a mask to obscure a face, license plate, or trademarked logo that is visible in your video.

You can also track the motion of an element so that you can follow it with a title or other object. For example, you can add a name label to follow a player in a video of a sporting event.

To track and mask an element in a video


- 1 In the **Edit** workspace, right-click a video in the Timeline to which you want to apply a mask, and choose **Track Motion > Mask Object**.
- 2 In the **Mask Object** area, click a **Shape** icon.



- 3 Drag in the preview window to apply the shape to the area that you want to cover. Fine-tune the mask by dragging the orange mask nodes



- 4 In the **Mosaic** or **Blur** area, choose the settings you want to apply to obscure the selected area.



Mosaic effect (left). Blur effect (right)

- 5 Track the selected area of the video by choosing one of the following **Analyze** options:
 - **Track selected mask backward all frames** — tracks the selected area backward from the current time point until it is not detected onscreen


- **Track selected mask backward by 1 frame** — tracks the selected area back one frame from the current time point. Good for short tracking segments that are not easily tracked.
- **Track selected mask** — tracks the selected area (back and forward of the current time point) until it is no longer detected onscreen
- **Track selected mask forward by 1 frame** — tracks the selected area forward by one frame from the current time point. Good for short tracking segments that are not easily tracked.
- **Track selected mask forward all frames** — tracks the selected area forward from the current time point until it is not detected onscreen.

- 6 Check the tracking analysis by playing the video using the navigation controls below the preview.


Pause the video if you notice points where the mask doesn't fully cover the selected area, and readjust the nodes in the preview area. You can change the shape of the mask by clicking the orange mask outline to add a node (pointer displays a plus sign), or by clicking a node (selected node is white) and pressing **Delete** to remove the node.


- 7 Click **OK** when you are satisfied with the mask and to return to the **Edit** workspace.

The **Mask Object** is added to the Timeline above the corresponding video.



To track an element in a video with a title or object

- 1 In the **Edit** workspace, ensure that the title or object you want to use is above the video that you want to track.
- 2 Right-click the title or object and choose **Track Motion > Follow Object**.
- 3 In the **Follow Object** area, click the **Tracker** icon .



- 4 In the preview area, click the element that you want to track. Choosing an area that has distinct color and contrast works best. The title or object that you selected appears in the preview area.



- 5 To adjust the position of the title or object, in the **Offset** area, adjust the **Horizontal** and **Vertical** settings.
- 6 To scale the title or object, in the **Size** area, adjust the **Width** and **Height** values.

- 7 Track the selected element of the video by choosing one of the following **Analyze** options:
 - **Track backward all frames** — tracks the selected area backward from the current time point until it is not detected onscreen
 - **Track backward by 1 frame** — tracks the selected area back one frame from the current time point. Good for short tracking segments that are not easily tracked.
 - **Track** — tracks the selected area (back and forward of the current time point) until it is no longer detected onscreen
 - **Track forward by 1 frame** — tracks the selected area forward by one frame from the current time point. Good for short tracking segments that are not easily tracked.
 - **Track forward all frames** — tracks the selected area forward from the current time point until it is not detected onscreen.
- 8 Check the tracking analysis by playing the video using the navigation controls below the preview.

If the tracking is lost at any point, find the point where the tracker is lost, and reapply the tracker.
- 9 Click **OK** when you are satisfied with the tracking to return to the **Edit** workspace.



Pinnacle Studio's Montage is a method of enhancing your movies with off-the-shelf slideshow, animation and multitrack editing effects. Numerous professionally designed sequences, called templates, are available to give your productions instant impact. The templates are grouped into matching themes, so that along with the technical sophistication of the templates you will also find it easy to maintain a consistent look.



But the prepared templates are only half the magic of Montage. The other half is customization. Montage templates have slots that can contain several types of custom data, including video, text captions, photos and more. You can fill in a slot just by dragging a suitable asset to the corresponding displayed drop zone.

Montage in the Library

Templates are grouped by theme in the Montage section of the Library. Each theme consists of a set of templates that can be added to your

project as ‘Montage clips’. You can create attractive, visually consistent sequences that integrate artist-created titles and animations with your own photos and video. See “The Montage section of the Library” on page 187 for further information.

Montage titles vs. standard titles

Although you can make fancy ‘titles’ from Montage templates, these are not the same as those made in the Title Editor. Each has its particular strengths.

Montage templates are especially easy to use, and can provide effects not available in ordinary titles. On the other hand, the Title Editor gives you greater control over the appearance of titles and the animation of their graphical elements.

The template collection

Each of the templates in the Library’s Montage section is designed to cover a typical presentational need. Within each theme, the available templates are designed to complement one another when used in the same project.



Templates in the Library’s Montage section. Some details are shown (e.g. the presence of text captions) and some omitted (e.g. ratings) because of current Library settings.

For instance, most themes provide an Opening template and a matching Ending template. Many themes also provide one or more

Segue templates you can use when transitioning from one video or image clip to another.

Montage in your project

The first step in using a chosen template is to drop it onto your project's timeline. Once there, the Montage template is treated as an ordinary, self-contained video clip. To customize the clip by filling in the template's blanks, you will double-click the Montage clip to open the Montage Editor. For more information, see "Using the Montage Editor" on page 196.

Each template defines a video or graphic sequence with blanks to be filled in by you. The available customizations can take several forms. For instance, most templates provide one or more slots, or 'drop zones', for video or image clips. Many let you supply text captions for titles, and some have additional parameters for other special properties.

If you want to use other clips from the timeline to customize the Montage, they can be added using the **Paste to Drop Zone** command from the Montage clip's context menu, without opening the Montage Editor.

The Montage section of the Library

Montage templates are stored in their own section of the Library. To find it, click the down arrow on any Library tab, and select **Montage**, which is listed in the **Content** section.

The play button on any Montage icon loads the template into the Player, where it can be previewed with standard transport controls.



Click the Play button on the icon to preview the template.

To use a template in your project, drag the icon from the Compact Library in the Movie Editor or the Disc Editor to the project's timeline.

Using montage templates


Montage templates are stored in the Montage section of the Library, where they are grouped by theme. To use a template, simply drag its thumbnail to the timeline of your project from the Compact Library in the Movie Editor or the Disc Editor.



To use a template, drag its thumbnail onto the timeline. The numbers on the clip indicate that five subclips are available for customization.

Montage clips on the timeline can be trimmed and edited much like ordinary video. You can add transitions and effects, adjust their audio, and so on. You can even fill the slots in the Montage with timeline clips. For fully customizing the clip with your own content, however, a special editing tool is needed. This is the Montage Editor, which opens when a Montage clip is double-clicked on the timeline. It can also be accessed with the clip context menu command **Edit Montage**.

The Montage Editor allows the user to customize a Montage clip by adjusting its built-in settings or specifying video and audio clips for it to use.



The Montage Editor lets you specify template elements such as video or image clips, property settings, and text captions. Clips are added by dragging them from the editor's Compact Library to drop zones below the Player. Here, a Library clip is ready to drop on the second zone. The clip will replace the igloo graphic now occupying the zone.

Template backgrounds

Some templates have built-in graphical backgrounds, a selectable background color, or both. Many of these also provide a **Background** check box in the Montage Editor; leave the box unchecked if you want a transparent background. This allows the Montage to be used on an upper timeline track over a background of the video or photo material on the tracks below.

Montage clips on the timeline

Montage clips behave like ordinary video clips when it comes to operations on the timeline of a movie or disc project, such as adding transitions, trimming and positioning.

A Montage template dropped onto the timeline is added by one of three methods: insert, overwrite and replace. When the editing mode

button on the toolbar is set to smart, the replace method is chosen automatically. The default length of the clip varies from one template to another.

Inserting a Montage template: A Montage can be added anywhere on the timeline. If a Montage clip is placed in the middle of an existing clip, it will interrupt that clip on playback, and the current editing mode will determine whether the second part of the original clip is overwritten or simply delayed.

If you wish to insert a Montage at a cut point, between or adjacent to other clips but without disturbing them, begin by checking that the magnet button on the timeline toolbar is turned on. This ensures that when you drop one clip very near the start or end of another, it will automatically be positioned so that the clips adjoin exactly. Also set the editing mode button to insert, so that existing material moves rightward to make space when you drop the clip, rather than any portion of it being overwritten.

Replacing an existing Montage template: To replace an existing Montage template on the timeline, hold down the **Shift** key on the keyboard, then drop the new template onto the old one. The new clip takes over not just the location but any existing customizations of the old clip. The placement lines, drawn in blue, show the boundaries of the clip to be replaced; regardless of its designed default length, the new clip will inherit these boundaries.

Overwriting clips with a Montage template: If you want to drop a Montage template onto a timeline track and have it simply overwrite other clips on the track without making any changes to the remainder of the timeline, you may do so by setting the editing mode button to overwrite. The length of the Montage clip will determine how much of the track is overwritten.

Trimming Montage clips

Although trimming operations on the timeline are the same for Montage clips as for video clips, the actual result produced by trimming may vary depending on the nature of the template.

In an all-animated template, such as a fancy rolled title, the animation always runs to completion. The animation speed therefore depends on the clip duration. Shortening the clip causes the animation to run faster, but does not truncate the sequence.

Clips that include video, in contrast, can be trimmed in the usual way. Many themes include a variable-length video subclip. When one of these is present, the clip can be expanded as far as the length of the subclip will allow – indefinitely, if the subclip happens to be a still image.

Transitions and effects

Transitions can be used at the beginning and end of Montage clips in the same way as with other clip types.

Video and audio effects can also be added to Montage clips as usual, and apply to all the content the clip embodies. However, a few effects, such as Speed, are not available for use with Montage clips.

To add an effect to a Montage clip, right click on the Montage clip on the timeline and choose **Open Effects Editor** from the context menu. Alternatively, drag an effect from the Library and drop it on the clip. Effects are located in the **Content** section of the Library.

To edit, copy or delete an effect on a Montage clip, right click on the magenta line along the top of the clip and make the applicable choice on the **Effect** context submenu.

Anatomy of a template

For examples of how themes work, let's examine the included '50s Modern' theme, which contains five templates.


All the templates in this particular theme use the same backdrop design – an abstract, scrolling pattern. It is continuously visible except during full-frame video segments. The coloring of the pattern is set using a parameter control available for each of these templates in the Montage Editor.

Now let's look at each template in turn to see how it is constructed from the elements – clips and captions – that you supply in the Montage Editor.

Opening: An Opening template usually starts with some sort of animation, including titles, and ends with full frame video. Our '50s Modern' example follows that pattern.



The scrolling background animation runs through most of this sequence. Within the animation, two customizable captions are displayed. They are represented in the diagram below by lines on the Animation bar. Both captions are flown into and out of the frame (dark line color), with a one and a half second pause for stationary display (light line color) in between.




Schematic representation of the Opening template in the '50s Modern' theme, at its default length of about 14 seconds.

Just as the second caption is leaving the frame, an animated panel containing the running video subclip is launched. The video zooms to full frame by 11:18 in the template clip, and remains so through to the end (the white portion of the 'Video' bar in the diagram).

By default, the length of this template clip is 14:00. The embedded video clip starts at a fixed offset of 7:03 and runs to the end; its length is therefore 6:27. If your video subclip is long enough, you can lengthen the overall clip, extending the full-frame video portion. This capability is indicated in the diagram above by the arrow at the end of the 'Video' bar.


Segue A: Segue templates connect two full-frame video sequences by means of some kind of animation. This first Segue example begins with two seconds of full-frame video, then zooms out to reveal a formation of multiple video panels running simultaneously. Zooming in on the final subclip leads to an expandable section of full-frame video.



Segue A integrates multiple video sources.

Segue B: This Segue achieves the basic aim of connecting two video clips more simply than the previous one. The first subclip starts at full frame, then zooms out while rotating away from the viewer. When the reverse side of its rotating panel comes into view, the second subclip is


seen to have replaced the first. The panel zooms in to fill the frame towards the end of the clip.



Segue B creates a simpler transition.

Once again, the full-screen segment of the second subclip can be extended by expanding the template clip on the timeline.

Segue C: This is similar to Segue B, except that the flying video panel takes an extra spin in the middle to admit one more subclip into the sequence.




Segue C includes a bridging video subclip.

The final subclip is again expandable.

Ending: The purpose of an Ending template mirrors that of an Opening template, and in this example the internal structure is also mirrored almost exactly. Full-frame video recedes to a flying panel that gives way to animated captions – exactly the opposite of the Opening sequence

described above. The one difference is that in this case the full-frame video portion of the clip is not extendable.



The Ending template is almost a mirror image of the Opening one.

Montage editing

Studio's main tool for customizing a Montage clip is the Montage Editor, which allows you to interact with all the settings a Montage provides. Using the editor, you can add content from the Library, change the background, and edit any text in the Montage. The editor can be invoked from a Montage clip on the timeline of a project by double-clicking the clip or with Edit Montage on its context menu.

A useful trick lets you add timeline clips directly to a Montage clip via the Clipboard. Copy the chosen clip using the **Copy** command on its context menu or **Ctrl+C**. Then right-click the Montage clip to open its context menu. Choose **Paste to Drop Zone**, then choose from the graphical submenu of all the available slots in the Montage to select one as the destination.

Using the Montage Editor

Each Montage template has its own set of slots for video and photo content, represented by drop zones in the Montage Editor. Most templates have at least one slot; the most is six. Some also provide text captions and other parameters to customize special features. You can

set a default method for how content is scaled to fit the montage templates (fit, crop, or no scaling). For more information, see “Project settings” on page 376 (**Montage scaling**).

The Montage Editor is split into five parts. On the left, the compact version of the Library provides access to your videos and photos; on the right is a customization panel including any text fields or other controls required by template parameters. The Player shows you the results of your changes. Below the Preview are the drop zones for your video and images. Below the drop zones are the drop zones for your video and images.

Interior trimming of Montage clips

When a Montage template begins or ends with a user-settable amount of full-frame video, as many do, the Montage Editor timeline provides handles for adjusting the lead-in and lead-out times – the durations of the full-frame portions. Click a handle and drag left or right to adjust either duration separately. The duration of the center part of the clip – the animated part – will shorten or lengthen accordingly. If you want to balance the lead-in and lead-out without affecting the duration of the center portion, click between the handles and drag.



Part of the Montage Editor, with the timeline (bottom) and drop zones for video or images (middle). The lower portions of the Library and the Player are also visible. Click and drag on the timeline to adjust the timing of the Montage.

For a detailed explanation of the template structure, see “Anatomy of a template” on page 193.

Working with drop zones

Clearing drop zones: To delete a subclip from its drop zone, right-click the zone and select **Remove Media** from the context menu.

Muting subclip audio: Some drop zones are marked with an audio symbol, indicating that the audio portion of any video in that zone will be included in the Montage clip's audio. If you don't want the audio to be used, click the symbol to mute the subclip.

Choosing the start of your subclip: Video in a drop zone can be adjusted to start from an offset in the subclip. Click and drag the start of clip slider located under the drop zone to adjust the start frame. The keyboard left and right arrow keys are handy for making fine adjustments.



If the drop zone you are working with is active at that time index, the preview will reflect any changes to the start frame. When you are fine tuning the start frame of a subclip, it's a good idea to set the scrubber position to the location where the Player preview will be of the greatest assistance.

Using the start of clip slider changes neither the position of the subclip within the template nor its duration, but only which excerpt of the subclip is used. If you set the start of the subclip so late that the video runs out while its zone is still active, the subclip's last frame will be frozen to fill the allocated time.

Adding effects within drop zones: It is possible to apply video or audio effects directly to a Montage subclip by dragging the effect to the drop

zone. As usual, a magenta stripe on the top of the clip signals that effects have been applied.



Removing effects within drop zones: Look under Effects the zone's context menu for the **Delete all** command, or for the Delete submenu on which you can select the effect to be deleted.

Note: If you remove or replace the media in a drop zone, all the effects applied to that media are removed, too.

Chapter 7: The Title Editor

Pinnacle Studio's Title Editor is a powerful tool for creating and editing animated titles and graphics. Its extensive suite of text and image effects and tools provides innumerable possibilities for the visual design of your movie.



Areas of the Title Editor: 1. Presets Selector; 2. Library; 3. Edit Window; 4. Settings Panel; 5. Toolbar; 6. Layer List

These are the main areas of the Title Editor display, numbered as in the illustration above:

- 1 The **Presets Selector** provides tabs for **Look** and **Motion** presets, with the presets organized by style within each tab. A Look is a visual styling of a text or shape layer in your title; a Motion is an animation routine that can be assigned to any layer but is most


often applied to text. See “Preset Looks” on page 208 and “Preset Motions” on page 209 for further information.

Hover your mouse over any preset to see how it will affect your title. A single click applies the preset to the current layer. After being applied, Looks can be customized using the Settings Panel.

- 2 The **Library** provides resources for building your titles. The tabs across the top provide access to all available media and content. This compact version of the Library is functionally identical to the full Library as described in “Chapter 2: The Library” on page 17.
- 3 The **Edit Window** is your main work area when authoring or editing a title. It provides a scrubbable preview of your title with hands-on editing. See “The Edit window” on page 220 for details.
- 4 The **Settings Panel** has separate collapsible subpanels for each of three settings categories: **Text settings**, governing the style and size of text captions; **Look settings**, for the configuration of faces, edges and shadows; and **Background settings**, which pertain to the title’s background layer.
- 5 The **Toolbar** has four control groups. From left to right: the add text and add shape tools; a set of layer manipulation controls; a full set of transport controls including a loop button; and a pair of counter readouts showing the duration of the title and the current playback position.
- 6 The **Layer List**: Each graphical or textual element constitutes a layer in the title, which is a stack of such layers. The opaque parts of each layer obscure the layers below; the bottommost layer can obscure only the background.

In addition to listing each layer by name, the Layer List includes an animation timeline showing the time span during which each layer is active, and the Motions that have been assigned to it. These properties can be adjusted by dragging.

The process of building up an image in layers is called ‘compositing’. Because the information in each layer is maintained separately, to be combined only when the image is output, it is possible to return to the composition at any time and add new layers, and to adjust, reorder, remove or replace existing ones.



Building up an image in layers starting with an empty frame (top left). The checkerboard pattern indicates transparency. Although backgrounds can have transparent or translucent areas, here we add an opaque background (0) for clarity, followed by successive layers with some opaque content (1, 2, 3). In the final composition (bottom right), upper layers obscure those below.

Launching (and leaving) the Title Editor

The Title Editor can be invoked in two ways: by double-clicking any title in the Library or on your project’s timeline; or by clicking the Title button on the toolbar of the timeline.

Keywords in title names

Some of the provided titles in the Library have transparent areas through which the content of underlying tracks will be visible. The names of these titles all contain the keyword 'overlay'.

'Full-screen' titles have no transparent areas: they fully occupy the video frame. Their names contain the keyword 'fullscreen'.

In the Library, you can easily view only the titles of one or the other type by searching on the appropriate keyword.

Tip: Other search keywords to try out with titles in the Library are 'roll', 'crawl', 'name' and 'title'.

Saving the title

Use **Save Title** as in the **File** menu in the Title Editor to store titles to your computer's file system. From there, titles can be exported to other computers, and shared with other Pinnacle Studio users. If you save to a watchfolder, the edited title will appear in your Library automatically.

Closing the Title Editor


To close the Title Editor, use any of the following methods:

- Click the **OK** button at the bottom of the Title Editor. If you opened the title from the Library, you will be prompted to save any changes to the title under a new name. If you opened the title from a timeline, your new or updated title becomes part of the current project.
- Click on the **Cancel** button at the bottom of the Title Editor. Any changes you have made are discarded.

- Click the Cancel button (X) at the top right of the window. This is equivalent to clicking **Cancel**, except that if you have made changes you will be given an opportunity to save before closing.

The Library

The Library appears in the Title Editor as a tabbed panel on the left side of the window. The tabs across the top give access to all the available media and content. This compact view of the Library is functionally the same as the main view described in Chapter 2. For editing titles, the Library sections of interest are Photos, Video, and Movie Projects.



The compact version of the Library in the Title Editor provides the same comprehensive access to your media as the full version.

Adding Library media to a title

To add a video or photo to the title, drag it from the Library into the Edit Window. The new element is created at a default size where you drop it in the Edit Window. You can then move, resize or rotate it as you like.

To add a video or photo as a full-screen background for your title, drop it onto the background drop-zone of the Background Settings subpanel. See “Background settings” on page 214 for details.


You can also use a video or photo as the fill for the face, border or shadow of your text. To do so, first add a face, border, or shadow to your Look Settings using the add buttons. Then drop your photo or video into the drop zone to the right of the **Fill**.



The Presets Selector


Quickly setting up an attractive title is easy with the Title Editor's Presets Selector. After entering your text, and with the text layer still selected, apply any of the preset Looks to it with a single mouse-click. To make it even easier, as you hover the mouse over any Look icon, the Edit Window previews the effect on your title of applying the Look to the current layer.

Even if you can't find exactly the Look you want among the presets, you can often save time by starting with one that's almost what you want, then tweaking it in the Look Settings subpanel.



The Presets Selector, with the Looks tab selected. Clicking the name of one of the listed preset families opens a pop-down tray of icons.

To give your title some visual impact, there's nothing like a bit of animation. Click the Motions tab of the Presets Selector. The three groups of presets available correspond to phases in the life of a layer.



The Motion presets are categorized by the role they play in introducing the layer, displaying it, or removing it from view.

As with Looks, Motions can be previewed as they will appear in your title by hovering the mouse over any of the preset icons. Once your mind is made up, you can apply the chosen Motion with a single click.

Preset Looks


The Looks tab of the Title Editor Presets Selector provides visual styles that can be applied to the text and shape layers in your title.

Previewing Looks

To preview a particular Look on a particular layer, first select the layer, then open the Looks tab of the Presets Selector and hover your mouse over the thumbnails. As you hover, the Edit Window previews your title as it would appear with the selected Look applied. This lets you immediately gauge its effect in context.

Applying a Look

To apply a preset Look to a text or vector graphics layer, first select the layer with the mouse by clicking in the Edit Window or the Layer List. You can also affect more than one such layer simultaneously using multiple selection or a layer group.



To begin using Looks, select a family of presets: Standard, Shadow, Beveled or Outlined. Hover over thumbnails to preview presets; click the thumbnail to apply one to the current layer.

Having selected the layer or layers to change, use one of the following methods to apply a Look:

- Click its thumbnail in the Presets Selector.
- Drag the thumbnail from the Presets Selector onto the layer in the Edit Window.
- Drag the thumbnail from the Presets Selector onto any of the layers or grouped layers in the Layer List header.

Preset Motions

The Motions tab of the Presets Selector contains the animation routines that give the Title Editor much of its power. These Motions are assigned to and operate on single layers in your title. The Motions are divided into three classes based on the portion of the layer's lifespan they affect: enter, emphasis and exit.

- An enter Motion controls the arrival of the layer – its first appearance within the running title.
- An emphasis Motion maintains audience focus on the content of a layer by giving it an attention-getting action during its time on-screen.
- An exit Motion takes the layer off-stage again, completing its life cycle.

Each layer is allowed to have one Motion of each type. All Motions are optional, however, and it's also quite possible to have a title with no Motions at all.

The Motions collection

In each of the three types of Motion, most of the animations can be grouped into several standard classes based on their mode of action.

Letter-based Motions operate at the level of individual letters in a text caption (other kinds of layer are treated as consisting of a single 'letter'). For instance, in the enter Motion 'Letters turn', the letters in the text layer are first seen edge on, then rotate in place one by one until all are in their normal orientation.


Word-based Motions work similarly, but with words as the smallest unit of animation. In the enter Motion 'Words from bottom', the words in the layer float up into position one by one from below the frame.

Line-based Motions are meant for layers with multiple lines of text, each of which is processed in turn. In the enter Motion 'Lines from behind', each line of text is brought onto the screen along a perspective track as though it originated from behind the viewer's own position.

Page-based Motions affect the entire layer simultaneously. One example is the enter Motion **Barrel roll**, which 'rolls' the layer into position from above as though it were painted on the side of an invisible rolling barrel.

Matching the enter and exit Motions

Most enter Motions have a corresponding exit Motion with which they can be paired if visual consistency is desired. For example, a layer that enters with the 'Words from infinity' Motion could be configured to exit with 'Words to infinity'. However, this kind of consistency is only an option, not a requirement, and you can mix and match Motions of the three types in any way you choose.



The Presets Selector offers Enter, Emphasis and Exit Motions. Each layer in a title can use one Motion of each type.

Previewing Motions

To preview a particular Motion on a particular layer, first select the layer, then open the Motions tab of the Presets Selector and hover your mouse over the thumbnail of interest. As you hover, a looping preview of the title animation will begin to run in the Edit Window so that you can immediately see the effect.

Adding Motions

To add a particular Motion to a particular layer, first select the layer, then do one of the following:

- Click the Motion's thumbnail in the Presets Selector.
- Drag the Motion's thumbnail from the Presets Selector to an accessible layer (one not masked by other layers) in the Edit Window.
- Drag the Motion's thumbnail from the Presets Selector onto any of the layers or grouped layers in the Layer List header.

Upon using any of these methods, the Motion will be added to the layer, replacing the existing Motion of the same type on that layer, if any. See "The Layer List" on page 231 for details on working with Motions in the Layer List.

Creating and editing titles

A title in Pinnacle Studio's Title Editor is built from elements of four types:

The background layer: By default, the background is fully transparent. For overlay titles, this is normally what you want. For special purposes, or for full-screen titles, you can choose a color, a gradient, an image, or video for the background. For additional flexibility, the Background Settings also include an opacity control. See "Background settings" on page 214.

Video and image layers: The resources that make up these layers originate in the Videos, Photos and Movie Projects sections of the Library. The layers support the same operations as text and shape layers except for the application of Looks.

Text and shape layers: These are 'vector-based' layers, meaning that they are stored not as bitmapped images like video and photo files, but as a kind of 'recipe' for recreating the images from straight and curved line segments to which properties (e.g. color) and special effects (e.g. blur) can be applied. Like video and image layers, these vector-based layers can be dragged, resized, rotated and grouped, and you can apply Motions to them. Unlike the other layers, however, they can also be customized with Looks from the Looks section of the Presets Selector. See "Preset Looks" on page 208 for details.

Motions: Motions are animation routines that can be applied to any layer in the title composition except the background. Motions are selected and applied from the Motions tab of the Presets Selector. Once a Motion has been applied to a layer, its timing can be adjusted in the Layer List timeline. See "Preset Motions" on page 209 and "The Layer List" on page 231 for further information.

Creating text and shape layers

To create a **text layer**, either click the **add text** button in the header bar of the Layer List timeline, or simply double-click an empty area of the Edit Window. A new layer containing default text will appear. The text is automatically selected, and will be replaced if you now begin to type.



To create a **shape layer**, click the **add shape** button (to the right of add text), then make a selection on the pop-up menu. The available choices include circle, square, ellipse, rectangle, horizontal and vertical 'pill' shapes, and triangle. Upon selection, a new layer of the given shape and a default size appears in the center of the Edit Window.



Editing layers


The remainder of this chapter provides details on editing the background and layers in the Title Editor.

- To learn about customizing the Background layer, see "Background settings" on page 214.
- For information on moving, resizing, rotating and rearranging all types of foreground layers, see "The Edit window" on page 220 and "The Layer List" on page 231.
- To learn about editing text and setting text properties, see "Text and text settings" on page 223.
- For working with stereoscopic titles, see "Titles and stereoscopic 3D" on page 229.
- Multiple selection and grouping is covered under "Working with layer groups" on page 237.

- Finally, to learn about Motion editing in the Layer List timeline, refer to “The Layer List” on page 231.

Background settings

Unlike the foreground layers in a title, the special background layer does not appear in the Layer List, and is not modifiable in the Edit Window. Instead, the background is controlled from the Background Settings panel.



The Background Settings panel lets you create the background of a title. The small preview area serves as a Color Selector button, and also as a drop target for videos or images from the Library. Here the Aspect Ratio menu has been opened by clicking the button just above.

The default background for a title is fully transparent. If your title appears on an upper track in your project’s timeline, any video or other imagery on the tracks below will be visible behind the title foreground.

To create a solid or gradient background, click the background preview area. This brings up a color selection dialog, and also provides an eyedropper that allows you to pick up a color from anywhere within the Title Editor window.

You may choose to have a gradient background by choosing the **Gradients** tab at the top of the color palette. Additional gradient

markers can be set by single-clicking below the gradient bar. Gradient markers can be removed by dragging them vertically out of the bar area.


To use video or a still image as your background, drag the item down from the Videos or Photos sections of the Library to the background preview, which also serves as a drop zone.

To make the background translucent, position the **opacity** slider anywhere between fully transparent (all the way to the left) and fully opaque. Double-clicking the slider returns it to full opacity.

To reset the background to its default state (with no background), click the **trashcan** button.


Look settings

The **Settings** panel provides access to the Look Settings, where you can examine, modify, add or delete the individual detail layers that are overlaid to generate a particular Look.



Click the 'Look Settings' arrow on the Settings panel to open a subpanel where the Look of a layer can be edited. Under the name of the currently-selected preset ('Blue Bevel') are three buttons for creating new detail layers. The edit panel for the Face detail is open.

There are three types of detail layer: **face** (surface), **edge** and **shadow**. The three types differ not in the settings they support, but in the default position at which they will be inserted in the layer stack. Unless explicitly dragged out of position, face details always appear at the top of the stack, followed by edges, and finally shadows. After a detail has been created, however, it can be dragged up or down in the layer stack as desired.




Face, Edge and Shadow: A new face detail (left, top) is added above the uppermost existing face layer; new edge and shadow details are added below the bottommost layer of their respective types.

The properties of individual detail layers can be modified by means of controls on collapsible panels in the Looks Editor.

The following detail properties are available:

- **Offset X, Offset Y:** These sliders set the position of the detail layer relative to the nominal position of the text or graphic to which the Look is applied. The range of offset is -1.0 (left, or bottom) to +1.0 (right, or top). The maximum offsets represent one eighth the width and one eighth the height of the Edit Window work area.




In this example, a Look with three detail layers has been applied to a single text layer. The detail layers are configured identically except for their offset values, as follows: top left (-1.0, 1.0); center (0, 0); bottom right (1.0, -1.0).

- **Size:** This slider sets the thickness of the segments used to draw the text or graphic, from zero to 2, where 1 represents the default thickness.



This example includes three detail layers with varying size values. From left to right: 0.90, 1.0, 1.20. The visual effect of varying the size depends on the default thickness of the strokes in the layer. In a text layer, this depends on the font family and size chosen.

- **Blur:** As this slider increases in value from 0 to 1, the detail layer affected becomes increasingly ghostly and indistinct.



The detail layers in this example differ only in their blur settings. From left to right: 0.15, 0, 0.40.

- **Opacity:** This slider sets the opacity of the detail layer from 0 (transparent) to 1 (opaque).
- **Fill:** Click the color swatch button to open a color picker in which the fill color of the detail layer can be set. The color picker includes an eyedropper button to pick up a color from anywhere in the Title Editor. To set a gradient background, choose the Gradients button at the top of the color palette. Additional gradient markers can be set by single-clicking below the gradient bar. Gradient markers can be removed by dragging them vertically out of the bar area.

Working with detail layers

In addition to setting the properties of existing detail layers, you can add details of any of the three types, delete details, and reorder the detail layer stack.

To add a detail layer, click one of the three small buttons at the top right of the Look Settings. From left to right, these create a new face, edge and shadow layer respectively. The placement of the new detail layer in the layer stack is determined by its type, as explained above.



To delete a detail layer, click the **trashcan** button in the header bar of the detail's edit panel.


To rename a detail layer, double-click its name, type the name you want, and press **Enter**.

To temporarily hide a detail layer, click the dot-shaped visibility toggle icon in the detail's header.

To close down or open up the edit panel of a detail layer, click the arrow button at the left-hand end its header bar.

To reorder detail layers, drag the header bar of the edit panel to its new location. If the Look you are editing contains more than two or three layers, it can be easier to follow the action if you close down the panels first so that the whole stack is visible at once.

Saving a custom Look


Once you have finished editing a custom Look, you can save it to the 'My Looks' presets group by clicking the **save look** button  in the header bar of the Look settings. Before saving, it's a good idea to rename the Look. To do so, double-click the current name in the settings, type a descriptive name for the Look, and press **Enter**.

Once the Look is saved you can retrieve it at will through the Presets Selector, under 'My Looks'.

The Edit window

The Edit Window is the main preview and editing area of the Title Editor. This is where you rearrange, resize and rotate the foreground layers of your title.

A necessary first step for most kinds of editing is to select the layer or layers you want to affect. Selected layers are drawn within a frame having eight control points for sizing and a rotation handle at the top for rotating the selection in one-degree increments. Most types of layer can be ‘grabbed’ for dragging to a new position by clicking directly on the control frame.



Rotating a shape object within the Edit Window. The smaller dot at the top center of the control frame is the rotation handle for the layer. To rotate a layer, click down on its rotation handle and drag. When you are over the rotation handle, the mouse pointer will show as a circular arrow.

With text and shape layers, some of the layer content may appear outside the control frame. This occurs if one of the ‘details’ within the Look is defined with a horizontal or vertical offset that moves the detail away from the nominal location of the layer. See “Applying a Look” on page 208 for more information.

Layer operations in the Edit Window

The operations described here are for a single layer, but can be extended to work with multiple layers simultaneously. See “Working with layer groups” on page 237 for more information.

To select a layer in the Edit Window, click in the layer rectangle with the mouse. This causes the layer's control frame to appear, ready for editing.

Layers respond to mouse clicks anywhere within their containing rectangle (the rectangle shown by their control frame when selected). This means that you may not be able to manipulate a layer that is visible only because it lies beneath a transparent area within the rectangle of another layer. To perform any editing with the mouse in such cases, you should first hide the upper layer(s) as described under "The Layer List". See page 181 for details.

To move any non-text layer, click down anywhere within its rectangle and drag to the new position.

To move a text layer, position the mouse near the edge of the layer's control frame until you see the drag pointer (four-way arrows) appear, then click and drag normally. Clicking inside the frame, as you would do a non-text layer, would instead activate text-edit mode. See "Text and text settings" on page 223 for detailed information.



To resize a layer but retain its proportions, click down on a corner point of the control frame and drag outwards or inwards until the desired size is achieved.

To resize a layer and modify its proportions, click a side point of the control frame and drag. By resizing with the center control point on

two adjacent sides in succession, you can produce any desired size and proportion.

To rotate a layer, click down on its rotation handle and drag. For finer control over the rotation, move the mouse pointer away from the center of rotation while dragging. The extra distance makes it possible to define smaller angles between one mouse position and the next.

To change the stacking position of a layer, right-click the layer, and select from its context menu one of the commands on the **Order** submenu: **Send to Back**, **Send Backward**, **Bring to Front**, **Bring Forward**. Convenient keyboard shortcuts are available for all four operations; respectively, **Ctrl+Minus**, **Alt+Minus**, **Ctrl+Plus** and **Alt+Plus**.

Another approach to reordering layers, which may be more convenient in titles where several layers overlap, is to use the Layer List. For more information, see “The Layer List” on page 231.

To delete a layer, select the control frame or select it in the Layer List, then press **Delete**. Alternatively, you can use the context menu command **Delete Layer**. If the layer is a text layer in text-edit mode, the **Delete** command (and the **Delete** key) apply to the layer’s text only, not the layer itself.

Text and text settings

For all the graphical sophistication of the Title Editor, in many instances the primary reason for using titles is the text they contain. The editor therefore provides several specialized options to help you ensure that you can get your text looking exactly the way you want. The text operations we will look at below include:

- Editing the text

- Changing fonts, font sizes and styles
- Setting text justification and flow
- Copying and pasting text properties

The areas of the Title Editor of most interest in text work are the Edit Window and the Text Settings panel. For styling a text layer, the Looks section of the Presets Selector and the Look settings panel also come into play. See “Preset Looks” on page 208 and “Look settings” on page 215.

Text-edit mode

As described elsewhere, when dragging a text layer you have to be careful to click at the edge of the control frame, rather than anywhere within it, to avoid accidentally putting the layer into text- edit mode. For the operations described here, however, text-edit mode is exactly what we want. In a newly-created text layer, text- edit mode is already enabled: you can begin to type immediately and the default text will be replaced.

To activate editing for an existing text layer, click anywhere inside the control frame. Text-edit mode becomes active and – to save you an often-required step – all existing text in the layer is automatically selected. As usual, selected text is indicated by highlighting.



A text layer with all text selected. From left to right, the text editing controls in the header bar above govern letter styling (bold, italic, underline); text alignment and text flow; and font name and size. In text-edit mode, the mouse pointer over the layer has the 'I-beam' shape as shown here.

To modify the text itself, simply start typing. The highlighted text disappears and the text you type takes its place. As you type, the current insertion point (the place in the text where new letters are inserted) is indicated by a vertical line.

If you want to add new text without losing what was already there, click at the desired insertion point after putting the layer in text-edit mode, or use the arrow keys to maneuver the insertion point as desired.

You can also highlight (and thus replace) only part of the text before typing: drag across the letters with the mouse, or hold down Shift while using the arrow keys. You may also triple click to select all of the text in the layer or double click on a word to select just that word. Lastly, if you want to select all the text in the layer again, you can use the mouse or arrow keys as just described, or give the standard shortcut **Ctrl+A**.



The Text Settings panel

The topmost Settings subpanel is this group of controls for editing and styling the content of the current text layer.

Using the text field

In cases where text in the Edit Window is difficult or impossible to access for editing, the text field in the panel provides another convenient way to select and edit your text. This is the approach to take if the text is off-screen at the scrubber position, which can happen when Motions are involved. The text field expands to provide up to three lines as you type, then adds a scroll bar if further lines are entered.


Styling highlighted text

Most of the Title Editor text controls are probably quite familiar to you from using similar controls in other applications. Those that apply to the highlighted text only are these:

Font styling: To set or unset the bold, italic or underline properties of the selected text, use the toggle buttons in the header bar, or the standard keyboard shortcuts **Ctrl+B**, **Ctrl+I** and **Ctrl+U**. The buttons light up when their respective style options are active.



Font name: Your titles are the perfect place to experiment with fancy display fonts, so you'll likely be accessing this dropdown list quite often. If you have many fonts on your system, the list can be quite long. For ease of navigation, pressing the first letter of a font name will take you instantly to the corresponding alphabetical location in the list. Click the font you want, or move to the name using the up and down arrow keys and press **Enter**.



To select a font, open the dropdown list and click the one you want. The font is applied to the currently-highlighted text only.

Font size: The Title Editor provides several methods of setting the font size. You can enter a new value directly into the font-size edit field (up to 360), or use the neighboring dropdown arrow to display a list of sizes. Further to the right, the shrink font and enlarge font buttons change the size in intervals that widen as the font size increases.



Copying and pasting text styles

With both text and shape layers, the **Copy Attributes** and **Paste Attributes** context menu items, found by right clicking on a the control frame in the Edit Window, let you copy Looks from one layer to

another without having to open the Looks section of the Presets Selector.

With text, this operation also replicates the font name, size and style from one text layer to another, and also works on partial selections within text layers.

Text alignment

For titles with multiple lines of text, the Title Editor provides a standard menu of justification options. The default for new text layers is center justification (Align Center on the dropdown list), in which each separate line is horizontally centered in the available space. The additional options provide for **Align Left**, **Align Right** and **Justify**.



Text flow

To accommodate the various conventions of different languages with regard to the direction in which lines of text are written, and for maximum graphical design flexibility, the Title Editor offers a menu of eight text flow options. These options, which work in concert with the justification options just discussed, affect not just the way the text is displayed but also the meaning of standard keys like **Home** and **End**.



Styling with Looks

As explained in the topic “Preset Looks” on page 208, the appearance of text and shape layers can be transformed by the application of Looks from the Presets Selector. In a partially-highlighted text layer, applying


a Look affects only the highlighted text. In principle, each of individual character in your title could be given its own Look.



Titles and stereoscopic 3D

If you are working on a stereoscopic 3D project, you don't have to settle for a 2D title. The Library includes many titles identified as 3D, but any title at all can make use of stereoscopic text.

To set a 2D title as stereoscopic, select a text layer, then check the Stereoscopic box on the Stereoscopic Settings subpanel. Now the Text Depth setting becomes available; it allows you to change the apparent distance between the text and the viewer. If you save the title to a watchfolder, its Library thumbnail will carry the 3D indicator.




A stereoscopic title that has been opened from the Library or a 3D timeline will provide a stereoscopic preview. A stereoscopic title on a 2D timeline will preview in 2D only; the timeline settings must be changed to 3D in order to get stereoscopic playback.

Text depth: To change the depth of a text layer – its apparent distance from the viewer – select the layer and open the **Stereoscopic Settings** subpanel. Make sure the **Stereoscopic** box has an orange checkmark displayed. As you increase the value in the **Text Depth** slider, the text recedes from view; decreasing the value brings the text closer.

As you adjust the depth of the text, you may have to adjust the font size as well. Moving the text into the distance can decrease its apparent size to the point of unreadability, while bringing the text closer can make it too large to fit in the title frame.

The Layer List

The Layer List, which occupies most of the bottom part of the Title Editor display, has two columns: one of layer headers, and one of timeline tracks. In each row, the header contains the name of the layer, and a visibility button. To the right of the header, the timeline track serves as a graphical editor for controlling the lifespan of the layer within that of the title as a whole, and the durations of any Motions that have been assigned to the layer.



The left-hand portion of the Layer List contains the layer headers; to the right is an animation timeline where the timing of each layer, and of any Motions applied to them, is displayed and can be modified. (Only the leftmost portion of the timeline is shown here.)

If the title you are editing was opened from the Movie Editor or the Disc Editor, the Layer List timeline represent the current length of the clip. To modify it, return to the timeline of your project and trim the title there.

If the title was opened from the Library, and so is not bound to a clip in the project, its length can be edited in the Title Editor. Set the desired duration by entering a value directly into the duration counter at the right side of the toolbar. All layers will be adjusted relative to the new duration.

The Layer List toolbar is home to several important groups of controls (see “The toolbar” on page 234).

Working with the Layer List

The Layer List is a multitrack timeline very similar in conception to the timeline of the project itself in the Movie Editor or Disc Editor. Some operations, such as those to do with Motions, are particular to the Title Editor, however.

Layer operations

The procedures described here are all carried out in the header area of the Layer List.

Selecting layers

Clicking a header in the Layer List has the same effect as selecting the layer in the Edit Window (and vice versa). The layer name highlights, and the layer’s control frame appears. Multiple selection is also allowed, using the standard Windows mouse and keyboard combinations **Shift**-click (extend selection), **Ctrl**-click (toggle selection of one item), and **Shift+Ctrl**-click (extend selection from last item clicked). See “Working with layer groups” on page 237 for information on how to use multiple selections.

Layer names and renaming

When you create a new layer, the Title Editor gives it a default name based on the resource name or file name. Since the default names are often not very descriptive of the layer contents, it may be helpful in a title with a number of layers to give them custom names that make it easier to tell at a glance which name goes with which layer.

The name of a new text layer is the same as its default text (“Your text here”). Unless you give the layer a custom name, its default name will continue to match whatever text you type into the layer. Once you do rename a text layer, further changes to the text are no longer reflected in the layer name. The default behavior can be restored by setting a blank name, however.

To rename the primary layer, click its name. An edit field opens with the existing name selected. Type the new name, then press Enter or click outside the edit field to finish.

Reordering layers

As we saw in the topic “Layer operations in the Edit Window” on page 221, the position of a layer in the layer stack can be altered by means of commands on the Layer context submenu, or by keyboard shortcuts such as **Ctrl+Plus (Layer > Bring to Front)**.

The Layer List offers a more direct approach: simply drag the layer header to a new position in the list. This is particularly handy in situations where overlapping layers make mouse selection difficult. As you drag the layer, an insertion line shows where the layer will appear in the list when dropped.

Using multiple selection (see “Selecting layers” on page 232) you can drag several layers at once to a new position.



Hiding and locking layers

A complex title can get crowded very quickly as you add layers to the composition, and Motions to the layers. The **visibility** button at the right-hand end of the layer header is handy for simplifying such situations.


Click the eye-shaped **visibility** button to temporarily remove a layer from the Edit Window. The layer's information and settings are preserved, but you will be able to work on other layers for the time being without the hidden layer obscuring either your view or your mouse actions. Click again to restore the layer to visibility.

The toolbar

The controls and readouts on this header bar are in groups. From left to right:

- The **add text** and **add shape** buttons allow you to create new 'vector-based' layers to which Looks from the Presets Selector can be applied. Clicking **add text** adds a new text layer with a default Look and caption. As a shortcut for add text, you can simply double-click any unused area of the Edit Window. Clicking **add**


shape opens a pop-up menu from which you can select a particular shape as the contents of the new layer.



- Each of the **align**, **group** and **order** buttons opens a pop-up menu of commands that can affect multiple layers. These commands are covered under “Working with layer groups” on page 237.



- The 3D viewing mode switcher appears if you are editing a stereoscopic 3D title. Please see the “3D viewing mode switcher” on page 43 for information on the available formats.
- The transport buttons allow you to preview your title without leaving the Title Editor. From left to right, the functions of the buttons are: **loop play**, **jump to start**, **go back one frame**, **play/pause**, **advance one frame**, and **jump to end**.



The loop play button loops continuously once started; to halt it, click anywhere on the Edit Window, or click loop play again. As usual, pressing Space provides a convenient shortcut for stopping and starting playback.

- The **System Volume and Mute** button allows you to adjust the speaker volume of your system. It does not change the audio level of any clips on your timeline.
- The counters show the duration of the title and the current position of the Layer List timeline scrubber in the usual hours, minutes, seconds and frames format. For titles that come from your project rather than the Library, the scrubber position shown is relative to the start of your project's timeline, not the start of the clip.



Editing layers and Motions

When a layer is created, its duration is set to the full span of the title of which it is a part. To delay the first appearance of a layer in the running title, or to banish one layer while continuing others, drag the ends of the layer along the timeline in the same fashion as clip editing on the timeline of your project.




A title is like a stage on which the layers are actors who come on for their big scene and then depart. Trimming the layers in the Layer List timeline allows you to control precisely the timing of their entrances and exits.

Up to three Motions – one of each type – are allowed to each layer. These are also displayed on the timeline, where their durations too can

be adjusted. Enter and exit Motions are each anchored to their respective ends of the layer lifespan, but the end of the enter Motion and the start of the exit Motion can be freely edited with the mouse.

If the layer has an emphasis Motion, it occupies whatever unused duration remains (up to the whole length of the title).



Three layers with Motions. The top layer has only an Emphasis Motion (solid line), which therefore uses the full duration. The bottom layer has Enter and Exit Motions, and a static interval between them. The center layer has Motions of all three types. The Enter Motion is being trimmed (note the horizontal arrow cursor); as its length changes, the Emphasis Motion self-adjusts to consume fully any unused time.

To replace one of the Motions used by a layer, simply add the new Motion as usual: an existing one of the same type will be overwritten.

To delete a Motion without replacing it, select the layer and click the small 'x' in the center of the Motion's timeline graph.

Working with layer groups

The Title Editor Layer List allows you to group layers on either a temporary or a permanent basis.

To create a temporary group, you will use standard multiple selection techniques whether in the Edit Window or on the Layer List. You can then make changes, such as applying a Look, to all the members of the group simultaneously. The group remains whole only until you click another layer or an empty area of the Edit Window, whereupon the

layers resume their individual existences. In a temporary group, the control frames of each member are all visible at once.

To create a permanent group, you first create a temporary group, then click the **group** button on the Layer List toolbar (or use the Group command from any member's Grouping context submenu).

Once created, the group stays together until you explicitly disband it with the ungroup button or menu command, or by dragging the member layers out of the group in the Layer List. One further command, **regroup**, automatically reconstitutes the last group to have been ungrouped.

When a permanent group is selected, it has a shared control frame that encloses all its members. The control frames of the individual members are not visible.

Permanent groups have their own header entries and timeline track in the Layer List. The group header can be expanded or collapsed to reveal or hide the headers for the member layers. When the group is open, its member layers are indented with respect to the group header.



An ordinary layer and a group with three member layers in the Layer List. The timeline graphics show that Motions have been applied to the group itself and to one of its members. The mouse pointer is positioned to collapse the group, which would hide the names of the member layers.

Temporary groups and permanent groups respond differently to many commands as detailed below.

Note: Even when a layer belongs to a permanent group, it can still be individually selected, either in the Edit Window (unless the group itself is currently selected) or the Layer List. A member layer can even be added to a temporary group with other layers inside or outside the permanent one.

Multiple selection of layers

The first step in making a group is to select the multiple objects that will comprise it. In the Edit Window, this can be accomplished in two ways:

- By clicking and dragging with the mouse to mark out a selection rectangle (a 'marquee') that intersects all the objects you want to group.
- By clicking the first object you want to group, then **Ctrl**-clicking each of the others.

Another approach to multiple selection uses the Layer List. For more information, see “Working with the Layer List” on page 232.

Edit Window operations on the group

Both temporary and permanent groups can be repositioned, resized and rotated.

To reposition any group, drag it to the new position as though it were an individual layer.

To rotate a permanent group, drag the rotation handle of the shared control frame. All members of the group revolve about their common center like planets revolving around the Sun.

To rotate a temporary group, drag the rotation handle of any member. All members of the group rotate about their own centers like planets rotating on their axes.

To resize a permanent group, drag any control point of the shared frame. The size of the whole group changes as though you were stretching a rubber sheet with all the layers painted on it.

To resize a temporary group, drag any control point of any member’s control frame. Each layer is affected individually, expanding or contracting in place about its own center.

In resizing operations on groups, as with individual layers, dragging by a corner control point preserves the aspect ratio of the layer, whereas dragging by a side control point allows the proportions to be altered.

Applying properties to a group

Once a temporary group is selected, any property settings you make will affect every member to which the property is applicable:

- **If you apply a Look**, any text or shape member will receive it.
- **If you add a Motion** by right-clicking a Motion icon and choosing Add to selected layer(s), the result will be the same as if you had added it to each member individually.
- **If you select a font**, or change any other text styling attribute, every text member of the temporary group will be updated.

Except in the first case, permanent groups have their own rules for these operations:

- **If you apply a Look**, it works the same as with a temporary group: all text and shape layers in the group are affected.
- **If you add a Motion to a permanent group**, the group is treated for the purposes of animation as a single graphic object, without regard to the letters, words or lines its members may contain. However, the individual Motions of its members continue to run along with that of the group as a whole.
- **Text stylings** cannot be applied to a permanent group.

Aligning layers in temporary groups

The final type of group operation, one that applies to temporary groups only, is provided by the **group align** button on the Layer List toolbar. The commands, of which there are three for horizontal and three for vertical alignment, affect all the members of the group except for the first selected, which sets the position for the others.



Video may be thought of as primarily a visual medium, but the role of sound in your movies is often no less important than that of the images on the screen.

Feature film and television productions include numerous types of audio, beginning with the dialog and other sounds created during live action. In your movies, that raw soundtrack – the original or synchronous audio – is imported along with the video, and remains bound to it unless you explicitly separate them.

Most commercial productions also require sound effects – slamming doors, crashing cars, barking dogs – and incidental music, which may consist of music created especially for the production, songs taken from recordings, or both. With the ScoreFitter tool, you can even create a full-length musical background track at the press of a button. Voice-overs and other types of customized audio are also often needed.

Audio features of Pinnacle Studio

On the timeline of your movie or disc project, audio clips behave very similarly to clips of other types, but the timeline also has some features just for audio.



In this group of timeline toolbar buttons, the highlighted buttons are audio-related: Audio Mixer, Create Song, Voice Over, and Audio Ducking.



At the right-hand end of the toolbar, these buttons activate audio keyframing (left) and audio scrubbing (right).

For instance, the timeline toolbar includes a button for a pop-up audio mixer and a button for controlling clip dynamics with keyframes. One button lets you create a ScoreFitter background music clip; another in the same group lets you record a voice-over. Further along on the toolbar is a toggle button for audio scrubbing; which allows you to monitor audio in brief snatches as you drag the scrubber along the timeline.

The Library

Audio and music clips enter your productions via the Library, which handles audio files in wav, mp3 and other standard formats. When you want to add audio files to your production, you can do so by dragging the desired asset from the Library Browser directly onto the timeline of your project.

Corrections and effects

The correction tools in the Audio Editor let you apply various repairs and customizations, including noise reduction, compression and equalization, to audio clips in your project. Unlike effects (discussed next), these tools can also be applied to audio assets in the Library.


When you later use the asset in a project, the corrections will come with it; you can modify them further from the timeline if you choose. Corrections are non-destructive, meaning that the corrected audio file is not modified in any way.

The effects in the Audio Editor provide a number of ways of enhancing, transforming or having fun with sound clips on the timeline. Unlike the correction tools just discussed, effects can't be applied directly to Library assets, but only within a project. The effects come with preset parameter combinations that you can further edit according to your needs.

The Audio Editor

The Audio Editor provides tools for previewing, analyzing and manipulating digital audio from wav, mp3 and other file types. It includes special features for the original or synchronous audio track created during video recording.

For the general interface of the Audio Editor and the other media editors, please see Media editing overview.



Trimming and editing the stereo soundtrack of a Library video asset. At left is a video monitor panel and the channel mixer. The darkened portion of the waveform (center) represents material removed from this stereo sound by trimming on the timeline at bottom. The Compressor correction filter has been applied (right).

The Audio Editor provides two sets of tools for different purposes. These are Corrections and Effects. Corrections are available both for Library assets and for clips on your timeline of your movie or disc project. Effects are available for timeline clips only.

Corrections

When opened from either the Library or the timeline, the Audio Editor provides access to a suite of correction tools for overcoming common flaws such as excess sibilance in recorded speech. If you are editing a Library asset, any changes you make will be preserved when it is later

used in a project. Changes to a clip on the timeline, however, have no impact outside the project to which they belong.

For information about opening the Audio Editor to access the correction tools, along with general functions of the media editors, please see “Media editing overview” on page 128. The transport and marker controls are the same as for editing videos, and are described in “Video tools” on page 144. For descriptions of the audio editing tools themselves, see “Audio corrections” on page 251.

Effects

As just mentioned, when the Audio Editor is opened from the timeline, it provides a set of correction tools whose main purpose is to repair defects in media. These tools can be applied directly to assets in the Library as well as clips in the project.

With timeline clips only, the Audio Editor also provides a set of audio effects. These afford a wide range of possible ways to adjust or enhance your clips. Please see “Audio effects” on page 256 for details.

Channel mixer


The channel mixer allows you to make level adjustments and redirect audio signals from their original channel assignments to new ones. For instance, you can use the mixer to condense separate stereo channels to a left or right mono channel.

The mixer panel originally opens in the left-hand column of controls, but can be dragged to a new docking position at either side of the window. Other panels will reposition themselves as needed while you drag.

If you need functions the channel mixer does not provide, consider applying the Channel Tool effect to the clip. See “Audio effects” on page 256 for information about the Channel Tool.

Level adjustment: Click on the slider under the level meters to set the playback level of the clip. The level you set will be used whenever this clip is played or used in a timeline. The red area on the meters represents overmodulation of the sound and should be avoided if possible. To determine the maximum level you can safely use, click the normalize button.

Channel routing: This dropdown list contains all options for redirecting audio signals, such as a channel exchange (left interchanges with right, for example), or combining a two-channel stereo signal onto one mono channel. The 1:1 routing option routes the audio signal without changes.



Selecting a Channel Routing option in the Channel Mixer. Just above the list is the Level Adjustment slider (at the default setting of 0dB). To the right of the list is the Normalize button.

Normalize button: The normalize button examines the audio samples in the loaded sound to determine the amount of uniform increase that

can be applied without overmodulation (harsh digital clipping) of any sample. Unlike compression and limiting, which modify the dynamics of audio material, normalization preserves dynamics by uniformly increasing (or decreasing) amplitude.

Waveform graph and frequency spectrum

The waveform The waveform graph of the audio is shown in the central display. It shows statically how the amplitude of the sound changes with time. If you zoom in on the sound as far as possible, the vertical lines on the graph indicate individual sound samples. The waveform graph is also seen in the Library ('source') Player when an asset is selected.



The waveform graph shows the change in audio levels over time. For stereo recordings, the graph is horizontally divided as shown here, with the left channel uppermost.

An alternative, dynamic view of the same audio material is given by the frequency spectrum display, which shows the changing spectral composition of the sound as it plays back.

The **waveform** and **frequency** buttons at the lower right of the Audio Editor let you switch between these complementary displays at will.



The frequency spectrum breaks down the audio signals by frequency bands, showing the sound level in each band. Lower frequencies are on the left. Peak levels are shown as a small box above each main bar for which a peak has been detected in the past few seconds.

Controls for synchronous video

If you are editing video that has a synchronous audio track, both video and audio editing facilities are available through the Video and Audio buttons at the top of the window. While you are in the Audio Editor, a video monitor panel is also available.


Video / audio switch

If video is available, a tab is provided at the top left of the screen for switching to the Video Editor. For details on the controls available when the Video tab is selected, please see “Correcting video” on page 143.



Video monitor

If synchronous video exists for the currently-selected audio, a small video preview panel opens at the upper left of the Audio Editor. While you are previewing the sound, the video monitor lets you follow the action visually as well. If you switch to the Video Editor, you will see a waveform display panel at the same screen location. See “Correcting video” on page 143.



Audio corrections

The correction facilities in the Audio Editor are Equalize, Compressor, Expander, De-esser and Noise reduction. Each can be applied both to Library assets and to timeline clips.

Equalize

Equalizers are similar in principle to the treble and bass controls of an audio system, but with finer adjustment capabilities. This equalizer divides the audio spectrum into five frequency bands, each centered on a specified frequency and with a settable amount of gain.

Preset list: A number of fixed presets can be selected from the dropdown list; for example, you can select a ‘telephone voice’ effect.

Gain: Using the Gain parameter, you can determine the amount that the respective frequency band contributes to the overall sound (from -18 to +18).



Settings and presets for the Equalize and Compressor audio corrections. Most Expander settings (not shown) are the same as those of Compressor. See the description for details.

Frequency: Using the Frequency parameter you can specify the center frequency of each band.

LoCut and HiCut: These controllers completely eliminate frequencies below or above a set value. The default values allow all frequencies.

Adjustments

The only parameter available under the Adjustment tool the is LFE (Subwoofer), which lets you either activate or deactivate the Subwoofer channel for a particular clip, or to stay with the Library's setting, determined on import.

Compressor

A compressor smooths the dynamics instant by instant in an audio signal, scaling back the loud sections while typically boosting the overall sound. This gives the impression of a stronger signal, even though the level peaks are not higher after compression than before. Light compression is very commonly applied in audio mastering of music tracks. Compression can also be used creatively in numerous ways depending on the material.

Preset list: Choose from a number of premade parameter sets for the compression filter.

Ratio: This control sets the compression ratio, which is the amount of compression applied to sections of the input signal that exceed the Threshold setting. For example, a 2:1 compression ratio means that a 2 dB increase of source level above the threshold produces only a 1 db increase in the output level. The allowed range is from 1:1 (no compression) up to 100:1 (hard limiting).

Threshold: All levels above this setting are attenuated by the value set in Ratio. You can apply an overall boost with the Gain controller to compensate for the level lost.

Attack and Release: Attack governs how quickly the compressor responds to an audio signal that has crossed the threshold. Larger values delay the onset of compression, allowing (for example) the brief attack of a piano note to remain distinct, while applying compression as usual for sustained sounds. Release controls the speed with which compression is switched off when the signal falls back below the threshold.

Gain: It is best to make adjustments to the gain after it has already been compressed.

Knee: A higher knee value causes compression to take hold gradually as the threshold sound level is approached and departed from, rather than switching on all at once. This changes the tonal qualities of the compressed sound.

Expander

The Expander decreases the gain of signals that fall below a chosen threshold. Expanders provide a gentler way of reducing noisy low-level signals than the abrupt cut-off of a gate.

Ratio, Threshold, Attack, Release: These parameters have the same meanings as in the Compressor (see above).

Range: This controls the maximum gain reduction (attenuation).


Hold: This determines how long the expander remains active after the initial attack. Increasing this value is useful when, between louder signals, there are small pauses or much quieter passages that should not be amplified. In this use, the expander works like a noise gate.

De-esser

This audio filter inconspicuously removes distracting sibilance from recorded speech. The available parameters allow individualized fine adjustment of the effect.

Frequency: This knob sets the frequency above which the De-esser is deployed.

Range: This knob controls the maximum attenuation that will be applied to the detected sibilance.



Setting and presets for the De-esser and Noise Reduction audio corrections.

Noise reduction

Using the noise reduction filter you can reduce or eliminate undesirable background noise. The filter reacts dynamically to changing amounts and kinds of noise within the material.

Noise reduction can be applied for a range of problems. The results obtained may differ, however, depending on the source material and the origin of the problem. In many cases the results can be optimized through targeted use of the Level and Fine Tuning parameters.

Since a new setting may take a few seconds to go into effect, make changes slowly and in small steps, carefully auditioning each change.

Level: Outdoor video recordings in which the subjects are far from the microphone frequently suffer from excess background noise. It may even be enough to obscure sounds of interest, such as the subjects' voices. Under the same conditions, the operating noise of the camcorder itself, or the words of its operator, may be amplified to an off-putting degree. Experiment with the Noise reduction level until the best possible results for the source material have been achieved.


AutoAdapt: While this option is active, Noise reduction automatically and dynamically adapts to the type and amount of noise in the material. The **Fine tuning** option is ignored while **AutoAdapt** is selected.

Fine tuning: This controls the amount of correction. Its effect is only significant when lower Level settings are used, and it has no effect at all when **AutoAdapt** is active.

Remove wind: Select this check box to activate a filter that reduces wind and similar background noises in the current audio.

Audio effects

Audio effects, like video effects, are found in the Library under the Content branch. One way to add an effect to your project is to drag it from the Library onto any audio clip (including video clips with synchronous audio).



Adding the Grungelizer audio effect to the current clip.

Usually, though, effects are added with the help of an Effects panel in the Audio Editor, which lets you easily preview and customize them. The panel is available whenever you are working on timeline clips with audio. The panel is not available when you open the Audio Editor from the Library. (In contrast, the tools on the Audio Editor's Corrections panel are always provided.) See "The Audio Editor" on page 245, and "Audio on the timeline" on page 259 for details.

The overall interface for audio effects is exactly the same as that for video effects. The common features are not covered here. (See "Chapter 5: Effects" on page 151.) A few audio effects, such as the Equalizer and the De-esser, double as correction tools. These are covered under "Audio corrections" on page 251. Let's now take a look at the other audio effects.

Channel tool: The basic action of this effect is to route your stereo audio signal. It allows you to connect either or both of the left and right input channels to either or both of the output channels. In addition, channel tool offers special-purpose presets, including phase reverse and voice removal – the 'karaoke' effect.

Chorus: The Chorus effect creates a richer sound by repeatedly reintroducing 'echoes' into the audio stream. By controlling properties such as the frequency with which the echoes recur, and the decay in

volume from one repetition to the next, a variety of results is possible, including flanger-like sounds and other special effects.

Grungelizer: The **Grungelizer** adds noise and static to your recordings. It can make your clips sound as though you were hearing them on a radio with bad reception or a worn and scratched vinyl record.

Leveler: This effect helps compensate for a common problem in recording audio for video productions: the imbalance in the recorded volume of different elements in the original audio. For instance, your commentary as you shoot the video may be recorded at such a high level that it overwhelms other sounds at the location.

The trick in using the Leveler is to find a target volume somewhere between that of the loud and soft audio in the original clip. Below that volume, Leveler increases the original level by a fixed ratio. Above the target volume, Leveler acts as a compressor, reducing the original level. With careful adjustment of the parameters, the internal balance of the audio can be significantly improved.

Reverb: The **Reverb** effect simulates the effect of playing back the source sound in a room of a given size and sound reflectivity. The interval between the arrival of the original sound at the listener's ears and the first echoes is greater for a large room than a small one. The rate at which the echoes die away depends on both the room size and the reflectivity of the walls.

The presets for **Reverb** are named for the type of room they simulate, from the passenger cabin of a car all the way up to a huge underground cavern.

Stereo echo: This effect allows you to set separate delays on each of the left and right channels, with feedback and balance controls to provide a variety of interesting sounds.

Stereo spread: This effect allows you to decrease or increase the apparent width of the stereo listening field in an audio clip. Most often it is used to create a mix that sounds more open and spacious.

Audio on the timeline

The audio levels and stereo or surround positioning of individual clips can be adjusted directly on the timeline using audio keyframing. The same operations can also be accomplished with the Audio Mixer control area, which pops out to the right of the timeline header when you click its access button. Both methods have their own advantages. Making the adjustments on the timeline gives a good sense of time versus volume or balance, whereas the Audio Mixer, in combination with the Panner, facilitates mixing – separately adjusting the volume and balance of each audio- containing track.

Surround sound

The Panner tool is fully surround-capable. For maximum flexibility, you can position any clip’s audio as desired in a two-dimensional listening field – from front to rear as well as left to right.

If you mix the audio for every clip as though for surround playback, you can still output a movie file with a stereo soundtrack using just the left-right balance information. If you further decide to output your project on DVD, the 5.1 surround-sound production will already be complete.

Timeline audio functions

Along with the track management functions, the header area of the timeline is also home to a number of audio controls.

Master playback level

Below the timeline track headers is a master playback level indicator. As you preview your project, it shows the total output from all tracks as currently mixed.



Below the timeline track headers is a master playback level indicator.


Audio mixer

The **audio mixer** pops out to the right of the track headers when you click its access button in the timeline toolbar. For each timeline track, the panel provides two sliders.

Track level: The upper slider sets the output level of the track as a whole. You can restore the default value by double-clicking the slider—no overall change is applied to the original volume of the clips on the track.

Clip level: The lower slider sets the level of the current clip at the scrubber position. If no clip is currently selected on the track, this slider is unavailable. The volume contour of a clip can be controlled with keyframes, as discussed immediately below. When keyframing is in use,

the slider level causes new keyframes to be created or existing ones to be repositioned.



Click the diamond icon for the audio track to activate audio keyframing.

The Panner




This tool lets you regulate the apparent location of the sound source in relation to a listener within a 'surround' listening field.

Like the clip volume tool it works with keyframes assigned to the clip, and so is active only when the timeline scrubber is positioned on an audio clip or a video clip with synchronous audio. The contour line for panning changes is drawn in blue.

For the purposes of timeline editing, all panning occurs in surround mode, so you only have to deal with a single version of the Panner controls. The surround-panned clips can be mixed down to other output configurations after editing of the project has been completed. This lets you work with a single set of panning decisions for all formats you might eventually produce.

Changes made with this tool apply to the current clip only. They stay with the clip even if you move or copy it to another track.

To open the Panner, click grid icon in the track header mixer panel. This button is grayed if there is no clip on the track at the scrubber position. The sound source is denoted by a blue spot on a two-dimensional grid. The listener is situated in the center, facing forward.



Positioning the clip audio using the Panner in Dialog mode. Note that the icons for the front corner speakers are translucent, indicating that they are not used in this mode. As adjusted here, the audio for the track will be heard coming from the right.

Selection list

The dropdown list at the top of the Panner window provides three methods for distributing the sound across the set of six surround speakers.

5.1 is the best general purpose setting for natural sound reproduction. Use it for general atmospheric sounds, such as barking dogs, or cars passing by. The five main speakers are represented by icons in the work area. The sixth, the LFE (low-frequency effects) speaker, is too low-

pitched to provide positional cues. Its level in the surround mix is controlled by a slider beneath the work area.

Center channel off is the preferred setting for an immersive music track.

Dialog mode combines the center speaker with the two at the rear. This combination is suitable for dialog involving multiple speakers.

Work area

The main body of the Panner window schematically depicts a listening area with a typical arrangement of loudspeakers. The cross icon in the center of the area indicates the position of the listener.

A blue control point sets the position of the sound source. The speaker symbols at the edge of the work area show your typical surround 5.1 speaker arrangement, with the screen at the top.

If you want to control the sound source position in one dimension, horizontal or vertical, use the slider at the bottom or right of the work area respectively.

LFE channel: Surround supports a special subwoofer channel (the '.1' in '5.1') that allows you to boost or cut the lowest frequencies for special effects. Control the LFE enhancement with the slider under the work area. Since the ear is unable to pinpoint the location of these low-frequency sounds, the LFE is not assigned to a spatial position.

Keyframe buttons: The keyframe buttons at the bottom of the panel allow you to add, remove and navigate between keyframes. The Add symbol automatically switches to Delete if you are positioned on an existing keyframe's position.

Audio creation tools

The Movie Editor provides two authoring tools that allow you to build your own soundtrack rather than depending solely on Library- supplied media. Both tools are accessed with buttons on the toolbar above the timeline of your project.

ScoreFitter is Pinnacle Studio's resident composer. You can use it to generate either incidental music or a full background scores for your production. ScoreFitter music clips can be of any desired length, and take only seconds to specify and create in the style of your choice. By default, a ScoreFitter clip exists only within your project, but you can also save particular music selections to the Library for re-use.



Just above the timeline in the project editor, the ScoreFitter button (under the mouse pointer) and voice-over button (far right) provide access to tools that let you author new audio material.


The voice-over tool lets you record live material – vocal or otherwise – using a microphone attached to your computer. Its most common use is for voice-overs and narrative tracks, but you can record any sound at all, providing it can be produced on cue. The tool creates an audio file that is automatically imported to the Library then added to your project at the scrubber location. The clip is added to the special voice-over track rather than the current track as with other media types.

ScoreFitter



Pinnacle Studio's ScoreFitter automatically creates background music in the category of your choice. Within that category, you select one of several songs, and within

that song, any of a number of versions. The list of versions available also depends on the duration of background music you specify.



The ScoreFitter window. Select a Category, Song, and Version, then click the Add To Movie button.

To create music for a particular set of clips, select those clips before clicking the **Create song** button to open ScoreFitter. (To select your whole movie, use **Edit > Select All** or press **Ctrl+A**.) The total length of the selected clips will determine the initial setting for the music duration, but you can modify the value at any time by trimming the clip on the timeline or by editing the Duration counter in the tool.

In ScoreFitter, choose a category, song and version from the lists provided. Each category offers its own selection of songs, and each song its own selection of versions. Use the Preview button to audition the song while the tool is open.

Enter a name for the clip in the Name field and adjust its duration with the Duration counter, if desired. The music clip you create will be adjusted to fit exactly the duration you select.

When you have made your choice, click the Add to Movie button. Studio creates the new clip on the active track beginning at the current time index (as shown by the timeline scrubber and the preview frame in the Player).

Expanding your song collection

ScoreFitter songs come in collections called 'libraries'. The Standard library, which is included with Studio, includes more than 40 songs in styles ranging from Folk to Electronica. Additional libraries may be purchased from within Studio as they become available by clicking the Get More button.

The Voice-over tool



Recording a voice-over in Studio is as easy as making a telephone call. Just open the Voice-over tool, click Record and speak into a microphone attached to your computer.

You can narrate as you watch the movie play so that your words match the action on the screen. You can also use the tool as a quick way of capturing ambient music or home-made sound effects via your microphone.

Before you can record audio using the Voice-over tool, you will need to connect a microphone to the input jack of your PC sound board. Review the video scenes in your movie and decide where you want the voice-over to begin and end. When you are ready, open the Voice-over tool.

Select your starting point on the timeline of your project. You can do this by selecting a clip, playing the movie and stopping it at the desired point, or by dragging the timeline scrubber.

Position the microphone for use and try speaking a test phrase to check your recording level (see “Voice-over level” below). When you are satisfied, click the Rec button (which toggles to a Stop button during recording).

A three-second countdown is displayed, then your movie begins to run in the Player. Perform your narration, and click the Stop button when done.

Now you will be asked if you want to keep the recording. If you answer in the affirmative, the voice-over clip will be added to your Library and will also be placed automatically on the voice-over track on the timeline.



The Voice-over tool, ready to go. Just click the Rec button, count to three along with the software, then start talking.

Additional controls

Voice-over level: As you record, watch the peak level meter display to make sure that your microphone is generating a strong signal but not overmodulating. Watch this meter to make sure your recording levels

get neither too high nor too low. The indicator changes color from green (0-70% modulation), through yellow, to red.

Filename: With this text field you can preset the file name used for voice-over audio files. The first file is given the name you specify; if you leave it unchanged, later files are given a numeric suffix – e.g. ‘Voice-over (1)’ – that increases with each take.


Location: Clicking on the folder icon lets you navigate to a new file system folder for storing voice-over clips.

Adjust the recording level slider as necessary to stay in the right range. The slider is located immediately below the peak meter. Generally, you should try to keep your audio peaking in the yellow (71-90%) and out of the red (91-100%).


Mute all audio: The existing sounds on your movie soundtrack are sometimes distracting when you are trying to record a voice-over. This check box allows you to switch off timeline audio completely during recording.

Using Audio Ducking to automatically adjust volume


Audio ducking is used to automatically lower the volume of one track so that you can hear another track better. For example, if you have a video project that includes music and voiceover, you can use audio ducking to automatically decrease the music volume when the narrator is speaking. You can adjust the threshold that triggers “ducking” and you can adjust by how much the volume of the background track will drop.



To apply Audio Ducking

- 1 In the Timeline, select the track that you want to “duck” (to selectively lower the audio level), and click the **Audio Ducking** button  on the toolbar.
- 2 In the **Audio Ducking** dialog box, choose the main track that you want to hear from the **Master Track** box.
- 3 Adjust the following sliders:
 - **Ducking Level** — determines the volume decrease. Higher numbers result in a lower volume.
 - **Threshold** — determines the master track volume level that will trigger a volume decrease for the other track(s). You will likely

need to experiment with different settings to achieve the results you want.



In this example, the top track is a voiceover track that was set as the Master Track. Ducking was applied to the music track on the bottom to selectively lower the music volume whenever the narrator was speaking on the voiceover track, as indicated by the blue waveform. The green line represents the volume level and shows where the volume changes occur.

To remove Audio Ducking

- In the Timeline, right-click a track that has **Audio Ducking** applied, and choose **Remove Ducking**.



With the advent of DVD, Blu-ray and AVCHD discs, video technology has developed into an interactive medium that gives both the videographer and the audience new possibilities.

In a disc project you can go beyond the old idea of creating a movie to be viewed in strict sequence from beginning to end. Now the audience themselves can decide which parts of the production to view, and in what order.

Disc authoring is the process of designing and creating the structure that allows this interaction. Pinnacle Studio provides automated features that make authoring easy while still giving you full control.

If you want to create a disc quickly by using a preset template with menus and music, you can export your project directly to a MyDVD[®] file. For more information, see “Output to a MyDVD file” on page 364.



The Disc Editor in Pinnacle Studio. Here, one menu has been added to the Menu List, and is now available for use. The Player (top right) in this window provides a special mode for editing the behavior of menu buttons.

Your disc project can begin in the Disc Editor, using the same controls and techniques that you would in the Movie Editor, or you can import a movie project into the Disc Editor to add a disc menu to it. Please see “Chapter 3: The Movie Editor” on page 59 for information on how to construct a movie.

The upper part of the Disc Editor screen includes two functional areas: the Compact Library, from which disc menus and other resources are drawn; and the Player, where you can preview menus and other media and edit menu interactions.

Next below these is the timeline toolbar, with all the controls from the Movie Editor, plus the additional controls necessary for creating disc menus. The area below the timeline toolbar is shared by three separate navigation tools: the Menu List, where the your project’s menus are stored, the Navigator, and the Storyboard.

Only one of the Navigator, the Storyboard, and the Menu List can be visible, or this area can be hidden altogether. The Navigation tool selector, near the left end of the timeline toolbar, controls this area. Under the navigation area is the timeline for the media that will be the primary content of your disc. All use the full width of the window.



Disc menus

The essential feature that makes disc authoring possible is the menu. A particular disc may have one, a few or many menus, each consisting of a still image or a short video loop. Areas within the menus, called buttons, can be selected by the viewer to activate other content on the disc.

Some buttons cause playback to resume from specified locations, called chapters, on the timeline of your production. These chapter buttons often show a thumbnail frame or video loop as a clue to their content. If a return marker is encountered during playback, it will send the viewer back to the menu at that point.

Other buttons cause a transfer to another menu, or to another page of the same menu. Multipage menus, with each page displaying several chapter buttons along with automatically-managed navigation buttons, facilitate productions of almost any size. However, there is a limit of 99 on the total number of chapters and return markers allowed in a single production.

The Menu List

Unlike timeline clips, the menus in your production are not bound to a particular time offset. Instead, a disc player will loop the menu until user interaction is received.

Because menus exist 'outside of time', Pinnacle Studio provides the Menu List, a special area above the Disc Editor timeline to accommodate the menus in your project. Dragging a menu from the Library into the Menu List makes it available for use in your project.

Designing menu interactivity

A disc production may contain just one menu, or it may have many. Each menu contains graphically distinct areas, generically called 'buttons', that can be activated by the viewer, perhaps using the navigation keys on a DVD remote control.

The behavior of disc menu buttons can be set up using controls in the Disc Editor window. Alternatively, you can invoke the Chapter Wizard to create and configure a set of buttons automatically according to your chosen settings.

Activating a button either starts your movie playing back from a chosen point, or transfers control to another menu with its own buttons. The possible targets for menu buttons are:

- **A timeline location:** Upon activation, playback resumes from a chosen frame. The location, and the content found there, are referred to as a 'chapter' of your movie.
- **Another menu:** Buttons can link to any menu in the Menu List.
- **Another page of the same menu:** Multipage menus always include next and previous buttons for navigating between their pages.

Automatic page creation

As you insert new chapter links into a multipage menu, additional pages are created automatically as needed. These appear in the Menu List alongside those already in the project. A connector graphic links pages belonging to the same menu. To insert new linked chapters, use either the Insert Link button on the toolbar, or the Chapter Wizard.



A main menu and its matching multipage menu in the Library Player.

Next and Previous: It is the presence of the special next and previous buttons that causes a menu to support the multipage behavior. To create a multipage menu from an existing main menu, simply add buttons of both these types. Likewise, deleting either or both of the next and previous buttons from a multipage menu removes the automatic features.

Multipage menus in the Menu List

The icons of multipage menus are connected in the Menu List by a special graphic. It shows that the menus are linked, which is to say that you can navigate from one page within the menu to another by means of the next and previous buttons.

Splitting and joining: To unlink neighboring menu pages from each other, click the connector graphic between them. The graphic is removed. Pages to the left of the mouse remain with the original menu, while those to the right form a new, separate menu (with a new background color for its menu icons). Click in the gap between neighboring multipage menus to regroup them into a single menu.

Sorting chapters: A time-saving tool meant primarily for multipage menus is the sort button that appears with the Chapter Wizard button to the right of the menu's last page. When you have been working on a menu for a while – adding, deleting and rearranging chapters, perhaps even while editing the movie itself in parallel – you are likely to find that the chapter buttons are no longer in timeline order across the set of pages. Unless you want a custom order for some reason, the remedy is a single click on the sort button.



Pages from a multipage menu. The connector graphic shows that navigation within these pages is provided by Next and Previous buttons. The Sort button (top right, under pointer) arranges the chapter buttons in timeline sequence.

Adding disc menus

The disc menus section of the Library contains a collection of menus for a variety of occasions and in a spectrum of visual styles. Each menu comprises a background picture, a text title, and a set of navigation buttons appropriate to the menu's purpose.

To add a disc menu to your production, open the Compact Library in the Disc Editor, choose a menu in the Disc Menus (under Content), and drag it to the Menu List. To edit the actions assigned to the menu's buttons, you can use the authoring tools provided on the timeline in conjunction with the Player, or get some automated help from the Chapter Wizard. To modify the appearance of a menu (or create one from scratch) you will use the Menu Editor.

Menu types

Each menu design in the Library has two variations: **main** and **multipage**.

Main menu: In most productions, the first menu seen by the viewer is of this type. Main menus usually contain buttons with the default captions Play Movie and Scene Selection; you can change these if you like. Although the buttons' link targets are also up to you, it helps your audience if you stick to convention. For instance, the Play Movie button is normally configured to start playing back your movie from the beginning, and Scene Selection typically switches to a subsidiary menu, one with links to the 'chapters' of your movie.

Multipage menu: A scene selection menu often needs to provide more of these chapter buttons than will fit on a single screen. To solve this problem, Pinnacle Studio supports multipage menus, which have additional buttons just for navigation between menus. The behavior of these buttons is built in. A pair of next and previous buttons lets the view move between pages within the same menu; while a home button causes a transfer to the project's first menu.


Tip: To display the main menus side-by-side with their matching multi-page menus in the Library, right-click in the gray area next to a menu and choose **Sort by > Name**.

Menu buttons

The number of chapter buttons per page varies from one menu design to another, so one criterion for selecting a menu is the number of clips you want it to handle. But if you want a different number of buttons on a particular menu, you can add or delete buttons in the Menu Editor, which is launched by clicking the Edit button on the Player. See “The Menu Editor” on page 289 for details.

Menus with fewer buttons usually have more space for captions; those with many buttons will have to settle for abbreviated captions or none at all. Whether you need captions, and if so whether they should be simple (“Chapter 1”) or descriptive (“Cutting the Cake”) is a matter of your authoring style and the content of your movie.

Unlinked menus and buttons

Only the first menu in the Menu List is automatically available to the user (and then only if there is any content on the timeline to serve as the initial chapter). Menus added later do not become part of your production’s menuing system until you link them with the first menu. The link may be indirect, involving one or more intermediate menus, but until it exists the menu is an unreachable island. Such a menu is indicated by the symbol  in the bottom right-hand corner of its Menu List icon thumbnail.



A special indication is also given in the Player for menu buttons that have not yet been linked either to a timeline location (a chapter) or to another menu. A linked button shows which chapter (e.g. ‘C1’) or

menu (e.g. 'M1') it connects to. An unlinked one shows a question-mark icon instead. (If the button indicators are not visible, click the show/hide chapter numbers check box below the Player.)



Previewing disc menus


The Disc Editor, like the Movie Editor, includes a Player for previewing Library assets and timeline clips. For a general introduction to the Player, please see “The Player” on page 14.

The special functions provided by the Player when viewing menus in the Menu List are described here. Clicking a menu in the Menu List puts the Player into Menu input mode and previews the selected menu. You can also switch to that mode directly while any menu is selected by clicking the Menu tab above the Player screen in the Disc Editor.


Special controls also appear at the bottom of the Disc Editor Player.





Menu **Edit** button: Creating or modifying the design and layout of disc menus is the task of the Menu Editor.



With Menu selected as the Player input mode (top), the Player provides interactive zones on the preview screen for assigning chapter links. Here 'C1' shows a chapter link has been assigned to the Play Movie button; the '?' over the Scene Selection button shows that it is not currently assigned.

Show Link Numbers checkbox : Check this box to cause link numbers to be displayed in the preview over every button in the menu. The link numbers match the format and color of the timeline chapter flags.

Disc Simulator button : This button invokes the Disc Simulator window where you can preview your project with full interactivity to make sure your menus are behaving as expected.

Burn Disc button : When you are ready to test your project on an actual disc, click this button (or Export at the top of the screen) to invoke the Exporter, which will guide you through the process of 'burning' your movie onto an optical disc.

Link indicators

As seen in the illustration above, when a menu with unlinked chapter buttons is previewed, those buttons are indicated by red question marks rather than a chapter number. Except perhaps for an unused subset on the final page of a multipage menu, all the chapter buttons on your menus should link to your movie.

Menu editing on the timeline

Developing a project for optical disc, such as DVD, in Pinnacle Studio's Disc Editor gives you lots of opportunities for putting your creative stamp on the production.

Every aspect of a disc menu – the details of its visual appearance, the linking of its on-screen buttons, the precise timing of its 'chapters' – can be edited in Pinnacle Studio. For the visual aspects, you will turn to the Menu Editor, but the linking of buttons and the timing of chapters are both controlled within the Disc Editor itself.

For an overview of the Disc Editor interface, please see "Chapter 9: Disc projects" on page 271.


Timeline menu markers

The chapter buttons on a disc menu can be individually linked to any point on your movie's timeline. In the Disc Editor, those points are indicated on the timeline by chapter markers on the Chapter Track, which is a specialized timeline track that materializes above the other tracks when a first menu is added to your movie. (The track is removed again if all menus are deleted.) The caption of a chapter marker consists of the letter 'C' followed by the chapter's sequence number in its menu.

Return markers, which mark automatic exit points from the timeline back to a disc menu, are also shown in the Chapter Track. The caption of a return marker is the letter 'M' with the sequence number of the target menu.

Regardless of the length of your production, you are limited to a combined total of 99 chapter buttons and return markers.

The color of chapter and return markers matches the Menu List icon color of the menu to which the markers are assigned. Markers can be repositioned on the timeline by dragging. See “Timeline editing of chapter and return markers” on page 285 for details.



Dropping a menu onto an empty Menu List causes a chapter marker to be inserted at the start of your movie's first clip (provided it has one) as the target of the menu's Play Movie button. A return marker, marking an exit back to the menu, is placed at the end of the movie.

Authoring tools

In the Disc Editor, the timeline toolbar provides a number of authoring tools that you can use directly without switching windows or views.



Tools on the Disc Editor toolbar.



Create link: This button links the currently-selected chapter button in the Player to the location of the timeline scrubber.



Insert link: This button facilitates work with multipage menus by moving all existing button links (starting at the currently selected chapter button in the Player) one position towards the end.

In a multipage menu, the act of inserting a link may begin a chain reaction by forcing an existing link onto the next page, a link from there onto the page following, and so on to the final page, which itself will be created if necessary.



Remove link: Clicking on this button will remove the link that exists between the button on the menu and the chapter marker on the Chapter Track. An 'unlinked' chapter marker will remain on the Chapter Track. This unlinked chapter can be manually linked by drag-and-drop to another button on the Menu Preview, or it may remain as an unlinked chapter, in which case, during playback, it will work to jump through your disc using the jump button on your remote control. You may also right-click on one or more chapter markers and choose Remove Selected Link.



Button cycle: By clicking on the left and right arrows of this control, you can scroll through available buttons and make them active for editing. Click on the button caption to edit it. Buttons also may be selected by clicking the button links in the Player when a menu is previewed.



Set thumbnail: Clicking this button generates a thumbnail image of the frame at the timeline scrubber position, and displays it on the menu button selected in the button cycle control if it is of the Thumbnail type. For more information about menu button types, please see "Menu buttons" on page 289.



Create unlinked chapter: Unless the timeline scrubber is exactly positioned at a chapter or return marker, clicking this button will add a chapter marker to the Chapter Track, but will not link it to any menu. An unlinked chapter can also be created by double-clicking in the Chapter Track area just above the other timeline tracks.

The unlinked chapter can later be manually linked by drag-and-drop to a button on the Menu Preview if that's what you want. However, an unlinked chapter also serves a useful purpose in its own right: during playback, it designates one of the points to pause at when browsing a DVD with the jump button on the remote control.



Remove chapter: When the timeline scrubber is positioned at a chapter, the Create unlinked chapter button takes on the opposite function, and a modified symbol. Clicking on it will remove both the chapter marker and the link that binds it to a menu, if it has one. You can also remove chapters with the Delete Selected Chapter context menu command when one or more chapter markers are selected. To remove the links from chapter markers, leaving them unlinked but still on the Chapter Track, use Remove Selected Links from the same menu.



Create return: Unless there is already a marker at the timeline scrubber position, this button will add a return marker to the Chapter Track.

A return marker is active during viewing only if playback commenced from the same menu the marker is associated with. (On the timeline, the marker color should match that of the associated menu's icon in the Menu List.) When playback reaches the frame associated with an active return marker, it will jump back to the associated menu.



Delete return: If there is a return marker at the scrubber position, the Create return button converts to Delete return, with an appropriately changed symbol.

The Remove chapter button, and the Delete selected chapter context menu command, can both also be used to delete return markers.

Timeline editing of chapter and return markers

Chapter and return markers are tied to particular frames on your timeline at which playback will be launched from a disc menu (chapters) or at which playback again gives way to the originating menu (returns). Both types of marker can be dragged with the mouse to change the location at which they take effect in the movie.

When you are previewing a menu, dragging a chapter marker from the Chapter Track to a button on the Player will relink the button. The reverse operation, dragging a button from the Player to a point on the Chapter Track, is an alternative method of creating a new chapter marker.

A project that contains one or more disc menus must have a return marker permanently positioned at the end of the Chapter Track. This guarantees that any chapter played on the disc will encounter a valid return. The final return marker can thus not be deleted.

The Chapter Wizard


When a multipage disc menu has been dragged from the Library into the Menu List, a Chapter Wizard button is displayed at the top right corner of the menu icon. Clicking on this button will open the Chapter Wizard window.

Why use the Chapter Wizard?

The Chapter Wizard provides a fast way to create chapters for your movie. Chapter markers will be added to the Chapter Track on the Disc Editor timeline to show where each chapter begins. With the Link chapters to menu buttons option (see below), each chapter will be represented by one chapter button on a series of automatically-generated menu pages; these pages are linked into a series by next and previous buttons.



By activating chapter buttons when the menu is viewed, the viewer is able to play the movie from any of the provided starting points.



The Chapter Wizard is great for setting up slide shows and scene selection menus. If you are archiving video to disc, you can use it to generate a menu that will serve as a scene catalog. The series of menu

pages created can be arbitrarily long. Its length depends on how many chapters are created and on how many chapter buttons are provided in the menu's page design.

Incidentally, the Chapter Wizard does nothing that you could not do yourself using the available disc authoring tools within the Disc Editor (and they remain available for tweaking the generated menu afterwards). Its purpose is to speed your creative process by taking over much of the routine work that setting up a multipage menu entails.

Using the Chapter Wizard

The Chapter Wizard controls are grouped into three horizontal panels. When you have configured the controls to your satisfaction, click OK. The Chapter Wizard will carry out its work of creating new chapters for your production, complete with markers on the timeline and (by default) an automatically-generated set of menu pages with as many chapter buttons as necessary.

Place chapters at

This is the uppermost panel in the Chapter Wizard. The two options here can be used separately or together.

Optimal positions: When this box is checked, the Chapter Wizard creates chapters at a selected interval along the timeline, but will adjust the chapter to a nearby clip boundary when one is available. The desired average chapter length is specified in seconds. The initial value is based on the length of your movie. To adjust it, either click directly on the number and type, or drag horizontally within the text box.

Timeline markers: This option assumes that you have prepared timeline markers to indicate to the Chapter Wizard particular places in your movie to which a chapter link must be created.

Apply to

The second panel in the Chapter Wizard provides options that control the scope of the wizard's operation.

Whole movie: Chapter markers will be created throughout the entire movie.

Selection: Chapter markers will be placed only within the range from the beginning of the first selected clip to the end of the final one.

Options

The third panel offers two final choices, which may be set independently.

Link chapters to menu buttons: When this option is selected, as many pages will be added to the menu as are needed to accommodate buttons for all of the created chapters. Without this option, the chapter markers are created on the timeline in the 'unlinked' state, and no menu pages are created.

If you want to link an unlinked marker to a menu button, drag it to the button while previewing the menu in the Player. Even if you leave it unlinked, the chapter marker will still serve as an available resumption point when the viewer is skipping through the disc with the jump button on the remote control.

Return after every chapter: Checking this option will add a return marker at the end of each chapter. By default, the markers are placed so that each chapter will play up to the start of the chapter following, then return to the originating menu. To change the menu that a return marker is linked to, drag the marker to the menu icon in the Menu List. Remember, however, that the return marker will only be active when playback was launched from the menu to which the marker is linked.

The Menu Editor

The Menu Editor shares most of its controls and usage with the Title Editor (see “Chapter 7: The Title Editor” on page 201). The present section focuses on features particular to the Menu Editor.

Starting the editor

To open a menu in the Menu Editor, either click the **Edit** button on the Player while previewing the menu, or double-click it in the Menu List.

As with the Title Editor, when the Menu Editor opens, one line of text is already highlighted. To edit it, just start typing. To start editing a different line, click inside its text box and highlight the characters you want to change. To stop editing text, click on an empty area of the window.

The button cycle

One feature that differs between the Menu Editor and the Title Editor is the button cycle, a control also present in the Disc Editor. In both cases it is located on the right side of the toolbar, just above the timeline. Click the left and right arrows on the control to step through the active buttons in the menu, and make one available for editing.

Note: If you only want to edit text for the buttons on your menu, you do not need to enter the Menu Editor at all; instead, edit the button name directly in the button cycle control of the Disc Editor.

Menu buttons

Any visual element of your disc menu can be used as a ‘button’ that links to other content in your movie. Elements designated ‘Not a button’, on the other hand, have no linking behavior.

Button types

A menu button's type is the only factor that determines its behavior. Its text and appearance should almost always be consistent with that behavior in a well- authored disc production, but they don't affect it. Five button types are available.

Normal: This type of button lets your text, image or shape serve as a link to any chapter marker on your disc project timeline, or to a menu in your Menu List.

Thumbnail: This variation on the Normal button type allows a thumbnail from your timeline to be displayed on the button.

Previous and **Next:** These button types automatically handle navigation between the pages of multipage menus in the Menu List. During playback, the buttons are hidden automatically when their targets do not exist (on the first and last pages of the multipage set). Because their behavior is fixed, it is not possible to link these buttons to chapter markers.

Root: A button of this type links to the first menu in the Menu List. Its behavior cannot be changed.


Buttons for multipage menus

If you add both a **Next** and a **Previous** button to any menu, it can serve as a multipage menu. If either button type is absent, the menu cannot be used in the multi-page mode.

Button presets

Click the Buttons tab at the top of the Menu Editor to view the available categories of premade menu buttons. Select a button and it

will appear in the middle of the preview area, where it can be dragged to the desired position.



The three categories reflect the button types discussed above. The Navigation category includes all buttons of the Previous, Next and Root types.


General Buttons: These images are intended for use with Normal buttons, which may be linked to any chapter marker on your timeline.

Navigation Buttons: These designs are meant for Next, Previous and Root buttons with hard-wired navigation.

Thumbnail Buttons: These include a thumbnail area where a timeline clip can be previewed.

Button settings


The Button Settings panel is to the right of the Menu Editor preview.



The Button Settings panel is part of the Menu Editor.

The Disc Simulator

To preview your project after setting up its menus, click the play button at the bottom of the Player. This activates the Disc Simulator window.




When the Disc Editor Player is previewing a menu in your project's Menu List, a button (bottom center) is provided for testing your project in the Disc Simulator.

Provided the project is built correctly, the simulator should open at the main menu, with 'Play Movie' and 'Scene Selection' links ready for the viewer to use.

To move from link to link within the preview, use the DVD navigation buttons on the bottom right or click the links directly in the preview.

Take the time to verify all the chapter and menu links your production includes. Every desired user interaction should be checked: slip-ups are frustrating for the viewer, and easily avoided.



In the Disc Simulator, you use a control set similar to that found on a DVD remote control. Menu interactions and playback can be fine-tuned and fully tested before you burn the project to disc.

Once you are happy with the project, it can be exported as a movie file, saved to a disc image file, or burned to a disc. See “Chapter 11: The Exporter” on page 345 for more information.



Pinnacle Studio lets you incorporate many kinds of media into your video productions. When these are stored externally to your computer – on a camcorder tape, say, or a memory stick from your digital camera, or a cloud-based service – they must be transferred to local storage before you can use them.

This transfer process is variously called ‘capturing’, ‘importing’ or ‘downloading’, depending on the media involved and the method of transfer. Because most audiovisual recordings now are stored in digital form from the start, transfers can typically be achieved with no loss of quality. Only when transferring from analog or tape-based sources (e.g. VHS, Hi8 or DV tape) is there still a ‘capture’ process, often involving conversion to digital form. The terms ‘import’ and ‘importing’ can be used to signify all methods of bringing images and sound into the Library for use in your productions.

The file-based assets you can use in Pinnacle Studio – including video, photographic and audio media, and Pinnacle Studio projects themselves – must be imported from a source such as a local hard drive into the Library before they can be used. In most cases, importing is handled automatically using ‘watchfolders’. However, the Importer can also be used to import assets from local folders that are not set up as watchfolders.


The next step

After Studio has finished importing your assets, you will be able to access the imported files for use in your productions. For more information, see “Chapter 2: The Library” on page 17.

Using the Importer

The very first step in importing is to open the Studio Importer by clicking the Import button at the top left of the screen.

The Importer consists of a large central area surrounded by a number of smaller panels. One of these, the Import From panel at the top left of the display, has a pivotal role. It provides a list of device types that can serve as the source of your import operation. Your choice of input source in turn determines the rest of the Importer display. Above all, the set of controls and views offered in the central area for preview, browsing and selecting material depends on the chosen import type.



Studio Importer

Importing can be regarded as a four-step process:

- 1 Select the import source on the Import From panel.
- 2 Confirm or adjust the settings on the other panels.
- 3 Select material to import from the chosen source.
- 4 Initiate the import operation.

At this point Studio begins transferring the requested audio, video and pictorial material from the source device to your hard drive (if necessary), using the locations set in the Import To panel. The media are then immediately added to the Library. Once the import operation is complete, the Importer returns control to the prior screen, from which you can access the imported files through the Library. (See “Chapter 2: The Library” on page 17.)

Importing stereoscopic 3D content

Pinnacle Studio will recognize content as stereoscopic 3D and mark it as such for files with the following properties:

- **MTS:** MVC, SBS50, SBS100 (if H264 stream markers are present)
- **WMV:** Multistream, SBS50, SBS100, TAB50, TAB100 (if metadata tags are present)
- **MP4, MOV with H264:** SBS50, SBS100 (if H264 stream markers are present)
- **MPO:** Multistream
- **JPS, PNS:** SBS50, SBS100

If Studio has not correctly identified your 3D media, choose the correct setting from the Stereoscopic 3D dropdown in the Adjustments group of Corrections tools. Please see “Adjustments” on page 148 for details.

Importer panels

The actual selection of material to be imported takes place in the central area of the Importer. Each import source uses the central area somewhat differently.

Depending on the input source, the central area shares the Importer interface with up to five auxiliary panels with standardized functions.

The Import From panel


This is the top left panel of the Importer, a position that reflects its vital role in setting up the import operation.

The photos, music and video footage or projects you want to import may reside on a variety of device types and technologies. The supported import sources include:

- All types of auxiliary file-based storage media, including optical drives, memory cards and USB sticks (see “Import from file” on page 315). Click **My computer** in the **Import From** panel to select individual files for import from drives connected to the computer.
- Click **Scan For Assets** to import all files of specific types from a set of one or more directories.
- DV or HDV video cameras using an IEEE-1394 (FireWire) connection. See “Import from DV or HDV camera” on page 324. Devices are listed by name in the Import From panel by their device names (e.g. “DV Device”). Select the applicable one.
- Analog video cameras and recorders (see “Import from analog sources” on page 330). Any analog capture hardware on your system is listed by name (e.g. “Pinnacle Systems 710-USB”).
- DVD and Blu-ray discs. See “Import from DVD or Blu-ray Disc” on page 331.

- Digital still cameras. See “Import from digital cameras” on page 333.

Some sources in the Import From panel are chosen from a sub-list of actual devices that appears when you click the main source entry. In the illustration, DVD / Blu-Ray has been clicked. The user can now choose between the two DVD drives installed on this particular system.



Single-frame import


Studio provides two special modes for importing single frames, rather than continuous footage. These modes are:


- **Stop motion:** Create an animated film by importing one frame at a time from a live video source. See “Stop motion” on page 333.
- **Snapshot:** Import individual images from tape or from a live source like a webcam. See “Snapshot” on page 340.


Adjusting analog audio and video levels

Analog capture hardware may provide additional controls for modifying parameter levels of the audio and video signals. Such a

capability is useful for correcting exposure problems and the like in the source material, and when you need to compensate for differences in video from multiple sources.



To access the controls, select the analog source, then click the **more** button  beside the source name. This opens the Analog Input Levels window.



The Analog Input Levels window lets you adjust a number of video and audio parameters. The Hue slider (fourth from left) is not used with PAL sources.

Although you can also adjust these levels with the appropriate correction in the Video Editor, setting them correctly for capture can save you from having to worry about color correction later on.

Setting your audio options correctly as you capture will help in achieving consistent volume levels and quality.

Particular capture devices may offer fewer options than are shown and discussed here. For instance, with hardware that doesn't support stereo captures, an audio balance control will not appear.

Video: Choose the type of video you are going to digitize by clicking the appropriate source button (Composite or SVideo). The five sliders allow you to control the brightness (video gain), contrast (ratio of lightest to darkest), sharpness, hue and color saturation of the incoming video.

- The hue slider can be useful for correcting unwanted color shifts in NTSC material; it is not available when capturing from a PAL source.
- The saturation slider regulates the ‘color saturation’ – the amount of color – in the image. (An image with zero saturation has only black, white and gray tones.)

Audio: The sliders on the right side of the panel let you control the input level and stereo balance of the incoming audio.

The Import To panel


After importing from external devices, media items and Pinnacle Studio projects will be accessible as files on your own computer. The Import To panel of the Importer lets you specify where those files will be stored. Separate folders are available for projects, video, audio and picture items, but the Import To panel only lists those that are relevant to the current import source, as configured in the Import From panel.


As the number of media files and movie projects on your system grows, it becomes increasingly useful to give some thought to how best to organize the material into folders and subfolders such that in the future you can most readily retrieve any desired item. The controls on the Import To panel are designed to automate this process to whatever degree you choose.

Working with import folders

Until you specify otherwise, the Importer uses the standard document folders for video, music and pictures within your Windows user account, and a default folder for your Pinnacle Studio projects. The illustration shows a typical setup in Windows. To change an import

folder, click either the small folder button or the current folder path. (See “Selecting an import folder” on page 304.)




The folders you choose for each asset type, whether default or custom, serve as base locations for your imported files. In order to manage your file-based assets effectively, you can also specify either a custom subfolder name or a method of automatically- generating a name based on either the current date or the creation date of the imported material. Click either **set subfolder** or the **more** button  for the media type to access the subfolder options. (See “Setting a subfolder” on page 305.)

For example, if you set your main video folder to “c:\vid”, and your subfolder naming method to “Current month”, any video you import will be transferred to a folder with a name like “c:\vid\2012-10”.

Fill-level indicator: This bar graph shows for each import destination how much room is left on the storage device. The first part of the bar represents space already occupied on the device. The colored extension

shows how much room will be required by any currently-selected media files or project files awaiting import.




Available storage space display

Note: If a destination device reaches 98 per cent full during import, the operation is halted at that point.


Selecting an import folder


To choose a different base folder for a given asset type, click the corresponding folder button or folder name on the Import To panel. This opens a folder selection box where you can navigate to, and if necessary create, the folder you want to use.



Folders that contain subfolders are indicated with a plus icon to the left of the folder icon if they are currently closed, and a minus icon if they are open. Clicking the icon reverses the state of the folder.

Setting a subfolder

To designate a subfolder of the base folder as the actual import destination for the asset type, click either the set subfolder button or the more button . These buttons open a dialog window that represents an expanded version of the Import To panel, one that includes controls needed to set the subfolder name or the naming method for each asset type supported by the currently-selected import source.



The expanded Import To dialog window for file-based assets. Since files can be of any asset type, controls for all four types are provided. Most other sources import only video media, and don't show the Audio, Photo and Project controls.

The row of controls for each asset type includes a dropdown list of naming options:

No subfolder: With this option, the files you import will be stored in the base folder.

Custom: When you choose this option, an in-place edit box appears. Enter the name of the subfolder in which to store your next import or imports of the asset type.

Today: Your imports will go to a subfolder named with the current date, in the format “2012-10-25”.

Creation date: Each imported file will be stored in a subfolder named with the creation date of the asset, in the same format as above. When multiple assets are brought in as part of a single import operation, this may entail creating or updating multiple subfolders.

Current month: This is the same as the Today option but without the day portion, e.g. “2012-10”.


After making your choice, click the ‘x’ button at the top right of the dialog window to return to the Importer.

The Mode panel

The Mode panel of the Importer provides a place to adjust the options offered by several import sources.

DV / HDV import options

The options for DV and HDV import are in three groups on the Mode panel.



Presets: The Presets group offers two standard configurations for video and audio compression, and a custom setting that lets you fine-tune compression parameters in the Compression Options window, which opens when the upper more button ➤ is clicked. For more information, see “The Compression Options window” on page 310.

The fixed presets are:

- **DV:** This provides full-quality DV capture, using about 200 MB of disk space per minute of video.
- **MPEG:** MPEG compression produces smaller files than does DV, but requires more computational horsepower to encode and decode. This could result in slower performance on older computers.


Scene detection: When the scene detection feature is enabled, your footage is divided up on import into ‘scenes’ that can be displayed and manipulated separately in the Library. This greatly simplifies the task of locating material of interest during editing. Click the lower more button ➤ to open the Scene Detection Options window. (See “The Scene Detection Options window” on page 311.)

Stop at tape end: This option tells Pinnacle Studio whether to automatically stop capturing if a blank area of tape is encountered. A blank area – one without timecode striping – indicates virgin tape.

Provided you have avoided leaving any blank spots during shooting (by slightly overlapping neighboring shots), this option allows for unattended capture.

Import options for analog media

The options for analog import are similar to those just discussed for digital sources. See below for explanations of the Compression Options and Scene Detections Options windows.




Import options for file-based assets

The Mode panel provides two options affecting importing from file.

Import Mode: This option determines whether the media file or project file is physically copied from the source location to the target folder of the local hard drive (as specified on the Import To panel.) If Copy is selected, the file is copied. If Link is selected, the file is not copied and a link is created in the Library to the file in its original location.

It is strongly recommended that files on network drives be copied to the local hard drive.




Delete original: When this option is enabled, the original copies of the files you import will be deleted after copying. This option is handy if you are using the Importer to consolidate your assets and don't want your hard drive cluttered with redundant copies.

Ignore duplicates: This option helps you deal with redundant media files or project files you already have, by telling the Importer not to import extra copies of files that may be differently-named but are apparently identical.

Import options for stop-motion capture

In stop-motion animation, a series of individual frames is captured from a live video source. Depending on your plans for the stop-motion sequence, you can instruct the Importer to integrate the individual frames into a movie, or simply import each frame as a picture, or both.



The Compression Options window

The options provided in the Mode panel for both DV / HDV and analog import include access to this window for fine-tuning compression preferences. If you select either of the DV and MPEG presets, you can use this window to review the actual settings used. Editing the settings here automatically selects the “Custom” preset.


Because some options are contingent on others, not all will be visible simultaneously.

Video settings

Compression Codec: Use this dropdown list to select the codec you want to use.

Framesize: This line shows the dimensions of the captured video.

Quality, Data rate: Some codecs present quality options in terms of a compression percentage (Quality), and others in terms of the required data transfer rate in KB/sec (Data rate).



Compression Options for digital and analog video import.

Audio settings

Compression: This dropdown shows the codec that will be used to compress the incoming audio data.


Record audio: Clear this checkbox if you are not planning to use the captured audio in your production.

The Scene Detection Options window

The options provided in the Mode panel for both DV / HDV and analog import include access to this window for configuring scene detection preferences.

Automatic scene detection is a key feature of Studio when working with DV and HDV sources. As video capture proceeds, Studio detects natural breaks in the video and divides it up into scenes.

Scenes can be independently viewed and managed in the Scenes view in the Library.



The Scene Detection Options window for DV or HDV import. When importing from analog sources, only the last two options are supported.

Depending on which capture device you are using, automatic scene detection is carried out either in real time during capture, or as a separate step immediately after capture is completed.

The four scene detection options are:

- **Automatic based on shooting time and date:** This option is available only when you are capturing from a DV source. Studio monitors the time stamp data on the tape during capture, and starts a new scene whenever a discontinuity is found.
- **Automatic based on video content:** Studio detects changes in the video content, and creates a new scene wherever there is a large change in the images. This feature might not work well if the lighting is not stable. To take an extreme example, a video shot in a nightclub with a strobe light would produce a scene each time the strobe flashed.
- **Create new scene every X seconds:** Studio creates new scenes at an interval you choose. This can be useful for breaking up footage that contains long continuous shots.
- **Manually, by pressing spacebar:** Select this option if you want to monitor the entire capture process and decide for yourself where scene breaks should occur. Press the **Space** key each time you want to insert a scene break during capture.

The Metadata panel

In the Metadata panel, you can enter information that will be associated with the imported media file or project file in the Library. This can make it easier to find and manage the clip when you are searching the Library for assets to use in a movie.

Use the Collection field to enter the name of a Collection to which all imported assets will be added. You can enter the name of an existing


Collection, or create a new Collection by entering a new name. (See “Collections” on page 25.)

You can enter tags for the asset in the Tag field; these can later be used to find the asset. (See “Tags” on page 48.)

The Filename panel


This panel of the Importer is where you specify the names under which your imported media files or project files will be stored.

Each type of input source has a default filename assigned by Studio. For instance, the default filename when importing a Snapshot is “Snapshot”. To change it, click in the space and type the name you want.




The Importer never overwrites an existing file when importing. If a file with the same name as the target name already exists, a sequence number is added to the name of the incoming file.


When importing from file-based assets, additional file naming features are available. By default the naming formula for a file-based input is given symbolically as “[original].[ext]”, meaning that the original filename and extension are used.



If you want a custom name, enter it into the edit box as usual; however, in the case of file-based assets the target filename has two parts: a stem, which you supply, and a tail, which is generated by one of three simple rules at the time of import.



The default rule adds a unique sequence number to every filename. While you are entering your custom name, the edit box shows only the stem. But when the name is displayed at other times, the rule for the tail part of appears as well.

To select a different rule for the tail part, click the more button . This opens a dialog window with two dropdown lists. The first lets you choose between "original" and "custom" for the stem. You can use this if you ever want to revert to importing files under their original names. The second dropdown, which is displayed only for custom names, gives the available rules for generating the tail part:

- **Number:** This is the same rule used by other media types to avoid name collisions. If your stem is "Parade", the first file copied will be named "Parade" (plus the original file extension), the second will be named "Parade_001", and the numbers then continue in sequence.
- **Creation time:** The time of day when the file was created, in hours, minutes, and seconds, is used to generate file names like "Parade_20-30-00" for a file that was created at exactly 8:30 in the evening.
- **Time of day:** This is like the previous option, but the time of importing the file is used.



The Import Filename configuration window.


Selecting assets for import

Each source supported by the Importer has its own appropriate set of controls for selecting the material to be imported. When you click the source name in the Import From panel, the central area of the Importer configures itself appropriately with the controls you need.

Import from file

There are two methods for importing media files and project files from file-based storage media including local hard drives, optical drives, memory cards and USB sticks:

- Select My computer in the Import From panel of the Importer to select specific asset files or groups of files for import.



When importing from file-based assets, the Importer provides a folder and file browser in the central area. This is flanked on the left by the Import From and Import To panels, and on the right by the Mode, Metadata, and Filename panels. The Start Import button at bottom sets things in motion after the desired asset files have been selected.

- Select **Scan For Assets** in the Import From panel to select one or more folders and import all assets of the desired types that are found in those folders.

Selecting files for Import


When you select **My computer** in the **Import From** panel, the job of selecting the files to import belongs to the folder and asset-file browser in the central area of the display.

A single import operation can take in multiple types of files from multiple source folders. Each selected file will be copied to the correct folder for its asset type (as specified in the Import To panel).


The folder and file browser

The left hand column of the browser is a hierarchical view of all folders on all file-storage devices attached to your computer. These devices include hard drives, optical disc drives, memory cards and USB sticks.

Navigation in this “folder tree” is similar to that in Windows Explorer and other programs. Folders containing other folders are indicated by a plus sign to the left of the name when they are closed and by a minus sign when they are open. Click the sign to open out (“expand”) or close down (“collapse”) a folder’s list of subfolders.



Only one entry in the folder tree can be highlighted at a time. Any media files or project files contained in that folder are immediately listed in the larger, right-hand division of the browser. You can preview files on the spot, and earmark those you intend to import by checking the box at the top right of corner of each file icon.



Here, the folder 'Photos\Winter' is open, revealing a set of image files. To select (or unselect) files for import, click the checkbox in the top right corner of one or more icons. In the illustration, four files have been selected.

Previewing media and project files

Previewing audio and video: The file browser includes built-in previewing for all supported asset types. Click the play button in the center of video, audio, and project file icons in the Library to preview the assets they represent. For quick viewing, video files play back within the icon frame itself. Click anywhere on the icon to halt playback; otherwise the entire file is previewed.



Full-screen photo preview: To view a digital photo or other picture file at full-screen resolution, double-click its icon, or click the full-screen button in the toolbar beneath the browser, or press the F11 key.

Scrub preview: Audio, video and project file icons provide a scrubber control immediately below the file icon. Click and drag the scrubber knob to manually review any part of the file. The mouse pointer changes to a two-headed horizontal arrow when it is correctly positioned for scrubbing.



Marking files for import

To mark asset files one at a time for importing, click the checkbox at the top right corner of the file icon. This box is checked automatically when you browse to a new folder for all the files on display.



Click the checkbox to mark or unmark the file.

Marking multiple files: The browser also provides a method of checking or unchecking a group of highlighted files simultaneously. To highlight an individual file, simply click on its name or its icon; the highlighted state is indicated by an orange border. To highlight additional files, click icons in conjunction with either of the **Shift** and **Ctrl** keys, as follows:

- Click while pressing Ctrl to add or remove the highlighting from one file without affecting the others in the group.
- Click while pressing Shift highlights the clicked icon and all those between it and the previously clicked icon, inclusive. Highlighting is removed from any icons not within the range.



A group of four highlighted image file icons. Marking or unmarking any one will affect the whole group.

You can also highlight a range of icons directly with the mouse, by dragging out a rectangle that intersects the icons you want to include. Click the first icon and move to the last one before releasing the mouse button.

Having highlighted some icons you want to import, click the checkbox of any one of them to mark or unmark the entire group at once.

Check All and Uncheck All: Click these buttons along the bottom of the file browser to mark for importing either all or none of the asset files listed in the current folder. The buttons do not affect any files currently selected in other folders.



Use the Check All button to mark all asset files in the current folder.


Each time a file is added to or removed from the list of those to be imported, the file browser updates the count in the selection status indicator at the bottom right of the display.

Customizing the browser

Several controls allow you to configure the file browser appropriately for your display hardware and requirements.

Close the folder tree: To maximize the space for viewing files, click the left-pointing double-arrow icon at the top of the folder tree scroll bar. This collapses the folder tree to a vertical bar down the left-hand side. At the top of the bar is the right-pointing double-arrow that will reopen the tree. The name of the current folder is also shown.

Filter the file list: Another way to optimize your use of the file area is to limit the files shown to include only one asset type. This is the function of the asset filter dropdown at the bottom left of the browser. By default, all supported media file and project file types appear in the browser, but you can limit the view to picture files, audio files, video files or project files by your selection here. To see exactly which file types are included in a selection, hover on the item for a second or two to pop up the list.



Hovering over the Audio files option brings up a list of file types from which audio import is supported.

Zoom slider: A final tool for managing screen real estate is the zoom slider at the bottom right of the browser. Move the slider leftwards to reduce, or rightwards to increase, the size of the preview images in the file browser.



There are three ways of moving this slider with the mouse:

- Click on the slider knob and drag to the left or right.
- Click beside the slider knob to nudge it in the appropriate direction.
- Click the minus/plus buttons at the ends of the slider scale to move the knob by a larger amount.

Full-screen photo: To preview a selected photo on the full monitor screen, click the rightmost button.


Set preview volume: To set the playback volume of audio and video clips for previewing, hover the mouse pointer in the area of the audio/mute button in the bottom bar of the file browser. A volume slider will appear beside the button. Drag the knob up and down to control the volume. Click the audio/mute button itself to toggle audio muting.



Adjusting the import file date and time

The internal clocks of the recording devices are often set incorrectly, resulting in incorrectly timestamped media files. The Importer can correct this kind of problem by setting the date and time of the imported files according to your specifications.

To correct the file time or date:

Use the more button  on the selection status indicator to open a window that offers two options for adjusting the timestamps:

- **Correct time zone:** This slider changes the file-system timestamp of any media files you import by up to 12 hours in either direction. You can use this adjustment to compensate for the time difference when you bring home video from your travels.
- **Set date and time:** These fields let you enter an arbitrary date and time. The timestamp of any media files you import will be set to this.

Scan for assets

When you select **Scan For Assets** in the Import From panel, a hierarchical folder view is displayed, much like the one shown for My computer. Expanding and collapsing folders works as usual, including the use of the Plus and Minus keys as shortcuts.

Since you are selecting folders rather than files to be scanned, the media files and project files contained in the folders are not shown. A

checkbox appears next to each name in the folder tree, and four pop-up lists are offered on the toolbar at bottom.

These lists offer a menu of file types to import in each category: **Video**, **Photo**, **Audio** and **Projects**. By default, the file extensions on each menu are all checked, meaning that all the appearing file types will be included in the import operation. Uncheck the file extensions for any types that you do not wish to import.


To start importing, mark all the folders from which you want to import files. Use the file-type lists just discussed to narrow the range of incoming file types, if desired.

When selections have been made, click the **Scan and Import** button at the bottom to begin the Import operation. This will import all files of the selected types in the chosen directories.

Import from DV or HDV camera


To prepare for importing digital video, switch on your DV or HDV device in play mode and select it in the Import From panel of the Importer.

You will also need to make sure that your destination folder, compression presets, and other options are set up in the other panels the way you want them. (See "Importer panels" on page 298.)



Previewing video

The video currently playing on the source device should now be visible in the preview area at the central area of the display. Along the right edge of the video preview is a scale showing the moment- by-moment audio level.



When a DV or HDV source is selected, the central area of the Importer provides controls for previewing and importing the taped material.

Below the preview image is a row of controls for automating capture by setting mark-in and mark-out points. For more information, see “Recording video and audio” on page 328.


Another row of controls, the transport bar, serves as your navigation console for the source device.




The transport bar for DV and HDV import, with (from left) jog controls and timecode readout, transport buttons, a shuttle control, and an audio button with a pop-out slider for controlling the preview volume.

The **current timecode indicator**   shows your playback position according to the timecode recorded onto the tape

when it was shot. The four fields represent hours, minutes, seconds and frames respectively. To the left of the indicator is a pair of arrow buttons; use these to jog the position one frame back or frame forward at a time.

From left to right, the transport buttons  are **play/pause**, **stop**, **rewind** and **fast forward**. These buttons relay commands to your camera. Using them is equivalent to using the camera's onboard controls, but typically more convenient.

Drag the orange needle on the **shuttle control**  to the left or right to change the playback position in the reverse and forward directions respectively. The motor speed increases as you drag the needle further off center. When you release the needle, it homes to the center position and pauses playback.

Set preview volume: To set the playback volume for previewing, hover the mouse pointer in the area of the audio/mute button in the bottom bar of the file browser. A volume slider will appear beside the button. Drag the knob up and down to control the volume. Click the **audio/mute** button itself to toggle audio muting.



Mark-in, mark-out: The mark in and mark out timecode fields above the ends of the transport bar indicate the planned starting point and ending point of a video capture.

Note: DV and HDV sources are also suitable for snapshots.

Recording video and audio

The Importer supports two approaches to selecting a range of video to be imported.

In the manual approach, you simply watch the preview playback and press **Start Capture** at the start of the desired footage. When you reach the end of the segment, press **Stop Capture**. If you have continuous timecode on the source footage, and have set Stop at tape end to 'Yes' in the Mode panel, you can walk away and leave the Importer to switch off when the input is exhausted.

The automatic method of capture is good for setting the endpoints of your capture (the "mark-in" and "mark-out") points with single-frame precision, and for unattended importing that should halt before the end of the recorded material.

Sometimes you may want to use set the mark-in time and leave mark-out blank. When you click **Start Capture** the Importer will locate your start time then capture until you tell it to stop (or at tape end).


You can also set a mark-out time and leave the mark-in time blank. When you click **Start Capture** import will begin immediately, and end automatically at the mark-out point. Entering a duration and entering a mark-out time are equivalent. Whichever you specify, the Importer calculates and displays the other one automatically.

Note: Before starting the import operation, verify that the settings on the Import To panel and other panels (see "Importer panels" on page 298) have been configured correctly.

To capture manually with the Start Capture and Stop Capture buttons:


- 1 Make sure that the mark-in and mark-out points are not set. If needed, use the button associated with the field to clear it with one click.
- 2 Manually start playback of the source tape before the desired starting point of the capture.
- 3 Click the **Start Capture** button when the starting point is reached. The button caption changes to Stop Capture.
- 4 At the end of the segment click the button again. The captured material is stored in the Library.
- 5 Manually halt playback (unless automatic shutoff is in effect as noted above).

To capture automatically by setting mark-in and mark-out points:


- 1 Use the time counter controls to set the mark-in and mark-out values – the start and end points of the desired footage.
To set the mark-in point, either enter a value directly into the start field, or navigate to the desired point and click the **Start** button. A similar approach can be used to set the mark-out point.
- 
- 2 Click Start Capture. Studio positions the source device to the mark-in point and automatically begins recording.
 - 3 When the mark-out point is reached, import is terminated and the source device is stopped.
 - 4 The captured material is stored in the Library.

Import from analog sources

To record analog video (e.g. VHS or Hi8) you need a converter that connect to your computer and that has the required video and audio connections. This is also the case when recording from analog sound sources, such as a record player. Currently supported devices include Pinnacle products such as 500/510-USB, 700/710-USB and DVC 100, and webcams based on DirectShow technology.

To prepare for importing from an analog source, switch on the device and select it by name in the **Import From** panel of the Importer. Also choose the applicable input (e.g. "Video Composite" or "Video SVideo"). If you wish to tweak the incoming analog signal prior to digitization, click the more button , which provides access to the Analog Input Levels window. (See "Adjusting analog audio and video levels" on page 299.)

Before starting the capture, make sure that your destination folder, compression presets, and other options are set up in the other panels as you want them. (See "Importer panels" on page 298.)



To capture from an analog source:

- 1 Verify that the input device is connected (e.g. "Video S-Video").
- 2 Start the playback device just before the point at which you would like capture to begin.
Video and audio previewing should now be active. (If not, check the cabling and the converter installation.)
- 3 Click the **Start Capture** button to start recording.
The button caption changes to **Stop Capture**.
- 4 At the end of the segment click the button again. The captured material is stored in the Library.
- 5 Halt the source device.


To capture for a specified duration:

- 1 Verify that the correct input is connected (e.g. "Video S- Video").
- 2 Enter the desired capture duration in the Duration time-counter control below the video preview.
- 3 Start the playback device just before the point at which you would like capture to begin.
Video and audio previewing should now be active. (If not, check the cabling and the converter installation.)
- 4 Click the Start Capture button to start recording.
The button caption changes to Stop Capture.
- 5 The capture operation will stop automatically after the desired duration has been captured. You may also stop the capture manually by clicking the Stop Capture button.

Import from DVD or Blu-ray Disc

The Importer can import video and audio data from DVDs and BDs (Blu-ray discs).

Note: Blu-ray authoring is not included by default. To add it, choose **Help > Purchase Blu-ray**, and follow the steps to complete the purchase. If you have already purchased Blu-ray authoring for Pinnacle Studio 19, but need to reactivate it, see “Restore purchase” on page 378.



To begin, insert the source disc in its drive and select it in the **Import From** panel of the Importer. If you have more than one optical drive, choose the correct device among those listed.



Note: Copy-protected media cannot be imported.

Before starting the capture, make sure that your destination folder and file name are set up in the other panels the way you want them (see “Importer panels” on page 298).

Because large files can be involved when importing from optical discs, selecting the correct import directory is important. In particular, ensure

that the designated storage location has sufficient space available (see “The Import To panel” on page 302).

Previewing the disc files


The media on optical discs are accessed through the computer’s file system. For this reason, the previewing controls in the central area, the methods for selecting files, and the procedure for importing, are the same as for ordinary file-based assets (except that the unneeded folder view starts in the closed position). Please see “Import from file” on page 315.

Import from digital cameras

Like optical disc drives, the media on digital cameras is accessed through the computer’s file system. The camera may appear on the source list as a removable disk drive. Previewing, selecting and importing are the same as for ordinary file-based assets (except that the folder view starts in the closed position).

Stop motion

The Stop Motion function of the Studio Importer lets you create animated films by stitching together frames grabbed from a live source, such as a video camera, webcam or DSLR. The result of your Stop Motion import will be a collection of captured images, and a project file created from the images.



To prepare for Stop Motion import, make sure the camera is switched on and connected to your computer, then select it by name under the Stop Motion heading in the Import from panel of the Studio Importer. (See “The Import From panel” on page 298.) Before starting to capture, make sure that your destination folder, options and file name are set up in the other panels the way you want them.

If your source equipment is functioning correctly, you should have a live preview in the central area of the Importer window.

When you are ready to capture an image, you can click the **Capture Frame** button. A thumbnail of the grabbed frame is added to the Image Tray at the bottom of the window. Since this is a stop motion sequence, after each image is captured you will generally make small changes to the scene you are shooting in order to create the illusion of motion from frame to frame.

To make your task of gauging the movement easier, you can use alignment tools (line, grid, or circles). You can also use Onion Skin Mode, a mode that uses a ghosting effect whereby successive frames are shown simultaneously in translucent layers so that the differences can be clearly seen.

The number of images shot so far and the duration of the video (based on the number of images, rounded off) are displayed to the right below the control bar.

You can also import images that you have already captured for stop motion by clicking the Import File button below the control bar.

Project Settings

You can choose from the following settings for your stop motion project:

- **Aspect Ratio:** Set to **Standard** (4:3) or **Widescreen** (16:9)
- **Resolution:** Set to **NTSC Standard** or **PAL Standard**
- **Frame Rate:** Higher frame rates result in better quality, but require more image captures.
- **Image Duration:** Set the duration for each image you capture according to frames. The higher the number, the less images you need to capture, but the results might be less smooth.

The Stop Motion control bar

This bar provides transport and other functions for Stop Motion import. From left to right:



- **Video** and **Frames** indicators: These let you switch between previewing the live video feed and previewing the captured frames

in the Image Tray. You can review – and if necessary replace – particular frames without having to undo other work.


- **Auto Capture:** The **Auto Capture** button toggles the feature on (orange icon) or off (white icon). Click the arrow for **Auto Capture** to specify the settings (**Capture Interval** and **Duration**).
- **Navigation buttons:** These buttons are for previewing your animation. They let you play, go to start, go back one frame, or go forward one frame. A **Loop Play** button lets you cycle the animation continuously.
- **DSLR Capture:** These optional controls can be used when you have a compatible DSLR connected to your computer (at this time most Canon DSLRs are supported). The **DSLR Capture** icon is orange when your DSLR camera connected. The arrow button lets you access the **DSLR Settings** dialog box. Here you can control the DSLR. This ensures consistent results across frames. The settings vary somewhat according to your camera and camera mode. It is recommended that you set your camera to Manual mode.
- **Auto Focus (AF), Manual Focus (MF) and Show Focus:** These optional controls can be used to adjust the focus for your camera in Pinnacle Studio when you have a compatible DSLR camera connected to your computer (at this time most Canon DSLRs are supported). Your camera lens needs to be set to AF to use these onscreen focus controls.
- **Onion Skin Mode:** The **Onion Skin Mode** button toggles the feature on (orange icon) or off (white icon). Click the arrow for **Onion Skin Mode** to specify the settings. The first slider (**Original-Onion skin**) shows the difference in transparency between the original and successive frames. The **Frames** slider controls the number of frames, in addition to the current one, that will display onscreen. Experiment to find the settings that work best for your movie.



The number of images shot so far and the duration of the film (based on the number of images, rounded off) are displayed to the right below the control bar.

Using the Image Tray with Stop Motion

When you click Capture Frame (button displays below the Stop Motion control bar), the Image Tray opens and displays the images that you capture. You can view the start time for each image (time displays above the thumbnail). You can click a thumbnail to choose the frame. You can delete the frame by clicking the red trash icon above the thumbnail. You can also insert a frame to the right of the selected thumbnail by clicking Capture Frame. Note: You must be in Video mode to capture frames (click Video on the left side of the control bar).



Alignment tools

Gauging movement in stop motion projects can be tricky. In addition to the Onion Skin Mode described above, you can use the following tools:

- **Line:** Drag across the screen to set a line with nodes that mark intervals. Look for the pink node to find the suggested alignment for your next capture.
- **Grid:** Displays a grid overlay onscreen

- **Circles:** Displays a circle pattern onscreen



The interval for the nodes, grid lines, or circles is determined by the Time across setting. The value (seconds) determines how many suggested captures to make, as indicated by the space between intervals. You can use the alignment tools to create smooth even motion, or to help you gauge how much you need to move the subject to speed up or slow down the movement.

Exporting the animation

When you have added all the frames you want to the animation, click one of the following options:

- **Export to Library:** Converts the frames to an .axps file and imports both the .axps file and the collection of images to the Library. Similar to an .axp file, an .axps file is a project file that lets you easily reopen the project in the **Stop Motion** mode of the Importer so that you can continue to work on the project at another time. It references the project files.
- **Edit in Timeline:** Imports the frames to the Library and add the project to the Timeline (Edit mode) for further editing.

How to create a stop motion project in Pinnacle Studio

The steps below guide you through a basic workflow for a stop motion project. Before you start, it's best to have all your materials ready and have your shooting area set up with the lighting you need. If you are

using a DSLR that is supported in Pinnacle Studio, set your camera to **Manual** mode. A tripod is recommended.

To create a stop motion project

- 1 If using an external camera to capture your stop motion project, ensure that the camera is plugged into your computer and is on, ready to capture photos. Set the camera to manual mode.
- 2 In Pinnacle Studio, click the **Import** button (to the right of the **Author** button). The Studio Importer window opens.

- 3 In the **Import from** list, click **Stop Motion**.

Supported cameras that are connected to the computer and switched on are listed below **Stop Motion**. Click a camera name and do one of the following:

- On your camera, manually choose the best settings for your stop motion scene and adjust the focus (can set the lens to MF to focus manually).
 - If you have a compatible camera (most Canon and Nikon DSLRs are supported), in the control bar below the preview area, click the arrow beside the **Camera** button. In the **DSLR Settings** dialog box, choose your camera from the drop-list, and choose the settings for your camera, using the Preview screen as a guide. Make any adjustments you want and click **OK**. You can then focus the camera manually or set the lens to AF mode, and in Pinnacle Studio, enable **Show Focus** to display the onscreen controls. Click **Auto Focus** or **Manual Focus**. For **Auto Focus**, drag the rectangle to the area of focus. The camera will automatically adjust the focus. For **Manual Focus**, click the plus or minus symbol on the preview screen until the subject is in focus.
- 4 Choose your **Project Settings**, and if you want to change the default destination for your project files, in the **Import to** area, click the arrow buttons and navigate the location you want.

- 5 When you know what kind of motion you want to make, you can choose from different types of alignment tools and set the **Time across** setting (value is time marked in seconds).
- 6 When you have the subject set up, click **Capture Frame**.
- 7 Move your subject the way you want, and continue capturing an image for each movement. If you are making a series of simple movements, you can set up **Auto Capture**.
- 8 When you are ready to review the frames, on the control bar, click the Play button to review the movie. To reactivate the **Capture Frame** button if you want to add more frames, click **Video** in the control bar.
- 9 When you are finished, click **Export to Library** or **Edit in Timeline** button.


If you want to save the project without exporting to the Library, click the **Save** button in the Project name panel (on the left side). You can click the **Open** button (beside **Save**) to access the saved project.

Snapshot

The Snapshot function of the Importer is used to record individual frames (still images) from cameras or players connected to the system. To prepare, make sure the source device is switched on, then select it by name under the Snapshot heading in the Import From panel of the Importer. For more information, see “The Import From panel” on page 298.

Before starting the capture, make sure that your destination folder and file names are set up in the other panels as you want them. For more information, see “Importer panels” on page 298. Now start your camera, or roll your tape, and start monitoring the embedded preview display in the central area of the Importer window. Click the full-screen

button at the right-hand end of the transport bar to preview on the full monitor screen.



When you want to capture an image as it goes by, click the **Capture Frame** button.

A thumbnail of the grabbed frame is added to the Image Tray at the bottom of the window.




Capturing snapshots in the Importer. While previewing live or taped video in the central area of the window, use the Capture Frame button to grab still images. Grabbed frames accumulate in the Image Tray at the bottom of the window until you click the Start Import button to transfer them to the Library.

Capture as many additional frames as are required. The Importer adds each one in turn to the collection growing in the Image Tray. In the course of capturing, you can change tapes, re-aim your camera, and so on as you see fit. The source video doesn't need to be uninterrupted as long as there is signal present when you actually click the Capture Frame button.

Using the Image Tray

For on-the-spot review of a frame you have already grabbed, click the thumbnail of any but the most recent frame in the Image Tray. This switches the preview display from the video source to the captured file,

and activates the File indicator. You can also activate the indicator by clicking it directly.



Click the File indicator or any thumbnail in the Image Tray to review images already grabbed. Here, thumbnail 5 has been clicked, and the mouse pointer is poised over the trash-can icon to delete it. The heavy line to the right of the selected thumbnail is where the thumbnail of the next grabbed frame would be inserted.

To delete a captured frame, select it in the Image Tray, then click the trash-can icon that appears in the top right corner of the thumbnail.

To switch back to previewing video after reviewing files in the Image Tray, click the Live indicator beneath the preview display.


Importing the frames

When you have grabbed all the frames you want from the video source, click the **Start Import** button. The Importer adds the grabbed images to the still images section of the Library.

The header image for Chapter 11 features a woman swimming underwater, holding a blue surfboard. The Pinnacle logo, consisting of a colorful pinwheel icon and the word "pinnacle", is in the top right corner. The chapter title "Chapter 11: The Exporter" is displayed in a large, white, sans-serif font at the bottom of the image.

Chapter 11: The Exporter


One of the great things about digital video is the large and growing number of devices that can make use of it. Studio lets you create versions of your movie for whatever video viewers your audience will be using, from hand-held DivX players and mobile phones to HDTV home theaters.



When you have finished editing your project, open the Exporter by pressing the Export button at the top of the screen. With a few clicks you can tell the Exporter everything it needs to know to output your movie or asset in the format that best fits your requirements.

Note: To export directly from the Library without using the Exporter, please see “Exporting directly from the Library” on page 30.

The Exporter will ensure that your project is complete before it is exported. If there is any missing media, your project cannot be exported until the media is either relinked or deleted from the project. For more information, see “Missing media” on page 22.



The Exporter. The buttons at upper left set the export destination to File, Disc, Cloud (the Internet), (portable) Device, or MyDVD File. Other controls let you set output options as needed for the chosen output type. The name of the project appears above the Player, while the panel below it shows the currently-selected output format.

Begin by selecting one of the **File**, **Disc**, **Cloud** and **Device** buttons to set the media type of your finished project.



File output creates movie files that can be viewed from just about anywhere: your hard drive, your website, your portable movie player – even your mobile phone. See “Output to file” on page 352.



Disc output lets you copy a movie onto a recordable disc in your computer’s CD, DVD or Blu-ray recorder (also called a ‘burner’), or onto a flash memory card. You can also direct the Exporter to create a copy, or ‘image’, of the disc on your hard drive, without actually burning it. See “Output to disc or memory card” on page 349.



Cloud output creates a file for uploading to a cloud-based service provider, where you can decide whether to limit your audience to a few close friends or share your project with the world. See “Output to cloud” on page 360.



Device output creates a file that can be viewed from your portable movie player, mobile phone, tablet computer, or similar device. See “Output to a device” on page 363.



MyDVD File creates a file that can be used in the MyDVD application. MyDVD lets you access templates to quickly create a final DVD with titles, graphics, and full menus. For more information, see “Output to a MyDVD file” on page 364.

Configuring output

Output can be configured quickly within each media type using the dropdown lists in the **Settings** panel. If you need hands-on control, click the **Advanced** button to open a panel of options for the media type.




When you have confirmed your settings, click either **Create Image** or **Burn Disc** to output in disc format, **Start Publishing** to send your movie to the Cloud, or **Start Export** to begin saving as a file or to a portable device.

Preparing your movie for output

Before your movie is completely ready for output some preprocessing will usually be required. In general, Pinnacle Studio will need to 'render' (generate video frames in the output format) any transitions, titles, disc menus and video effects you've added to your movie. Any files generated during the rendering process are stored in the auxiliary files folder, whose location you can set in the application settings window.

Create between markers

For output to file or to the Cloud, you have the option of exporting only a selected portion of your movie. Adjust the trim calipers in the Player or the Timeline to indicate which part of the movie you want to export.



Set the Mark In and Mark Out calipers to export a segment of the timeline.

Output to disc or memory card

Studio can output movies directly onto DVD and Blu-ray discs, if the requisite disc-burning hardware is available on your system.

Whether or not you have a disc burner, Studio can also create a ‘disc image’ – a set of files containing the same information as would be stored onto the disc – in a directory on your hard drive. The image can subsequently be burned onto a disc or transferred to a flash memory card.

Note: Blu-ray authoring is not activated by default. To activate it, choose **Help > Enable Blu-ray authoring**.

DVD and Blu-ray

If your system has a DVD burner, Studio can create two types of DVD disc: standard (for DVD players) and AVCHD format (for Blu-ray players).

If your system has a Blu-ray recorder, you can record onto any recordable media supported by the device.

Your standard DVD discs can be played back:

- On any DVD player that can handle the recordable DVD format your burner creates. Most players can handle the common formats.
- On a computer with a DVD drive and suitable playback software.
- On any HD DVD player.

Your Blu-ray disc, or DVD disc in AVCHD format can be played back:

- On the Panasonic DMP-BD10, the PlayStation 3, and other Blu-ray players (not all players support the AVCHD format, but most do).


- On a computer with a Blu-ray drive and suitable playback software.

SD card, Memory Stick and Built-In Media

AVCHD 2.0 disc structures can be written to flash memory cards, such as SD cards or Memory Sticks, or even to devices with built-in media support (e.g. camcorders with AVCHD 2.0 support).

Creating 3D discs

If your project is in stereoscopic 3D, you can easily create 3D discs in DVD, AVCHD and AVCHD 2.0 formats. On the Settings panel, the S3D dropdown menu lets you choose the correct mode. Use Anaglyph, Anaglyph Crossed Eyed, or Side-by-side 50% to create the disc.



Stereoscopic 3D choices for AVCHD.

A multistream 3D project can be exported in AVCHD 2.0 format to flash memory, such as an SD card, Memory Stick or built-in media storage.


Outputting your movie

Studio creates your disc or disc image in three steps:

- 1 First the entire movie must be rendered to generate the MPEG-encoded information to store on the disc.
- 2 Next, the disc must be compiled. In this phase, Studio creates the actual files and directory structure that will be used on the disc.
- 3 Finally, the disc must be burned. (This step is skipped if you are generating a disc image rather than an actual disc.)

To output your movie to disc, or to a disc image:

- 1 Click the **Disc** tab to bring up this display:



The circular display summarizes your disc usage. It also shows an estimate of the time the movie will occupy on your writable disc.

Use the folder button to change the hard drive location Studio uses for storing auxiliary files. If you create a disc image, it too will be stored in that folder. The dropdown list on the lower display specifies the disc burner to use if more than one is available.

- 2 On the Settings panel, select the disc Type you are using, then whichever video quality and disc usage Preset best matches your intent.

If you wish to fine-tune your output settings, choose the **Custom** preset then click the **Advanced** button to bring up the **Advanced Settings** panel.

- 3 Click the **Burn Disc** button.

Studio goes through the steps described above (render, compile, and burn) to create the disc. Click the **Create Image** button to perform the identical steps but omit the burn step.

- 4 When Studio has finished the burning operation, it ejects the disc.
- 5 If you want to burn a previously created image press the **Burn Image** button.

Quality and capacity of disc formats

The differences amongst the various disc formats can be boiled down to these rules of thumb regarding the video quality and capacity of each format:

- **DVD:** Each disc holds about 60 minutes of full-quality MPEG-2 video (120 minutes if the disc recorder supports dual-layer recording).
- **DVD (AVCHD):** Each disc holds about 40 minutes of full-quality AVCHD video per layer.
- **BD:** Each disc holds more than 270 minutes of HD video per layer.

Output to file

Studio can create movie files in all of these formats:

- 3GP
- 360 Video
- Audio only
- AVCHD/Blu-Ray
- AVI
- DivX
- DivX Plus HD
- Flash Video
- Image
- Image Sequence

- MOV
- MPEG-1
- MPEG-2
- MPEG-4
- MTS
- *Real Media
- Smart
- Windows Media
- XAVC


*Supported in 32-bit only.

Choose whichever format matches the needs of your audience and the details of their viewing hardware.


The size of the output file depends on both the file format and the compression parameters set within the format. Although compression settings can easily be adjusted to produce small files, heavy compression comes at the expense of quality.

The detailed settings for most formats can be adjusted by choosing the Custom preset and clicking the **Advanced** button. Other presets load settings designed for typical situations.

If you are exporting a stereoscopic 3D project, an S3D menu will appear, offering various 3D formats, or the option of exporting your project in 2D.



When your output options are in place, click the Create file button. A file browser opens to let you specify a name and location for the video file you are creating.



When you are exporting a movie to a file, these panels on the Exporter display your export settings.

As a convenience after output has completed, the Exporter provides shortcuts for opening Windows Media Player and the QuickTime Player. To view your output file as soon as you have created it, click the icon representing the player of your choice.

3GP

Pinnacle Studio can generate movies in this widely-used file format using your choice of MPEG-4 or H.263 video compression, along with


AMR audio compression. The format is adapted to the comparatively modest processing and storage capabilities of mobile phones.

The list of presets for this file type offers two frame sizes in either encoder. Choose Small, at 176x144, or Very Small, at 128x96.

Audio only

Sometimes a movie's soundtrack can stand alone without visuals. Live entertainment footage, and video recordings of interviews and speeches are instances in which an audio-only version might be desirable.

Pinnacle Studio lets you save your soundtrack in wav (PCM), mp3 or mp2 format.



Click the preset that best meets your needs; or choose **Custom**, then click the **Advanced** button to open the Advanced Settings panel.

Transport Stream (MTS)

Transport Stream (MTS) may contain video in MPEG-2 or H264/AVC compression. Its applications include HD playback on AVCHD-based camcorders, AVCHD disc, or Blu-ray disc.

Click the preset that best meets your needs; or choose Custom, then click the **Advanced** button to open the Advanced Settings panel.

AVI

Although the AVI file type for digital video is itself widely supported, the actual coding and decoding of video and audio data in an AVI file is performed by separate codec software.

Studio supplies a DV and an MJPEG codec. If you wish to output your movie as an AVI in some other format, you can use any DirectShow-compatible codec installed on your PC, as long as that codec is also installed on the PC that will play your movie.

Click the preset that best meets your needs; or choose Custom, then click the Advanced button to open the Advanced Settings panel.

DivX

This file format, based on MPEG-4 video compression technology, is popular for video files disseminated over the Internet. It is also supported by a range of DivX-compatible hardware devices, from DVD players to portable and handheld units.

Click the preset that best meets your needs; or choose **Custom**, then click the Advanced button to open the Advanced Settings panel.

DivX Plus HD

This file format, based on H264 video compression technology, is popular for HD video files disseminated over the Internet.

Click whichever of the quality presets matches your needs; or choose Custom, then click the **Advanced** button to open the Advanced Settings panel.

Flash Video

Studio supports output in Flash Video (flv) format, version 7. Virtually all current web browsers are able to display this popular format, which has been widely adopted by social networking sites and news sites.

Click the quality preset that matches your needs; or choose Custom, then click the Advanced button to open the Advanced Settings panel.


Image

A frame of your video project can be exported as an image, a JPG, TIF or Custom. If you select the **Custom** option, use the Advanced button to open the Advanced Settings panel.

Image sequence

A section of your video project can be exported as a series of images, one per frame. The video selected must be at least one second long. Each second of video will generate between 25 and 60 images, depending on the frame rate setting.

The images can be TIF, JPG, TGA, or BMP, in a variety of sizes. If the project is in stereoscopic 3D, you will be offered S3D formats for output.



MOV Video

This is the QuickTime file format. It is particularly suitable when the movie will be played on the QuickTime player.

The presets provide a variety of size and encoding options.

MPEG

MPEG-1 is the original MPEG file format. MPEG-1 video compression is used on VideoCDs, but in other contexts it has given way to newer standards.

MPEG-2 is the successor format to MPEG-1. Whereas the MPEG-1 file format is supported on all Windows 95 and later PCs, MPEG-2 and MPEG-4 files can only be played on PCs with appropriate decoder software installed. Several of the MPEG-2 presets support HD (High Definition) playback equipment.

MPEG-4 is another member of the MPEG family. It offers image quality similar to MPEG-2 but with even greater compression. It is particularly suitable for Internet use. Two of the MPEG-4 presets (QCIF and QSIF) create 'quarter-frame' video sized for cell phones; two others (CIF and SIF) create 'full-frame' video suitable for handheld viewers.

Custom presets: With all MPEG variants, Custom lets you configure movie output in detail by clicking the Advanced button to open the Advanced Settings panel.


Real Media

Real Media movie files are designed for playback on the Internet. Real Media movies can be played back by anyone around the world who has the RealNetworks RealPlayer software, which is a free download from www.real.com.

Click the **Advanced** button to configure your output with the Advanced Settings panel.

Windows Media

The Windows Media file format is also designed for streaming Internet playback. The files can be played on any computer where the Windows Media player – a free program from Microsoft – is installed.




Click the **Advanced** button to configure your output with the Advanced Settings panel.

Output to cloud

The Pinnacle Studio Exporter lets you share your movie creations with your social network on Facebook, with your professional peers on Vimeo, and with potentially the entire world on YouTube.

Storing your media and projects on the Cloud means they are also accessible from your smart phone or tablet, and can easily be transferred between computers for collaboration and convenient access.



When uploading to the Cloud, whether to Facebook, Vimeo or YouTube, the only action available within the Exporter itself is 'Publish'. Settings are chosen after logging in to the service provider.

After selecting a sharing provider, click the Start Publishing button at the bottom of the Studio Exporter window. If you are not already logged in to the provider's site, a log-in page will appear.

After logging in, select a format for uploading your project. The choices provided in the Format dropdown are Fastest (360p), Standard (480p), HD (720p) and HD (1080p). Each specifies a different combination of frame size and video data rate.

Facebook

After logging in to your Facebook account, you can enter a new Title, or Description for your movie, and select Format and Privacy settings from the dropdown menus.

Use the **Start** button at the bottom of the Studio Exporter window to render and upload your project.

Vimeo

After logging in to your Vimeo account, you can modify the movie's Title, Description and Tags. Choose the Format you prefer from the dropdown menu.

When ready, click the **Start** button at the bottom of the window to render and upload your project.

YouTube

After logging in to your YouTube account, you can enter a new Title, Description, or new Tags. Choose your Format and Privacy settings from dropdown menus.

Upload to **You Tube**™

Title: the-sky-is-the-limit

Description: Created with Corel Pinnacle Studio

Tags: Island Vacation 2014

Privacy: Public ▼

Format: Fastest (360p) ▼

Adding tags

When the settings are to your satisfaction, click the Start button at the bottom of the window to render and upload your file.

After uploading

When the upload is finished, you have the option of opening a web browser to view your creation, or returning to Studio. For Facebook, YouTube and Vimeo, your file must be processed before it can be viewed online, and so may not be immediately available.

Output to a device

Studio can create movie files that are compatible with the following list of devices:

- Apple
- Microsoft Xbox and Xbox One
- Nintendo Wii
- Sony PS3 and PS4
- Sony PSP

If you are exporting a stereoscopic 3D project, you will be offered the 3D formats compatible with the selected device.

Apple

Studio supports exporting files that are compatible with popular Apple devices like iPod, iPhone and iPad, and Apple TV as well.

The file format used for iPod and iPhone compatible devices is based on MPEG-4 video compression technology. The combination of powerful compression with a small 320x240 frame size produces very small output files relative to the more expansive formats. The three quality presets select different data rates, each providing a different balance of quality and file size.

Apple TV as well as iPad compatible files are based on the H.264 video compression standard. Output frame size is either 960x540 for Apple TV (first generation) or 720p (later generations).

Microsoft Xbox and Xbox One

Microsoft Xbox presets allow you to create files for full-screen playback on your Xbox. Two formats are available: DivX SD based on MPEG-4 video compression technology, and WMV HD.

Nintendo Wii

Pinnacle Studio can generate files for playback on your Nintendo Wii with the support of both AVI and FLV output formats.

Sony PS3 and PS4

You can export files to your PlayStation by selecting the Sony PS3 or Sony PS4 export type. Studio supports the following file formats: Full size, which is in DivX file format at 720 x 400, and HD 1080/60i.

Sony PSP

Studio allows you to export files which are compatible with the popular Sony PlayStation Portable devices. Output files are based on MPEG-4 video compression technology.

As with the iPod-compatible type, the combination of powerful compression with a small 320x240 frame size produces very small output files relative to other formats.

Output to a MyDVD file

The **MyDVD File** option creates a file that can be used in the MyDVD application. MyDVD is an easy disc authoring application that uses templates to help you create professional-looking disc projects that include menus, and music. For more information about MyDVD, see the Help available in the MyDVD application.

You can open MyDVD by clicking the **Pinnacle MyDVD** shortcut on your desktop or by searching for **Pinnacle MyDVD** on your **Start** screen or **Start** menu.


To save a MyDVD file

- 1 After you create and edit your project in the Timeline of the Edit workspace, save your project.
- 2 Click the **Export** tab.
- 3 In the **Studio Exporter**, click **MyDVD File** in the **Export type** list.
Note: Only the timeline items are exported to a MyDVD file. Because MyDVD lets you create menus to finalize your disc, any menu items from Pinnacle Studio are removed in the exported file.
- 4 In the **Settings** area, choose the **Type** of disc and a **Preset**.
- 5 Click **Start Export**, navigate to where you want to save the file, type a file name, and click **Save**.



Pinnacle Studio's central configuration window is called the Control Panel.

To begin, on the Pinnacle Studio main menu, select **Setup > Control Panel**. When the Control Panel appears, choose a page from the directory on the left side of the window.



The Pinnacle Studio Control Panel is a central configuration window for the application.

The eight pages of Control Panel settings are described here in turn.

Watchfolders

Watchfolders are folders on a hard drive or other storage medium that are monitored by Pinnacle Studio. When the contents of a watchfolder change, the Library is automatically updated.

When you use watchfolders, a **Library Media** branch is added to the Asset Tree in the Library. You will also see a **Library Media** branch if Pinnacle Studio detects a library from a previous version of Pinnacle

Studio (you must enable watchfolders if you want to continue populating this branch).

You can create as many watchfolders as you wish and optionally set them up to watch for only one media type (video, image or audio) instead of all three, the default.

To designate a folder on your system as a watchfolder, click the Enable button, and then the Add Folder button below the watchfolders list, and navigate to the folder you wish to add. To cancel watchfolder behavior, select the folder in the list and click the Remove Folder button.

Click the Apply button to direct the Library to update its catalog in light of the watchfolder changes.

Audio device

This setup page provides the parameters available for recording devices (such as microphones) that are connected to the computer. Click the device name to access the Windows settings dialog for the device.

Event logging

Messages are logged in this window during certain operations, such as importing a number of files. You can check here for details about any problems that may have occurred during these operations.

Export and Preview

These settings affect the representation/display of video.

Quality: These options control the quality of video previewing throughout the application.

- **Best Quality:** Provides previewing at full resolution – the resolution at which the project will ultimately be exported. Under this option there may be dropped frames during playback on slower systems.
- **Balanced:** At this setting, the recommended one for ordinary use, some quality optimizations are omitted for the sake of a faster preview. In most cases the difference is barely noticeable.
- **Fastest Playback:** The preview is optimized in favor of processing efficiency, which may be helpful on a slower system.

Show full-screen preview on: Select the computer monitor (if more than one is available) on which you want the full-screen preview to be displayed.

Show external preview on: Select from a list of available devices and signal outputs (if any).

External preview standard: Select the TV standard of the connected video monitor.

Playback Optimization

Optimization threshold: The optimization threshold determines how much rendering is done when you preview your project. It can be set anywhere from **Off** (0) to **Aggressive** (100). Whether a particular timeline ‘slice’ will be rendered depends on the amount of computation needed to prepare the effects and transitions that are used, and on the value of the **optimization threshold**. If this value is set all the way to Aggressive, Pinnacle Studio will pre-render all transitions, titles, disc menus and effects even when the output would have been previewable; this can considerably delay playback.

If **optimization threshold** is set to **Off** (zero), on the other hand, the yellow and green markings that indicate rendering progress are not

displayed; instead, all effects are played back in real time. However, this can result in reduced playback quality (lost frames, 'jerky' playback) if the number and complexity of effects outstrips the available processing capacity of the system.

Render while play: When the Automatic setting is used, the application decides on the basis of system information whether real-time rendering can be done during playback. If the Off setting is used, rendering is disabled during playback but resumes when playback is stopped.

Third-party Codecs: Lets Pinnacle Studio use third-party codecs that are installed on your computer so you can work with additional video formats. Note: Some third-party codec packs might cause crashes or errors in Pinnacle Studio.


Hardware Acceleration

When activated, this feature shifts part of the processing load from the CPU to auxiliary hardware, such as the GPU (Graphics Processing Unit) of your graphics card. The level of support for hardware acceleration depends on the type of CPU and graphics card on your computer.

- Most NVidia cards support the CUDA architecture. When this is accessible, the GPU is used to assist with H.264 decoding.
- Machines equipped with a recent Intel CPU having the Intel Quick Sync Video feature can use it for rapid decoding and encoding of H.264 and H.264 MVC material.

To choose Hardware Acceleration type

- 1 Choose **Setup > Control Panel > Export and Preview**.
- 2 In the **Hardware Acceleration** area, choose an option from the **Type** dropdown.



Hardware Acceleration options

Default 3D Viewing Mode: This setting selects the default for stereoscopic 3D content throughout Pinnacle Studio. See 3D viewing mode switcher for more information. Please see “Choosing what to display in the Library” on page 45 for more information.

- **Left eye or Right eye:** The preview for stereoscopic content can be set to show only its left or right eye view.
- **Side By Side:** In Side By Side preview mode, you can monitor the individual 2D images for both sides at the same time.
- **Differential:** Rather than the image content itself, the differences between the left and right frames are displayed. Identical areas show as neutral gray.
- **Checkerboard:** Right and left eye views alternate in adjacent cells of a 16x9 grid.
- **Anaglyph:** An Anaglyph stereoscopic preview is suitable for viewing with red-cyan stereoscopic glasses.
- **3D TV (Side by Side):** This mode is to be used with a 3D – capable second monitor or projector.


- **3D Vision** If your system is 3D Vision capable and stereoscopic 3D is turned on in your driver settings, any stereoscopic content will be previewed in 3D Vision by default.

No stop when activating 3D Vision: This setting is available when Studio is run on a PC with a 3D Vision- capable system which has stereoscopic 3D turned on in the driver setting. By default, the No stop when activating 3D Vision setting is set to off. When turned on, playback will automatically stop wherever a 3D Vision preview is being activated or deactivated during playback.

Import

The default options for the Pinnacle Studio Importer may be set here; however, you can adjust or override them in the Importer at the time of importing.

Folder options: View or set the default storage locations for media and projects that are to be physically copied during import; unlike linked imports, including the Library's Quick Import feature, which simply link to existing files without relocating them. The folder locations are initially set to the user's music, video and images folders as configured in Windows, and to the default folder for saving Studio projects.



Selecting a video subfolder type on the Import Settings page.


After locating and selecting the folder you want to serve as the base folder, you can optionally set up a subfolder:

- **No subfolder:** With this option, the files you import will be stored in the base folder.
- **Custom:** When you choose this option, a Custom Project Subfolder box will appear. Click it to enter a name for the Subfolder for that media type.
- **Today:** Your imports will go to a subfolder named with the current date, in the format "2012-10-25".
- **Creation date:** Each imported file will be stored in a subfolder named with the creation date of the asset, in the same format as above. When multiple assets are brought in a single import operation, this may mean creating or updating multiple folders.

- **Current month:** This is the same as the Today option but without the day portion, e.g. "2012-10".
- **Scene detection:** This sets the default detection method for scene detection. "The Scene Detection Options window" on page 311.
- **Stop motion:** This sets the default import method for the frames you capture with the Stop Motion feature. See "Stop motion" on page 333.

Keyboard

Studio provides both an extensive default set of keyboard shortcuts and a means of customizing them. The Keyboard page of the Control Panel lists all commands to which shortcuts can be applied, together with their currently-assigned shortcuts where applicable. The commands are grouped by section.



Keyboard shortcut settings window.

To add a keyboard shortcut:

- 1 Select the target command.
- 2 Click in the **Press shortcut keys** edit box.
- 3 Press the keys for the desired shortcut. If the shortcut is currently is already in use, the **Shortcut currently used** by dropdown list will show any conflicting commands.
- 4 Click the **Assign** button to assign the entered shortcut to the selected command.

Adding a shortcut does not delete associations between a particular keyboard sequence and other commands it gives access to. In fact, it is possible for different commands to use the same shortcut provided they occur in different contexts. For instance, **Ctrl+L** is the default shortcut for two commands, **Timeline > Lock Track** and **Media Editor > Rotate Left**; which one is activated depends on what part of Pinnacle Studio you are currently using.

To delete a shortcut:

- 1 Select the target command.
- 2 Choose the shortcut to delete from the Shortcuts for selected command dropdown list.
- 3 Click the Remove button.

Restoring defaults

Controls are also provided that allow you to restore the default keyboard configuration either for the currently-selected command (the **Reset Current** button) or for all commands at once (the **Reset All** button).

Project settings

On this page of the Pinnacle Studio Control Panel, you can select your default settings for new projects, titles and transitions.

New movie project format: Select a resolution (such as PAL or HD 1920x1080i), as the default for every newly created timeline. Alternatively, let the first clip placed on the timeline define the format for the project with the option Detect format from first clip added to project. The format for the current timeline may be changed at any time while editing, by using the timeline settings located at the left end of the timeline toolbar.

Detect format from first clip: Detects the format from the first clip added to the project. If the format cannot be detected, the **New movie project format** is applied.

Default durations: Set the default durations of titles, images, and transitions when they are first brought to the timeline. (Once there, of course, the clip length can be trimmed as required.)

Ruler zooming: When this option is checked, dragging horizontally on the time-ruler zooms the timeline in and out. In this mode, you will need to drag directly on the scrubber handle to scrub or to reposition the playhead. When ruler zooming is turned off, you can click anywhere on the ruler to move the playhead. In either case, zooming may also be performed by using any of:

- The Plus and Minus keys on the numeric keypad
- The Navigator at the top of the timeline
- The scrollbars under the previews

Activate trim mode by clicking near cuts: Turn this on to launch trim mode by clicking. If this setting is off, trim mode can be activated with the Trim Mode button on the timeline toolbar.

Montage scaling: Sets the default method for fitting content to the montage templates: **None** (no scaling), **Fit**, or **Crop**.

Storage locations

This page allows you to set where to save media and projects you create with Pinnacle Studio. You can separately specify locations for each of the following file types:

- **Studio Movie Projects**
- **Studio Disc Projects**
- **Titles**
- **Menus**
- **Restore Project**

This folder is used both for project packages that have been unpacked for further work and for projects imported from Studio for iPad.

- **Render Files**

This folder is for the temporary files produced while rendering items requiring intensive computation, such as video effects.

The changes made here apply only to future file operations; any existing files remain in their current locations.

Delete render files: You can delete render files to save space without concern over permanently losing data. Note, however, the files will be recreated the next time your project needs to be rendered.

Reset

You can restore your version of Pinnacle Studio to its default state (sometimes called “factory default”). All customizations will be lost, but saved projects are not affected.

To reset Pinnacle Studio to the default state


- 1 Save any open projects that you want to keep.
- 2 Click **Setup** menu > **Control Panel**.
- 3 Click **Reset** in the directory to display the **Reset to Default Settings** page.
- 4 Click the **Reset** button, and then click **OK** and restart the application.

Restore purchase

You can restore purchases that you have made through Pinnacle Studio. For example, purchases need to be restored if you move Pinnacle Studio to a new system.

To restore purchases made in Pinnacle Studio

- 1 Click **Setup** menu > **Control Panel**.
- 2 Click **Restore Purchase** in the directory to display the **Restore purchase** page.
- 3 Click the **Restore** button, and click **OK**.



Record computer actions and mouse movement by using the screen capture feature in Pinnacle Studio. This feature lets you create videos that require visualization in a few easy steps. You can also define the capture area for more emphasis and focus or integrate voice-overs. You can capture audio from your computer system and microphone and capture side-by-side apps that are displayed in Windows Snap view.

This section contains the following topics:

- Starting a screen capture project
- Recording your screen


Starting a screen capture project

To open the Screen Capture window

- Click the Live Screen Capturing program tile on the **Start** screen (Windows 8) or select Live Screen Capturing from the programs list in **Start** menu (Windows 7).

The capture area frame automatically covers the entire screen by default and appears along with the **Screen Capture** toolbar.

Screen Capture toolbar basics



Part	Description
1 Capture area frame	Specifies the display area to capture. This covers the entire screen by default.
2 Recording Controls	Contains the buttons that control your screen capture.
3 Capture area frame dimensions	Specifies the active program to capture and the exact dimensions of the area to capture in the Width and Height boxes.
4 Settings (default view)	Lets you specify file, audio, display and keyboard shortcut settings.

Recording your screen


Before taking the actual screen capture, make sure to configure the settings of the video first.

To configure your video

- 1 Click **Settings**.
- 2 In **File Settings**, specify the following details:

- **Filename** — Enter a filename for your project.
- **Save to** — Lets you specify the location where you want to save the video file.

Note: Screen captures are saved to your Documents folder (...Documents/**Pinnacle Studio Screen Capture/20.0**) by default.

Click  to add a new folder and change the location where the file is saved.

- **Format** — Choose an option from the available formats in the drop-list.
- **Frame rate** — Lets you specify the number of frames to be used when recording.

Note: Using a lower frame rate is ideal for uploading videos to the Internet as it yields a smaller file size but with less accuracy on screen dynamics. A higher frame rate produces a larger file size and is most useful for detailed presentations to capture actual screen dynamics.

- 3 In **Audio Settings**, choose one of the following **Voice** options:
 - Click **ON** to record a voice-over. Click the **Sound Check** button to test your voice input.
 - Click **OFF** to disable voice-over recording.
- 4 In the Audio Settings, choose one of the following System audio settings:
 - Click **ON** to include system or microphone audio and adjust the slider to your preference.
 - Click **OFF** to disable **System audio**.
- 5 In **Control Settings**, the following options are available:
 - **Mouse click animation** — Enable to include mouse clicks in the screen capture.
 - **Enable F10/F11 shortcut key** — Turns the keyboard shortcuts for screen capture on and off.

Note: If the screen capture shortcut keys are in conflict with the program you want to capture, it is recommended that you disable this feature to avoid accidental stops or pauses while recording.

- 6 In **Monitor Settings**, choose a display device.

Note: The program automatically detects the number of display devices available on your system. **Primary monitor** is selected by default.

To record your screen capture

- 1 Choose one of the following options:

- **Full screen** — lets you capture the entire screen. When you launch the **Screen Capture** toolbar, this option is enabled by default.
- **Custom** — lets you specify the area to capture. The capture area dimensions are displayed accordingly. You can also specify an application window to capture by choosing an option from the list of active programs.

- 2 Click **Settings** to access more options.

Note: To include voice-overs and system audio, you must enable and configure the respective settings before you start recording.

- 3 Click **Start / Resume Recording** to start the screen capture.

All activities inside the specified capture area are recorded. Screen capture starts after the countdown.

Note: You can press **F10** to stop and **F11** to pause or resume the screen capture.

- 4 Click **Stop Recording** to finish your screen capture.

Note: Note: The screen capture is added to the custom folder that you have specified and you will be prompted to add it to the Pinnacle Studio Library.



The **Multi-Camera Editor** lets you create professional-looking video compilations from footage of events that have been captured on different cameras, from different angles.

The easy multi-view workspace lets you edit on the fly, as the video clips play back simultaneously—up to *six cameras. With a simple click, you can switch from one video clip to another in the same way a broadcast studio switches from one camera to another to capture a different angle or element of a scene.

Footage can be captured on a wide range of video recording devices, such as action cameras, drone cameras, DSLRs, or smartphones. You can also include audio captured independently on a microphone.


**Number of cameras depends on the version of the software you have.*

This section contains the following topics:

- The Multi-Camera Editor workspace
- Basic steps in multi-camera editing
- Importing video and audio clips into the Multi-Camera Editor
- Synchronizing video and audio clips in multi-camera projects
- Choosing an audio source for your multi-camera project
- Editing multiple clips to create a multi-camera compilation
- Adding picture-in-picture (PIP) in the Multi-Camera Editor
- Managing multi-camera source files
- Saving and exporting your multi-camera project
- Using Smart Proxy for a faster, smoother editing experience

The Multi-Camera Editor workspace


The image below identifies the main features of the Multi-Camera Editor.




Toolbar, playback, and other controls


The controls found in the workspace are listed below.

The main toolbar includes the following controls:

 **Camera Number** — Lets you set the multi-view pane to show four or six cameras, depending on your version of the software.



Source Sync Type — Lets you synchronize the clips. For more information, see “Synchronizing video and audio clips in multi-camera projects” on page 389.



Main Audio — Lets you select a preferred audio source. For more information, see “Choosing an audio source for your multi-camera project” on page 390.



Split Clip — Lets you split a clip into segments. For more information, see “To split a clip in the Multi-Camera Editor” on page 395.



Set/Remove Marker — Lets you add markers on the Camera tracks for editing purposes, such as audio syncing.



Rotate Left and **Rotate Right** — Let you rotate clips in the Camera tracks before you add them to your Multi-Camera track or your PIP track. Note: Only unlocked tracks can be rotated.



Transition and **Duration** — Lets you apply a transition between clips in the Multi-Camera track and set the duration for the transition. For more information, see “To add a transition between multi-camera segments” on page 394.

The main preview pane includes the following controls:




Playback bar with **Home**, **Previous Frame**, **Play**, **Next Frame**, and **End** buttons.



Loop — Lets you play the selected track continuously by looping back to the start when it reaches the end.




Set Volume — Lets you adjust the audio volume for playback.





Timecode control — Lets you view and set the time/frame that appears in the main preview pane and where the scrubber


is set in the timeline. Click the arrows or a click number value to set a time/frame.


The timeline includes the following controls:


 **Source Manager** — Lets you add and remove clips. For more information, see “Managing multi-camera source files” on page 396.


 **Show/Hide Audio Waveform View** — Lets you view the audio waves for Camera and Audio tracks.

 **Lock/Unlock** — Appears on individual tracks. Locking tracks is recommended after you synchronize them.


 **Include/Exclude from Synchronization** — Lets you determine which tracks are included in the synchronization process.

 **Mute/Unmute** — Lets you turn the audio off (mute) or on (unmute) for the selected audio track.

 **Zoom to Timeline** — Located in the lower left corner of the timeline, this control lets you expand or compress your project so you can view the whole project in the timeline.

 **Zoom Level** slider — Drag the slider or click the **Zoom in** (plus sign) or **Zoom out** (minus sign) to change the zoom level for your project. This is particularly helpful when editing individual segments in the **Multi-Camera** track.

The following general controls appear in the upper-left corner of the application window:

 **Settings** — Lets you access the Proxy Manager and Save As. For more information, see “Using Smart Proxy for a faster, smoother editing experience” on page 398 and “To save your multi-camera project” on page 397.



Undo and Redo — Lets you undo or redo most actions.

Basic steps in multi-camera editing

The following steps provide a basic overview of the multi-camera editing process.

- 1 Import the video and audio clips that you want to use into the Pinnacle Studio Library.
- 2 Choose the clips in the Library and import them into the Multi-Camera Editor, using a special import window that lets you assign the clips to "Camera 1", "Camera 2", etc...
- 3 Synchronize the clips across the timeline. You can do this automatically if all the clips have audio, but there are a range of methods you can use for synchronization.
- 4 Choose the audio you want to keep (if you are using the original audio). You can choose a separate audio track as well.
- 5 Start building your multi-camera compilation. You can play all the clips simultaneously, and in the multi-view pane, click the "Camera" that you want to show. You can switch clips as many times as you like. The selected footage displays in the main preview pane. You can then review your project in **Multi-Camera** track and fine-tune it.
- 6 Exit the **Multi-Camera Editor** to further refine and output the project using Pinnacle Studio.

*Important! It's recommended that you finish your multi-camera editing before you exit the **Multi-Camera Editor**. Changes that you make to your project in another editor might not be supported if you re-open the project in the **Multi-Camera Editor**. This means that some changes will be reverted.*


Importing video and audio clips into the Multi-Camera Editor

The first step in creating a multi-camera project is to import your clips into the **Multi-Camera Editor**. In most cases, this will be a selection of clips from the same event that have been imported to the Pinnacle Studio Library.

You can work with up to six video clips at one time and include up to two independent audio clips.

To import video clips into the Multi-Camera Editor

- 1 In the Pinnacle Studio Library, select all the clips you want to use.
- 2 Do one of the following:

- On the timeline toolbar, click the **Multi-Camera Editor** button .
- Right-click a selected clip and choose **Multi-Camera Editor**.

- 3 In the **Multi-Camera Import** window, type a name in the **Project Name** box.

- 4 Verify the clips in the project clip list in the right pane.

If you want to reorder the clips, drag a clip to a new position in the list.

If you want to add more video or audio clips, choose the track you want in the Library pane, and drag it to the project clip list.

If you want to remove a clip, right-click a clip and choose **Remove**.

- 5 Click **OK**.


Synchronizing video and audio clips in multi-camera projects




You can synchronize your video and audio clips so that they are all aligned to the same moment in time. The easiest way to do this is to let the **Multi-Camera Editor** analyze the audio for each of the clips and sync the clips automatically. If your recordings are planned, you can use a special audio signal, such as clapping your hands (similar function to using a clapper board in professional shoots). Some events have natural audio cues that help the sync process, such as music performances or sporting events with a start signal.

You can also synchronize the clips by using markers, shooting time, or you can adjust them manually by dragging the clips in the timeline to the timecode you want. For example, you could use a common visual element, such as a flash to sync videos manually. These methods are helpful if your video footage doesn't include audio or the audio waveforms within the clips are difficult to sync, or you simply prefer to align the clips manually.


In some cases you might need to use a combination of the synchronization options, depending on your source footage.

To synchronize video and audio clips in the Multi-Camera Editor

- 1 After importing your clips to the **Multi-Camera Editor**, choose one of the following options from the **Source Sync Type** drop-list on the toolbar:
 - **Audio** — Click the **Sync** button  next to the drop-list to synchronize the clips in the timeline. Note: Your video clips must include audio to use this option.

- **Marker** — Select a clip in the timeline, play the clip or scrub to the position you want by using a visual cue, and click the **Set/Remove Marker** button  on the toolbar to add a marker. After a marker has been added to each clip, click the **Sync** button  on the toolbar to align the clips according to the markers.
- **Shooting Date/Time** — Click the **Sync** button  to synchronize the clips according to the shooting date and time as indicated by the metadata recorded by the camera. Note: The clocks must be in sync on the cameras to get accurate results.
- **Manual** — In the timeline, drag each clip to the position you want by using a visual cue.

Note: If there are clips that you want to exclude from the synchronization process, click the **Exclude from Synchronization** button  on the corresponding track. Click the button again (**Enable for Synchronization** ) to include the track.

Tip: After you synchronize your clips, you can use the **Lock** buttons  on the individual tracks to ensure that the tracks stay synchronized during the editing process.

Choosing an audio source for your multi-camera project


After you import and synchronize your clips in the **Multi-Camera Editor**, you can make some decisions about the audio for your project. For example, if you have four video clips, and they all include audio, it is recommended that you listen to each clip individually, and choose the

one that has the best sound quality. You can also choose to use a separate audio clip.

Other options let you use the audio from all clips, none of the clips, or switch audio (Auto) when you switch cameras, a choice you might make to take advantage of the audio captured with sport or other action footage.

By default, the audio for **Camera 1** is selected.

To choose an audio source for your multi-camera project

- 1 With your clips displaying in the **Multi-Camera Editor** timeline, on the toolbar, click the **Main Audio** box and choose a **Camera** or **Audio** clip. Click **Play**  to listen the quality of the audio for each clip.
- 2 Choose the **Camera** or **Audio** clip that you want to use for your project. The audio from all other tracks will be muted.

Other options include:

- **Auto** — Switches the audio to match the clip that you are playing
- **None** — No audio is included in the multi-camera project. You can add your audio in Pinnacle Studio, after you leave the Multi-Camera Editor.
- **All Cameras** — Plays audio from all clips, simultaneously

Tip: If you plan to edit the audio in Pinnacle Studio after you exit the Multi-Camera Editor, please note that the setting you choose in **Main Audio** determines what tracks will be available as audio tracks in Pinnacle Studio.


Editing multiple clips to create a multi-camera compilation

After you import and synchronize your clips in the **Multi-Camera Editor**, and choose your audio settings, you can start editing your clips to create a multi-camera compilation. The multi-view pane in the **Multi-Camera Editor** helps make this task fun and easy. Much like a DJ switches and blends tracks to create a new music compilation, the **Multi-Camera Editor** lets you visually switch between video tracks and blend them together with transitions.

If you notice that playback is slow or lacks smoothness, you can check the **Smart Proxy** settings. For more information, see “Using Smart Proxy for a faster, smoother editing experience” on page 398.

After you build your basic compilation using the multi-view pane and the main preview pane, you can fine-tune your project in the **Multi-Camera** track and take advantage of editing features, such as transitions and a clip splitting tool. Note that some types of edits, such as rotating a clip, must be done in the individual **Camera** tracks before you add the clips to your compilation in the **Multi-Camera** track.

To create a multi-camera compilation

- 1 With your clips in the **Multi-Camera Editor** timeline, click the **Play** button  below the main preview pane.

Footage from all cameras can be viewed simultaneously in the multi-view pane.

- 2 To start building your project, as the videos play in the multi-view pane, click the preview for the camera that you want to show. The footage from the selected camera displays in the main preview pane.




The multi-view pane appears to the left of the main preview pane. Footage from all cameras can be viewed simultaneously in the multi-view pane.


- 3 To switch cameras, click a different camera preview in the multi-view pane. You can switch cameras as many times as you like. You can review your project in the **Multi-Camera** track.



The Multi-Camera track in the timeline displays the camera segments in your compilation.


If you want to adjust the zoom level for the **Multi-Camera** track, drag the zoom level slider **+**  **-** in the lower left corner of the timeline.

- 4 After you have completed a first pass using the multi-view pane, you can refine the timing for a switch in the **Multi-Camera track** by playing your project or scrubbing to the position that you want to edit, clicking a camera segment and dragging the edge until the frame where you want the switch to occur appears in the main preview pane.



To switch a segment in the **Multi-Camera** track to a different **Camera**, right-click the segment and choose a different **Camera** from the context menu or click the camera preview in the multi-view pane.

To add a transition between multi-camera segments

- 1 In the **Multi-Camera** track, click a segment.
- 2 On the toolbar, click the **Transition** button . The button has a yellow outline when active and a transition icon ("AB") appears in the timeline

If the button is grayed out, gently drag the edge of a segment by a small amount to reactivate the button.

A **Crossfade** transition is applied by default.

- 3 On the toolbar, type a time in the **Duration** box for the transition.

Tip: You can add black or blank segments to your project. You can change a segment that is already in the **Multi-Camera** track to a black or a blank by right-clicking the segment and choosing **Black** or **Blank**. You can apply a transition between a video segment and a **Black** segment. To add a black or blank segment while playing your project, instead of clicking a camera preview in the multi-view pane, click the **Black (B)** or **Blank (O)** swatch to the right of the camera previews.



To split a clip in the Multi-Camera Editor

- 1 In the timeline, select a clip in the **Multi-Camera** or **PIP** track and click **Play** or drag the scrubber to the position where you want to make the cut.
- 2 Click the **Split Clip** button.

Note: Splitting a clip is useful when you want to replace part of a segment with a different camera, essentially adding another switch.


Adding picture-in-picture (PIP) in the Multi-Camera Editor

You can add a picture-in-picture (PIP) effect to your multi-camera project. PIP lets you play a video in one area of the screen while the main video plays in the background.




The image above illustrates the concept of picture-in-picture (PIP).

To add a picture-in-picture (PIP) effect to your multi-camera project

- 1 After you create your multi-camera compilation in the **Multi-Camera** track, click the **Play** button  or scrub to the position in the **Multi-Camera** track where you want to add a PIP effect.


- 2 In the timeline, click the circle on the **PIP** track to activate the track.

The circle will have a red fill when active .

- 3 In the multi-view pane, click the preview for the **Camera** you want to use.

The segment is added to the **PIP** track.

- 4 To set the end point for the segment, in the **PIP** track, click the end of the segment and drag it to the position you want in the timeline.


- 5 To choose a corner for the PIP, click the **Change PIP Position** button  on the **PIP** track and choose the position you want.



The PIP position can be seen in the main preview pane.

Managing multi-camera source files

You can use the **Source Manager** to add and remove video and audio clips from tracks in your multi-camera project. You can also view information about the clips, such as the duration of the clip, clip location, and you can lock or unlock tracks.

To add, remove or manage clips with the Source Manager

- 1 In the upper left corner of the timeline, click the **Source Manager** button .
- 2 In the **Source Manager** dialog box, do any of the following:

- Click the **Lock/Unlock** button for a track to unlock a track for editing or to lock a track to prevent editing.
- To add a clip to a track, select a track, click the **Add Clips** button , navigate to the clip you want to add, and click **Open**. The clip appears in the numbered list for the track.
- To delete clips from a track, select a track, in the list of clips for that track, mark the check box next to the clips that you want to delete, and click the **Delete** button .


Saving and exporting your multi-camera project

When you finish building your multi-camera project, you can save it so that it can be edited, exported, and shared from Pinnacle Studio.

*Important! It's recommended that you finish your multi-camera editing before you exit the **Multi-Camera Editor**. Changes that you make to your project in another editor might not be supported if you re-open the project in the **Multi-Camera Editor**. This means that some changes will be reverted.*

To save your multi-camera project

- Click the **OK** button at the bottom of the window to save your project to the current name (as indicated in the upper-right corner of the window). This also closes the **Multi-Camera Editor**.

If you want to rename your project, before you exit, click the **Settings** button , choose **Save As**, and type a name in the **Project name** box.

Your multi-camera project appears in the Pinnacle Studio Library.

To open your multi-camera project (**.mcam**) in Pinnacle Studio, in the **Edit** workspace, drag your multi-camera project from the Library to the Timeline. By default, the project appears as a

composite clip. To expand the clip to work with individual tracks, right-click the clip in the Timeline and choose **Edit Movie**.

Using Smart Proxy for a faster, smoother editing experience

The main purpose of **Smart Proxy** is to provide a more fluid editing and previewing experience when working with large, high resolution video files.


Smart Proxy creates lower resolution working copies of larger source files. These smaller files are called “proxy” files. Using proxy files speeds up editing of high resolution projects (for example, projects that have HDV and AVCHD source files).

Proxy files are source-dependent rather than project-dependent. In other words, proxy files can be shared among different projects.

When you render a video project, the original, high-quality video source files are used.

You can use the **Smart Proxy Manager** to enable or disable **Smart Proxy**, change the default resolution threshold that enables **Smart Proxy**, and access the **Smart Proxy File Manager** and **Smart Proxy Queue Manager** to manage existing and future proxy files.

To enable or disable Smart Proxy

- Click the **Settings** button  > **Smart Proxy Manager** > **Enable Smart Proxy**.

Note: The **Smart Proxy** feature is enabled by default if the computer’s hardware can support the feature.

To set the resolution threshold and location for Smart Proxy files

- 1 Select **Settings > Smart Proxy Manager > Settings**.
- 2 In the **Smart Proxy** dialog box, set a resolution threshold for the creation of proxy files and choose a proxy folder.

To manage proxy files

- 1 Select **Settings > Smart Proxy Manager**, and choose one of the following options:
 - **Smart Proxy File Manager** — Lists the source and proxy files. You can use this manager to delete proxy files you no longer need.
 - **Smart Proxy Queue Manager** — Lists source files for which proxy files will be generated (according to the current settings)



Before you begin troubleshooting, take some time to check your hardware and software installation.

Update your software: We recommend installing the latest operating system updates for Windows.

Check your hardware: Ensure that all installed hardware is functioning normally with the latest drivers, and is not flagged as having a problem in Device Manager (see below). If any devices are flagged you should resolve the issue before starting the installation.

Get the latest drivers: We also highly recommend installing the latest drivers for your sound card and graphics card. Each time it is launched, Pinnacle Studio verifies that both cards support DirectX.

Opening Device Manager: The Windows Device Manager, which lets you configure your system's hardware, has an important role in troubleshooting.

The first step in accessing Device Manager is to right-click on **My Computer**, and then select **Properties** from the context menu. This opens the **System Properties** window. The **Device Manager** button is listed on the left panel.

Ensure that all installed hardware is functioning normally with the latest drivers, and that nothing has been flagged in Device Manager with the yellow exclamation mark icon indicating an error condition. In the case of a driver problem that you cannot resolve yourself, contact the device manufacturer or your computer vendor for assistance.

Contacting support

Learn about all of your support options on our website:

www.pinnaclesys.com/support

Most common issues are already documented in our **Knowledgebase** and we encourage you to use this option first. To search the support Knowledgebase effectively, please include the name of the product in your query.

Forums

Please visit our discussion forums to join the conversation on Pinnacle Studio. Scroll down the forum list to find the forum in your language:

go.pinnaclesys.com/forums

Top support issues

The remainder of this chapter draws on some of the Knowledgebase articles most consulted by users. The text presented here may be less detailed or current than that provided on-line. For the full text available under each document ID, please refer to the on-line knowledge base.

Compatibility with past content

Document ID 384211

Much, but not all, of the additional creative content from previous versions Pinnacle Studio can be used directly in the current version of Pinnacle Studio, as can many content offerings from third-party providers. Some of these are included in the product itself. A few of the third-party content packages require a paid upgrade to work with

Pinnacle Studio. For some others, no compatible version has been released.

Content-support chart

Pinnacle Studio content	Support
HFX Plus, Pro, Mega	Supported – Included in Pinnacle Studio
RTFX 1	Supported*
RTFX 2	Supported*
Hollywood FX Volume 1	Supported – Included in Pinnacle Studio
Hollywood FX Volume 2	Supported – Included in Pinnacle Studio
Hollywood FX Volume 3	Supported – Included in Pinnacle Studio
Premium Pack Volume 1	Supported – Included in Pinnacle Studio
Premium Pack Volume 2	Supported – Included in Pinnacle Studio
Creative Pack Volume 1	Supported – Included in Pinnacle Studio
Creative Pack Volume 2	Supported*
Creative Pack Volume 3	Supported*
NewBlue Film Effects	Supported – Included in Pinnacle Studio
NewBlue Stabilizer	Supported – Included in Pinnacle Studio
NewBlue Video Essentials II	Supported – Included in Pinnacle Studio

NewBlue Video Essentials IV	Supported – Included in Pinnacle Studio
NewBlue Video Essentials VI	Supported – Included in Pinnacle Studio
NewBlue Video Essentials VII	Supported – Included in Pinnacle Studio
Winter Pack	Supported*
ScoreFitter Volume 1	Supported – Included in Pinnacle Studio
ScoreFitter Volume 2	Supported – Included in Pinnacle Studio
ScoreFitter Volume 3	Supported*
Title Extreme	Supported – Included in Pinnacle Studio
Third-party Ultimate/Ulimate Collection content discs	Support
Studio 11 - Stagetools: Moving Picture	Not supported
Studio 11 - BIAS SoundSoap V1 PE	Supported – Paid upgrade required
Studio 11 - ProDAD VitaScene	Supported – Paid upgrade required
Studio 12 - ProDAD VitaScene	Supported – Paid upgrade required
Studio 12 - Red Giant Magic Bullet Looks	Supported*
Studio 14 - Red Giant Knoll Light Factory	Supported*
Studio 14 - Red Giant ToonIt	Supported*

Studio 14 - Red Giant Trapcode 3D Stroke	Supported*
--	------------

Studio 14 - Red Giant Trapcode Particular	Supported*
---	------------

Studio 14 - Red Giant Shine	Supported*
-----------------------------	------------

Third-party eStore content	Support
-----------------------------------	----------------

BIAS SoundSoap V2 PE	Supported*
----------------------	------------

Studio 17 - Red Giant Magic Bullet Looks Indie Pack	Supported*
---	------------

Studio 17 - RedGiant Particular Studio Preset Pack	Supported*
--	------------

Studio 17 - RedGiant Shine Studio Preset Pack	Supported*
---	------------

Studio 17 - RedGiant ToonIt Studio Preset Pack	Supported*
--	------------

Studio 17 - RedGiant Knoll Studio Preset Pack	Supported*
---	------------

Studio 17 - Red Giant Trapcode Starglow	Not supported
---	---------------

Studio 17 - Red Giant Warp	Supported*
----------------------------	------------

ProDad Vitascene	Supported*
------------------	------------

ProDad Adorage	Supported*
----------------	------------

ProDad Adorage FX Pack 10	Supported*
---------------------------	------------

ProDad Adorage FX Pack 11	Supported*
---------------------------	------------

NewBlue Video Essentials I	Supported*
----------------------------	------------

NewBlue Video Essentials II	Supported*
-----------------------------	------------

NewBlue Video Essentials III	Supported*
------------------------------	------------

Third-party eStore content	Support
proDAD Mercalli	Supported*
Third-party bonus DVD plugins	Support
Bravo Studio 1, 2 & 3	Not supported
BWPlugins 1, 2 & 3	Not supported
Dziedzic Effects Pack 1 & 2	Not supported
eZedia Effects	Not supported
NewBlue Art Effects 1	Not supported
NewBlue Effects	Not supported
NewBlue Time Effects 1	Not supported
PE CameraPOV	Not supported
proDAD Adorage	Supported*
proDAD Heroglyph 1	Not supported
proDAD Heroglyph 2	Not supported
proDAD Vitascene 1.0	Supported*
StageTools Moving Picture Full	Not supported
StageTools Moving Picture LE	Not supported
Vance Effects	Not supported
Algorithmix	Not supported
NewBlue Audio Enhancements 1	Not supported
NewBlue Audio Essentials 1	Not supported
NewBlue Audio Essentials 2	Not supported
NewBlue Audio Essentials 3	Not supported
NewBlue Audio Essentials 4	Not supported

*Might not be supported in the 64-bit version of Pinnacle Studio.

Capture hardware compatibility

Document ID 384431

Pinnacle Studio has been tested and found to work successfully with a wide variety of video capture hardware. However, some older devices are not supported.

Supported hardware

The following capture devices will work with all versions of Pinnacle Studio.

USB-based

- 710-USB
- 510-USB
- 700-USB
- 500-USB
- MovieBox Deluxe
- DVC-90
- DVC-100
- DVC-101
- DVC-103
- DVC-107
- DVC-130 (no 64-bit drivers available)
- DVC-170 (no 64-bit drivers available)

PCI-based

- 700-PCI (Pinnacle Studio Deluxe 2)
- 500-PCI (Pinnacle AV/DV)
- Any 1394 card

Unsupported hardware

The following list of hardware came with older versions of Studio and is no longer in warranty or supported.

- DC10
- DC10 Plus
- MovieBox® DV
- Dazzle® DVC 80, 85
- Linx
- MP 10
- S400

Serial number information

Document ID 384215

This FAQ will give you information on the location of your Pinnacle Studio serial numbers, and how to use your serial number from a previous version to activate an upgrade to Pinnacle Studio.

Finding your serial number

For a product that you downloaded, the serial number is shown on the confirmation page at the end of the ordering process, and in the confirmation email sent at that time.

If you own a physical copy of the product, the serial number is shown on either the inside or the outside of the DVD case, if one is included; and on the outside of the paper sleeve otherwise.

If you have lost your serial number, please check the knowledge base for document 232809, How to replace a lost Pinnacle Studio serial number.

Looking up your customer information:

- 1 Start by logging in at **www.pinnaclesys.com**.
- 2 Browse to 'Your Product'.
- 3 Choose your products again from the products section.
- 4 Your serial number is listed in the 'Your products' window that comes up.

Using a serial number when upgrading

To upgrade Pinnacle Studio, you will need the serial number from the old version.

After you have found your old serial number, start the install. A window will appear asking for both the new and old numbers. Put them in the correct windows and click **Next**.

Error or crash while installing

Document ID 284219

Here are some tips for troubleshooting errors or crashes that could occur while installing Pinnacle Studio.

Specific Errors

Error 1402: If you are getting a 1402 error during installation, please follow the instructions in document 364555 in the knowledge base, Error 1402 on installation.

Error on install "Setup will now abort installation": If this error occurs during installation, please follow the instructions in knowledge base document 363187, Error on install "Setup will now abort installation".

General troubleshooting

Here are some further avenues to explore if you are having trouble getting the application to install.

Try cleaning the disc: Inspect the install disc, checking its surface for smudges and dirt. If cleaning is necessary, use a soft cloth, not paper towels or any abrasive material. Wipe from the center of the disc to the outer edge rather than a circular motion. Once the disc is clean, try installing again.

Another optical drive: Many systems have two optical drives; for instance, a DVD burner and a separate DVD reader. Put the disc that won't install into the other drive, if available, and retry.

Restart the computer: In some cases the installation can crash if Windows Update is running. If that happens, it is best to restart the system as requested by Windows before trying again to install Studio.

Startup tasks/programs: If you are familiar with msconfig, you can use this tool to disable any programs launched at start-up that might be interfering with the Studio installer.

When all else fails

If the disc is damaged with deep scratches or cracks so that it won't install, please contact support. Please have your Pinnacle Studio order number or proof of purchase (receipt) from the store available.

Hangs or crashes while launching

Document ID: 284223

If Pinnacle Studio previously launched successfully and now does not, review any changes that have been made to the computer recently for

possible clues. If necessary, undo the changes to see if the problem goes away.

Further troubleshooting steps:

- 1 **Restart the computer:** Unstable software behavior of undetermined cause can often be fixed by resetting the system. This is almost always a good place to start when troubleshooting.
- 2 **Wait a few minutes:** If Pinnacle Studio still won't launch, wait a few minutes to let it finish launching. On some computers it may take a little while for the launch to complete.
- 3 **Update Studio:** When troubleshooting any problem, it is always best to use the latest version of the software if possible.
- 4 **Disconnect capture hardware:** If possible, unplug any capture hardware and try launching Pinnacle Studio again. If you can't launch with your webcam plugged in, try it unplugged, and vice-versa. You may have to set the webcam up in the same way every time you launch Studio.
- 5 **Download and reinstall hardware drivers:** During the Studio software launch process we do check that you have a DirectX compatible graphics and sound card. Download and reinstall the latest version of the driver for the graphics card that is on your system. If you need assistance with this step, please contact the graphics card manufacturer.
- 6 **End background tasks:** There are a couple ways to accomplish this. One is to use start-up management software to assist in eliminating unnecessary programs that launch on Windows start-up. Many shareware and freeware programs of this type have been created. Use an Internet search engine such as Google or Yahoo to search for 'startup managers'. We don't endorse any particular one, but recommend you try a couple to see which one works best for you.

Alternatively, you can also use the Microsoft System Configuration Utility (msconfig), which is part of Windows, to disable start-up programs.

Whichever route you take, we recommend disabling all programs and then re-enabling them one at a time until the conflicting program is located.

- 7 **Reinstall:** If all of the above fail, you may want to try uninstalling Pinnacle Studio from the Control Panel “Programs and Features” list. Once it is uninstalled, reinstall Pinnacle Studio and try launching again.

Troubleshooting software crashes

Document ID: 384231

If Studio is crashing repeatedly, the cause of the problem is most likely a configuration issue, or a problem with a project file. Many customers fix this type of issue by:

- Optimizing their computer
- Rebuilding a corrupt project
- Recapturing a corrupt clip, etc.
- Uninstalling and reinstalling Pinnacle Studio

For further troubleshooting, determine which of the failure modes below best matches your problem, then read on to review the suggested troubleshooting steps for that case.

Case 1: Pinnacle Studio crashes randomly. There doesn't seem to be any one thing that will cause the crash, but it seems to crash frequently.

Case 2: Pinnacle Studio crashes after a user action such as a click on a certain tab or button. The crash is predictable and consistent.

Case 3: Pinnacle Studio crashes repeatedly when you perform some specific combination of steps.

Case 1: Studio crashes randomly

Here are some troubleshooting steps to try. You can work through them in order until you get a result.

Get the latest version

Make sure that you have the latest version of Pinnacle Studio installed.

Optimize settings

Check these Preview settings in Pinnacle Studio that may be adjusted to get better results.

Quality: Select 'Fastest Playback' and see if your results improve.

Optimization threshold: Turning this setting off will let you discover whether it helps your crashing problem. However, poor preview playback may result if the threshold is not used, or is not properly adjusted.

Render while play: Try turning off this option if you notice that the crash tends to occur while you are previewing.

End background tasks

It is important with this type of problem to unload any background processes before using Pinnacle Studio.

Many 'tasks' (software programs) run 'in the background' on every Windows system, usually without drawing attention to themselves.

Occasionally, however, one of these may be the cause of instability in a particular application.

In Windows 7 or Windows 8, the **Ctrl+Alt+Delete** key combination leads to the Task Manager. The Processes tab will show you what is running. See knowledge base document 229157, [How do I turn off background programs that are interfering with system performance and software installation?](#), for detailed instructions about how to proceed.

Defragment your hard drive

See knowledge base document 232457, [Windows hard disk defragmenting information](#), for instructions and advice on this step.

Update video and audio drivers

Make sure that you have the latest sound and video card drivers loaded from their manufacturer's websites.

You can determine what sound and video card you have by checking in the **Device Manager** list in Windows (under **Sound, video and game controllers** and **Display adapters**). To determine the manufacturer and date of its driver, double-click the card name. Now click the **Driver** tab to see all the driver information including **Driver Provider** and **Driver Date**.

Driver updates are often released through the websites of the hardware manufacturers.

Update Windows

Make sure you have all available Windows updates for your computer.

Optimize computer performance

Windows provides a built-in tool for this purpose.

1. Right-click **Computer** (or **My PC**) and select **Properties**.
2. Click the **Advanced System Settings** link.
This will bring up the **System Properties** window.
3. Click the **Settings** button in the **Advanced** section.
4. Select **Adjust for best performance**, and click **OK**.

Free space on boot drive

Make sure you have 10 GB or more on your boot drive for paging. If you do not have 10 GB, you will need to free up some space.

Uninstall and reinstall Pinnacle Studio

If none of the suggestions so far help, you could have a corrupted installation of Studio. If that is the case, you should try uninstalling Pinnacle Studio and then reinstalling it. You can uninstall Pinnacle Studio from the Windows **Control Panel**, by clicking **Uninstall a program**. Uninstall Pinnacle Studio. Once Pinnacle Studio is uninstalled, install it again from your disc or program download.

Check for a corrupt project

Try rebuilding the first few minutes of your project. If this does not cause any instability, try adding a few more minutes to the project. Continue to rebuild the project if the system remains stable.

Check for corrupt media

If the instability seems to occur when you manipulate certain audio or video clips, you should recapture or import the audio or video. If the media were imported and created by another application, you should capture with Studio and create a test project. While Studio works with many video formats, the clip you have may be corrupt or in an uncommon variant format. If you have a wav or mp3 files that seems to be problematic, convert the file to the other format and then import the file.

Reinstall Windows

This is quite a drastic step, but if the steps to this point have not helped, Windows itself may be corrupt. The heavy processing demands made on your system by a multimedia authoring tool like Pinnacle Studio can reveal instabilities that might not show up with ordinary applications. One way to help determine if your Windows install is part of the problem is to run the Microsoft system information tool. This tool keeps track of when Windows crashes.

To use the system information tool:

- 1 In the Windows **Run** dialog box (Windows key + **R**), type **Msinfo32** in the search window. Press **Enter** to bring up the **System Information** window.
- 2 Expand the **Software environment** category on the left side of the window.
- 3 Click on **Windows error reporting**.

If the Windows Error Reporting window has many entries, it could be an indication that the OS is unstable or that the computer has a hardware issue. Inspecting the entries may show what caused the crash. If most of the crashes involve system software like Window

Explorer, then the OS has a problem. Frequent random crashes are another common sign of a corrupt Windows installation.

Case 2: Studio crashes after a user action

If Pinnacle Studio crashes, or tends to crash, when you click on some particular tab or button, start by trying all of the steps in Case 1 above. Such a problem usually means that Studio is not installed properly or has become corrupt, so uninstalling Studio, then reinstalling it, and then patching the latest version should correct the situation.

To try to determine if the failure is specific to a particular project, create a test project and add a few scenes to the timeline from the sample video. Then click on the tab or button that seems to cause the failure. If this test project does not crash, it may mean that the problem is with the actual project you are working on rather than with Studio or your system. If the test project does fail, please contact support and provide us with the details on the exact failure mode. We will try to recreate the problem.

Case 3: Studio crashes repeatably

If Studio crashes when you performing some specific procedure or combination of steps, start by trying the troubleshooting steps given above for Case 1, since this is just a more complicated version of Case 2. It is often very difficult to pin down the exact sequence of steps that results in a failure. A simple test project using the sample video, as noted above, will be a big help first in your own investigations, and second to help achieve a fast resolution if support is required.

Export problems

If errors are reported, or the application freezes or performs incorrectly while exporting a file or disc, please check our knowledge base for articles regarding the specific failure scenario you are experiencing.

Disc playback problems

Document ID: 384235

If you have a problem with DVDs created by Studio not playing back, or appearing to be blank, the steps below should help to resolve it.

Other kinds of playback problems may be addressed elsewhere in the knowledge base.

- If the video on your disc plays back, but the sound does not, read document 222577, Discs burned with Studio have no sound.
- If only a portion of your disc project appears on the DVD, or if recent changes are missing, try document 219785, DVD created with Studio is missing part of the project.

If your DVD does not play back, or appears blank:

- 1 Check the disc for cleanliness. Ensure that there are no obvious smudges or scratches on the disc surface. If the disc is dirty, clean it with a soft cloth (don't use a paper towel) by wiping the DVD radially from the center to the outside edge, not in a circular motion.
- 2 Insert the disc into a DVD drive on the computer and verify that it contains file-system folders.
 - Double-click **My Computer** or **This PC**.
 - Right-click the DVD drive and choose **Explore**.

There should be two folders on the DVD, named 'audio_ts' and 'video_ts'. The 'audio_ts' folder should be empty, while 'video_ts' should contain files with bup, ifo and vob extensions.

If the files are present, the issue definitely relates to playback as such rather than the burning of the disc. Conversely, if the disc is in fact blank, you are looking at a burn problem rather than a playback problem. In that case, follow the instructions in document 214533, Studio burn problems.


- 3 If the disc fails in your set-top DVD player, try playing it back on the computer. The disc should play back successfully when DVD player software like PowerDVD and WinDVD are used. DVD playback in Windows Media Player may work depending on your version of Windows. If you have problems playing the disc DVD even on your computer's DVD drive, read document 221479, Playing DVDs on your computer.
- 4 Try playing the DVD on other set-top players. Some equipment may not play a certain brand of DVD or a certain DVD media format (-R, +R, -RW or +RW).

If you are uncertain whether the DVD player supports a given media type, check the manufacturer's website for information.

If the disc type is not supported by the player, you will need to recreate the disc in another format. If the disc plays in one DVD player but not another, it may be that the second player is on the verge of device failure, or that it cannot reliably read writable media. In this situation, experiment with DVD brands and types until you find a combination that works dependably on your equipment.


- 5 Confirm that the project you created is set for the playback format used in your region (e.g. NTSC for North America, PAL for Europe). If the project, and hence the disc, are in the wrong format, some DVD players will not be able to play the disc.

To check the project video format, click the gear icon at the top left of the timeline in the **Disc Editor**.



Opening the timeline settings dialog.

On the Timeline Settings dialog, make sure that the **Size** dropdown is set to the right standard.



Checking the Size setting.

You can also set the default video standard for projects on the **Project Settings** page of the Pinnacle Studio setup dialog.



To shoot good video, then create from it an interesting, exciting or informative movie, is something anyone with a little basic knowledge can achieve.

Starting from a rough script or shooting plan, the first step is to shoot your raw video. Even at that stage, you should be looking ahead to the editing phase by making sure you will have a good set of shots to work from.

Editing a movie involves juggling all your fragments of footage into some kind of harmonious whole. It means deciding on the particular techniques, transitions and effects that will best express your intent.

An important part of editing is the creation of a soundtrack. The right sound – dialog, music, commentary or effect – can work with the visuals to create a whole greater than the sum of its parts.

Pinnacle Studio has the tools you need to create professional-quality home video. The rest is up to you – the videographer.

Creating a shooting plan

It is not always necessary to have a shooting plan, but it can be very helpful for large video projects. The plan can be as simple or as complex as you like. A simple list of planned scenes might be enough, or you might also want to include some notes regarding detailed camera directions or prepared dialog. The really ambitious can go all the way to a full-fledged script in which every single camera angle is

described in detail along with notes about duration, lighting and props.

Title: Jack on the kart track

No.	Camera angle	Text / Audio	Duration	Date
1	Jack's face with helmet, camera zooms out	"Jack is driving his first race...". Noise of engines in the background.	11 sec	Tue. 06/22
2	On the starting line, driver's perspective; low camera position.	Music is played in the hall, noise of engines.	8 sec	Tue. 06/22
3	Man with a starting flag is accompanied into the scene to the start position. Camera stays, man goes out of the scene after start.	"Let's go...". Carry out the start, add starting signal.	12 sec	Tue. 06/22
4	Jack on the start position from the front, camera follows, shows Jack up to the bend, now from behind.	Music from the hall no longer audible, fade up same music from CD over noise of engines.	9 sec	Tue. 06/22
5	...			

Draft of a simple shooting plan

Editing

Using varying perspectives

An important event should always be shot from varying perspectives and camera positions. Later, during editing, you can use the best camera angles alone or in combination. Make a conscious effort to

tape events from more than one camera angle (first the clown in the circus ring, but then also the laughing spectator from the clown's point of view). Interesting events can also take place behind the protagonists or the protagonists may be seen in a reverse angle. This can be helpful later when trying to establish a sense of balance in the movie.

Close-ups

Don't be stingy with close-ups of important things or persons. Close-ups usually look better and more interesting than long shots do on a television screen, and they work well in post-production effects.

Long shots / Semi-long shots

Long shots provide the viewer with an overview and establish the scene of the action. However, these shots can also be used to tighten longer scenes. When you cut from a close-up to a long shot, the viewer no longer sees the details, and it is thus easier to make a chronological jump. Showing a spectator in a semi-long shot can also provide visual relief from the main action, and the opportunity of a transition away from the action if desired.

Complete actions

Always shoot complete actions with a beginning and an end. This makes editing easier.

Transitions

Cinematic timing requires some practice. It is not always possible to film long events in their entirety, and in movies they often have to be represented in severely abbreviated form. Nonetheless, the plot should

remain logical and cuts should almost never call attention to themselves.

This is where the transition from one scene to the next is important. Even if the action in neighboring scenes is separated in time or space, your editorial choices can make the juxtaposition so smooth that the viewer bridges the gap without conscious attention.

The secret to a successful transition is establishing an easily-felt connection between the two scenes. In a plot-related transition, the connection is that of successive events in an unfolding story. For example, a shot of a new car might be used to introduce a documentary about its design and production.

A neutral transition doesn't in itself imply a story development or a change of time or place, but can be used to smoothly connect different excerpts from a scene. For example, cutting away to an interested audience member during a podium discussion lets you then cut back unobtrusively to a later point in the same discussion, omitting the part between.

External transitions show something apart from the action. For example, during a shot inside the marriage registry, you might cut to the exterior of the marriage registry, where a surprise is already being set up.

Transitions should underscore the message of the film and must always fit the respective situation, in order to avoid confusing viewers or distracting from the actual story line.

Logical sequence of action

The shots strung together during editing must interact appropriately in relation to the action. Viewers will be unable to follow the events

unless the story line is logical. Capture viewer interest from the very beginning with a fast-paced or spectacular start and maintain that interest until the very end. Viewers can lose interest or become disoriented if scenes are strung together in a manner that is illogical or chronologically false, or if scenes are too hectic or short (under three seconds). There should be some continuity of motif from one scene to the next.

Bridging the gaps

Make an effort to bridge the gaps from one filming location to another. You can use close-ups, for example, to bridge chronological jumps, zooming in on the face, then back out after a few seconds onto a different scene.

Maintain continuity

Continuity – consistency of detail from one scene to the next – is vital in providing a satisfying viewing experience. Sunny weather does not fit with spectators who opened their umbrellas.

Tempo of cuts

The tempo at which a film cuts from one scene to the next often influences the message and mood of the film. The absence of an expected shot and the duration of a shot are both ways of manipulating the message of the film.

Avoid visual disjunctions

Stringing together similar shots in succession may result in visual disjunctions. A person may be in the left half of the frame one moment and in the right half of the frame the next, or may appear first with and then without eyeglasses.

Do not string together pan shots

Pan shots should not be strung together unless they have the same direction and tempo.

Rules of thumb for video editing

Here are some guidelines that may be helpful when you come to edit your movie. Of course, there are no hard and fast rules, especially if your work is humorous or experimental.

- Do not string together scenes in which the camera is moving.
- Pans, zooms, and other moving shots should always be separated by static shots.
- Shots that follow one another should be from different camera positions. The camera angle should vary by at least 45 degrees.
- Sequences of faces should always be shot alternately from varying angles of view.
- Change perspectives when shooting buildings. When you have similar shots of the same type and size, the picture diagonal should alternate between front left to rear right and vice versa.
- Make cuts when persons are in motion. The viewer will be distracted by the ongoing motion and the cut will go almost without notice. In particular, you can cut to a long shot from the middle of the motion.
- Make harmonious cuts; avoid visual disjunction.
- The less motion there is in a shot, the shorter it should be. Shots with fast movements can be longer.
- Long shots have more content, so they should also be shown longer.

Ordering your video sequences in a deliberate manner not only permits you to produce certain effects, but even enables you to convey messages that cannot or should not be shown in pictures. There are basically six methods of conveying messages through cuts. Let's look at each in turn.

Associative cuts

Shots are strung together in a certain order to trigger associations in the mind of the viewer, but the actual message is not shown. Example: A man bets on a horse race and, in very next scene, we see him shopping for an expensive new car at a car dealership.

Parallel cuts

Two actions are shown in parallel. The film jumps back and forth between the two actions; making the shots shorter and shorter until the end. This is a way of building suspense until it peaks. Example: Two different cars drive from different directions at high speed toward the same intersection.

Contrast cuts

The film purposely cuts unexpectedly from one shot to another, very different shot, in order to point up the contrast to the viewer. Example: A tourist lying on the beach; the next shot shows starving children.

Substitutionary cut

Events that cannot or should not be shown are replaced by other events (a child is born, but instead of childbirth, the blossoming of a flower bud is shown).

Cause and effect cuts

Shots are related by virtue of cause and effect: without the first shot, the second would be incomprehensible. Example: A man fights with his wife and, in the very next shot, is seen sleeping under a bridge.

Formal cuts

Shots that vary in content can be strung together if they have something in common – the same shapes, colors, or motions, for example. Examples: A crystal ball and the earth; a yellow raincoat and yellow flowers; a falling skydiver and a falling feather.

Soundtrack production

Soundtrack production is an art, but it is an art one can learn. Of course, it is no easy task to create a superb narration, but short, informative comments are often very helpful for the viewer. Whatever narration there is should sound natural, expressive and spontaneous, not wooden or stiff.

Keep comments brief

A general rule applicable to all commentary is that less is more. Pictures should speak for themselves, and things that are evident to viewers from the pictures require no comment.

Preserve original sounds

Spoken commentary should be mixed with both the original sounds and the music in such a way that the original sounds can still be heard. Natural sound is part of your video footage and should not be cut away altogether if at all possible, because video without natural sound can easily seem sterile and lacking in authenticity. Frequently, however,

the recording equipment captures noises from aircraft and cars that do not appear in the scene later. Sounds such as these, or loud wind noises, which can be distracting or annoying, should be masked, filtered or replaced with appropriate narration or music.

Select appropriate music

Appropriate music adds a professional finishing touch to your movie and can do a lot to reinforce the message of a video. The music selected, however, should always be appropriate to the message of the film. This is sometimes a time-consuming matter and a challenge, but greatly appreciated by the viewer.

Title

The title should be informative, describe the contents of the movie, and arouse interest. If it's also a striking turn of phrase, so much the better.

When it comes to presentation, the Title Editor gives almost unlimited scope for creative visuals. It's one place in your production where you're not tied to the reality of actual footage, so you can let your fancy run free.

Of course, the ultimate goal is to communicate, so some basics almost always hold true. For instance, a concise title in a large, legible font is likelier to get its message across than one that is over-decorated or too long.

Title colors

The following combinations of background and text are easy to read: white with red, yellow with black, and white with green. Exercise caution with very white titles on a very black background. Some video

systems are unable to handle contrast ratios in excess of 1:40 and are unable to reproduce such titles in detail.

Time on screen

As a rule of thumb, a title should be displayed long enough to be read twice. Allow about three seconds for a title with ten letters. Allow an additional second of on-screen time for every five additional letters.

'Found' titles

Besides postproduction titles, natural titles like directional signs, street signs or title pages of local newspapers also create interesting possibilities.



Multimedia terminology contains computer and video terminology. The most important terms are defined below.

720p: A high-definition (HD) video format with a resolution of 1280x720 and progressive (non-interlaced) frames.

1081i: A high-definition (HD) video format with a resolution of 1440x1080 and interlaced frames.

ActiveMovie: Software interface by Microsoft for the control of multimedia devices under Windows. See *DirectShow*, *DirectMedia*

ADPCM: Acronym for Adaptive Delta Pulse Code Modulation, a method of storing audio information in a digital format. This is the audio encoding and compression method used in CD-I and *CD-ROM* production.

Address: All available saving positions in a computer are numbered (addressed). By means of these addresses each saving position can be occupied. Some addresses are reserved for the exclusive use of particular hardware components. If two components are using the same address, this is called an "address conflict".

Aliasing: An inaccurate display of an image due to the limitations of the output device. Typically, aliasing appears in the form of jagged edges along curves and angled shapes.

Anti-aliasing: A method of smoothing out jagged edges in bitmap images. This is usually accomplished by shading the edges with pixels

intermediate in color between the edge and the background, making the transition less apparent. Another method of anti-aliasing involves using higher resolution output devices.

Aspect ratio: The ratio of width to height in an image or graphic. Keeping the aspect ratio fixed means that any change to one value is immediately reflected in the other.

AVI: Audio Video Interleaved, a standard format for digital video (and *Video for Windows*).

Batch capture: An automated process that uses an *Edit decision list* (EDL) to locate and recapture specific clips from a videotape, usually at a higher data rate than the clip was originally captured.

BIOS: Acronym for Basic Input Output System, which refers to basic input and output commands saved in a ROM, PROM or EPROM. The essential task of the BIOS is the control of input and output. When the system is started, the ROM-BIOS carries out some tests. See *Parallel port*, *IRQ*, *I/O*.

Bit: Abbreviation of “Binary digiT”, the smallest element of a computer’s memory. Among other things, bits are used to store the color values of pixels in an image. The more bits used for each *Pixel*, the greater the number of available colors. For example:

- 1-bit: each pixel is either black or white.
- 4-bit allows 16 colors or gray shades.
- 8-bit allows 256 colors or gray shades.
- 16-bit: allows 65,536 colors.
- 24-bit: allows about 16.7 million colors.

Bitmap: An image format made up of a collection of dots or “pixels” arranged in rows. See *Pixel*.

Blacking: The process of preparing a videotape for insert editing by recording video black and continuous control track on the entire tape. If the recording deck supports timecode, continuous timecode will be recorded simultaneously (also called “striping”).

Brightness: Also “luminance”. Indicates the brightness of video.

Byte: One byte corresponds to eight bits. With one byte, exactly one alphanumeric character can be displayed (i.e. a letter, number).

CD-ROM: Mass storage media for digital data, such as digital video. CD-ROMs can be read from but not written (recorded) onto; ROM is an acronym for Read-Only Memory.

Channel: Classifications of information within a data file to isolate a particular aspect of the file. For example, color images use different channels to classify the color components in the image. Stereo audio files use channels to identify the sounds intended for the left and right speakers. Video files use combinations of the channels used for image and audio files.

Clip: In Pinnacle Studio, any media element used on the timeline of a movie or disc project. Clip media include videos, audio files, photos, titles, and Montage.

Clipboard: A temporary storage area shared by all Windows programs, used to hold data during cut, copy, and paste operations. Any new data you place onto the clipboard immediately replaces the existing data.

Closed GOP: See *GOP*.

Codec: Contraction of compressor/decompressor – an algorithm that compresses (packs) and decompresses (unpacks) image data. Codecs can be implemented in either software or hardware.

Color depth: Number of bits delivering the color information for each pixel. A 1-bit color depth allows $2^1=2$ colors, an 8-bit depth allows $2^8=256$ colors, and a 24-bit depth allows $2^{24}=16,777,216$ colors.

Color model: A way to mathematically describe and define colors and the way they relate to each other. Each color model has its own strengths. The two most common color models are ??RGB and ??YUV.

Color saturation: Intensity of a color.

Complementary color: Complementary colors are opposite in value to primary colors. If you were to combine a color with its complement, the result would be white. For example, the complementary colors of red, green and blue are cyan, magenta and yellow respectively.

COM Port: A serial port located on the back of your computer for attaching a modem, plotter, printer or mouse to the system.

Composite video: Composite video encodes luminance and chrominance information into one signal. *VHS* and 8mm are formats that record and play back composite video.

Compression: A method for making files smaller in size. There are two types of compression: lossless and lossy. Files compressed with a lossless scheme can be restored unchanged from their original state. Lossy schemes discard data during compression, so some image quality is sacrificed. The loss of quality may be negligible or severe depending on the amount of compression.

Cropping: Choosing the area of an image to be displayed.

Data rate: The quantity of data transmitted per unit time; for example, the number of bytes read from or written to a hard drive per second, or the amount of video data processed per second.

Data transfer rate: The measurement of the speed at which information passes between the storage device (e.g. CD-ROM or hard drive) and the display device (e.g. monitor or MCI device). Depending on the devices used, some transfer rates may offer better performance than others.

DCT: Discrete Cosine Transformation – part of JPEG image data compression and related algorithms. The brightness and color information is saved as a frequency coefficient.

DirectShow: System extension by Microsoft for multimedia applications under Windows. See *ActiveMovie*.

DirectMedia: System extension by Microsoft for multimedia applications under Windows. See *ActiveMovie*.

DirectX: A bundle of several system extensions developed by Microsoft for Windows 95 and its successors to make possible video and game acceleration.

Dissolve: A transitional effect in which the video is faded from one scene to the next.

Dithering: Increasing the number of apparent colors in an image by the application of color patterns.

Decibel (dB): A unit of measurement of the loudness of sound. An increase of 3 dB doubles the loudness.

Digital8: Digital videotape format that records DV-coded audio and video data on Hi8 tapes. Currently sold only by Sony, Digital8 camcorders and VCRs can play both Hi8 and 8mm cassettes.

Digital video: Digital video stores information bit by bit in a file (in contrast to analog storage media).

DMA: Direct Memory Access.

Driver: A file containing information needed to operate peripherals. The video capture driver operates a video capture board, for example.

DV: Digital videotape format for recording digital audio and video on 1/4"-wide metal evaporated tape. Mini-DV tapes hold up to 60 minutes of content, while standard DV tapes can hold up to 270 minutes.

ECP: "Enhanced Compatible Port". Enables accelerated bi-directional data transfer via the parallel port. See *EPP*.

Edit decision list (EDL): A list of clips and effects in a particular order that will be recorded to your output disc or file. Studio allows you to create and edit your own edit decision list by adding, deleting and reordering clips and effects in the Movie Editor and the Disc Editor.

EPP: "Enhanced Parallel Port". Enables accelerated bi-directional data transfer via the parallel port. See *ECP*.

EPROM: "Erasable Programmable Read-Only Memory". Memory chip that after programming retains its data without power supply. The memory contents can be erased with ultraviolet light and rewritten.

Fade to/from black: A digital effect that fades up from black at the beginning of a clip or down to black at the end.

Field: A frame of video consists of horizontal lines and is divided into two fields. The odd lines in the frame are Field 1; the even-numbered lines are Field 2.

File format: The organization of information within a computer file such as an image or word processor document. The format of a file is usually indicated by its "file extension" (e.g. doc, avi or wmf).

Filters: Tools that alter data to produce special effects.

FireWire: Apple Computer's trademarked name for the *IEEE-1394* serial data protocol.

Field: A frame of interlaced video consists of horizontal lines and is divided into two fields. The odd lines in the frame are Field 1; the even-numbered lines are Field 2.

Frame rate: The frame rate defines how many frames of a video sequence are played in one second. The frame rate for NTSC video is 30 frames per second. The frame rate for PAL video is 25 frames per second.

Frame size: The maximum size for displaying image data in a video or animation sequence. If an image intended for the sequence is larger than the frame size, it must be cropped or scaled to fit.

Frequency: The number of repetitions in a periodic process (like a sound wave or an alternating voltage) per unit of time. Usually measured in repetitions per second, or Hertz (Hz).

GOP: In MPEG compression the data stream is first divided into "Groups Of Pictures" – sections of several frames each. Each GOP contains three types of frames: I-Frames, P-Frames (pictures) and B-Frames.

GOP size: The GOP size defines, how many I-Frames, B-Frames and P-Frames are included in one GOP. For example, current GOP sizes are 9 or 12.

Hardware codec: Compression method that uses special hardware to create and play back compressed digital video sequences. A hardware codec may offer better encoding speed and image quality than a codec implemented completely in software. See *Codec, Software codec*

HD: High Definition video. Most HD formats in use have a resolution of either 1920x1080 resolution or 1280x720 resolution. A substantial difference exists between the 1080 and 720 standards: the larger format uses 2.25 more pixels per frame. This difference substantially increases requirements for processing 1080 content in terms of encoding time, decoding speed, and storage. The 720 formats are all progressive. The 1080 format has a mixture of progressive and interlaced frame types. Computers and their displays are inherently progressive, whereas television broadcasting has been based on interlaced techniques and standards. For HD terminology, we indicate progressive with the letter 'p' and interlaced with the letter 'i'.

HDV: A format for the recording and playback of high-definition video on a DV cassette tape. has been established as the 'HDV' format. Instead of the 'DV' codec, HDV uses a flavor of MPEG-2. There are two varieties of HDV: HDV1 and HDV2. HDV1 is 1280x720 resolution with progressive frames (720p). The MPEG transport stream is 19.7 Mbps/s. HDV2 is 1440x1080 resolution with interlaced frames (1080i). The MPEG transport stream is 25 Mbps/s.

Hi8: Improved version of Video8 using S-Video recorded on metal particle or metal evaporated tape. Because of higher luminance resolution and wider bandwidth, the result is sharper pictures than Video8.

HiColor: For images, this normally means a 16-bit (5-6-5) data type that can contain up to 65,536 colors. TGA file formats support images of this type. Other file formats require prior conversion of a HiColor image into TrueColor. For displays, HiColor normally refers to 15-bit (5-5-5) display adapters that can display up to 32,768 colors. See *Bit*.

Huffman coding: Technique used in JPEG and other data compression methods in which seldom occurring values receive a long code, while frequently-occurring values receive a short code.

IDE: “Integrated Device Electronics” – a hard-drive interface that combines all drive control electronics on the drive itself, rather than on the adapter connecting the drive to the expansion bus.

IEEE-1394: Developed by Apple Computers and introduced as FireWire, this is a serial data transmission protocol with rates up to 400 Mbits/sec. Sony offers a slightly modified version for transmitting DV signals named i.LINK, providing transmission speeds up to 100 Mbits/sec.

Image: An image is a reproduction, or picture of something. The term is often applied to digitized pictures, consisting of pixels, that can be shown on a computer display and manipulated by software.

Image compression: Method of reducing the amount of data required to store digital image and video files.

Interlaced: The screen refresh method used by television systems. The PAL TV image consists of two interleaved image halves (fields) of 312½ lines each. The NTSC TV image consists of two image halves of 242½ lines each. The fields are displayed alternately to produce a blended image.

Interleave: An arrangement of audio and video to promote smoother playback and synchronization or compression. The standard AVI format equally spaces audio and video.

I/O: Input/Output.

IRQ: “Interrupt Request”. An “interrupt” is a temporary break in the main processing stream of a computer so that housekeeping or background tasks can be performed. Interrupts can be requested by either hardware (e.g. keyboard, mouse) or software.

JPEG: Joint Photographic Experts Group, and the standard developed by them for compressing digital frames based on DCT.

Kbyte (also KB): One Kbyte (kilobyte) contains 1024 bytes. The “K” here stands for the number 1024 (2¹⁰), and not 1000 as in the metric prefix.

Key color: A color whose display is suppressed so that a background image can show through. Most commonly used when overlaying one video sequence on top of another, allowing the underlying video to display wherever the key color appears.

Keyframe: A video frame for which the value of a particular parameter of a video or audio effect is specified. During playback the animation of effects is accomplished by adjusting parameters smoothly from one key-framed value to the next. Animating effects by means of keyframes is often called ‘keyframing’.

LPT: See *Parallel port*.

Luminance: See *Brightness*.

M1V: (File extension for) an MPEG file that contains video data only.

Mbyte (also MB): One Mbyte (megabyte) corresponds to 1024 Kbytes – 1024 x 1024 bytes.

Mark In / Mark Out: In video editing, the mark in and mark out times refer to the starting and ending timecodes that identify the portions of clips to be included in the project.

MCI: Media Control Interface. Programming interface developed by Microsoft recording and playing back audio and video data. It is also used to connect a computer to an external video source such as a VCR or laser disc.

Modulation: The encoding of information upon an empty carrier signal.

Motion-JPEG (M-JPEG): A Video for Windows format, specified by Microsoft, for encoding video sequences. JPEG compression is used to compress each frame individually.

MPA: (File extension for) an MPEG file that contains audio data only. M1V, MPEG, MPG

MPEG: Motion Picture Experts Group, and the standard developed by them for the compression of moving images. Compared to M-JPEG, it offers 75-80% data reduction with the same visual quality.

MPG: (File extension for) an MPEG file that contains both video and audio data.

MPV: (File extension for) an MPEG file that contains video data only.

Non-interlaced: Describes an image refresh method in which the complete image is generated as a single field without skipping lines. A non-interlaced image (most computer monitors) flickers much less than an interlaced image (most TVs).

NTSC: National Television Standards Committee, and the color TV standard created by them in 1953. NTSC video has 525 lines per frame and 60 image fields per second. It is used in North and Central America, Japan and other countries. See *PAL*, *SECAM*.

PAL: "Phase Alternation Line", a color TV standard developed in Germany and used throughout most of Europe. PAL video has 625 lines per frame and 50 image fields per second. See *NTSC*, *SECAM*.

Parallel port: Parallel port data is transmitted via an 8-bit data line. This means that eight bits (one byte) can be transmitted at once. This kind

of transmission is much faster than serial transmission, but is not appropriate for long-distance connections. Parallel ports are often named "LPTn", where n is a number (e.g. "LPT1"). See *Serial port*.

Pixel: The smallest element of a monitor image. The word is an abbreviation of "picture element".

Port: Electrical transfer point for the transmission of audio, video, control or other data between two devices. See *Serial port*, *Parallel port*.

Primary colors: The colors that are the basis of the RGB color model: red, green, and blue. It is possible to create most other colors on a computer screen by varying the blend of these primaries.

QSIF: Quarter Standard Image Format. An MPEG-1 format specifying a resolution of 176 x 144 under PAL and 176 x 120 under NTSC. See *MPEG*, *SIF*.

Quantization: One part of the JPEG image data compression strategy. Relevant details are represented precisely, while details that are less relevant for the human eye are represented with less precision.

Raster: The area of a video display that is covered by sweeping the electron beam of the display in a series of horizontal lines from upper left to lower right (from the viewer's perspective).

Redundancy: This trait of images is exploited by compression algorithms. Superfluous information can be eliminated during compression and restored without loss during decompression.

Resolution: The number of pixels that can be displayed on the monitor horizontally and vertically. The higher the resolution, the more details can be displayed. See *Pixel*.

RGB: Red, Green and Blue: the primary colors in additive color mixing. RGB designates the method used in computer technology of encoding image information in pixels, each containing some combination of the three primaries.

ROM: Read Only Memory: Memory storage that, having been programmed once, retains its data without requiring electrical power. See *EPROM*.

Run Length Encoding (RLE): A technique used in many image compression methods, including JPEG. Repeating values are not stored separately but with a counter to indicate how many times the value occurs in succession – the length of the “run”.

Scaling: Adaptation of an image to a desired size.

SCSI: Small Computers System Interface. SCSI was long preferred as the hard drive interface for some high-performance PCs because of its high data rate. Up to eight SCSI devices can be connected to a computer at the same time.

SECAM: “Séquentiel Couleur à Mémoire”, a color TV transmission system used in France and Eastern Europe. Like PAL, SECAM video has 625 lines per frame and 50 image fields per second. See *NTSC*, *PAL*.

Serial port: Data transmitted via a serial port is processed one bit at a time; that is, “serially” – one after another. The transmission rate is much slower than that of a parallel port, where parallel data lines allow multiple bits to be sent simultaneously. Serial ports are named “COMn”, where n is a number (e.g. “COM2”). See *Parallel port*.

SIF: Standard Image Format. An MPEG-1 format specifying a resolution of 352 x 288 under PAL and 352 x 240 under NTSC. See *MPEG*, *QSIF*.

Single frame: A single frame is part of a series or sequence. When this series is viewed at sufficient speed, the illusion of a “moving picture” is created.

Software codec: Compression method that can create and play back compressed digital video sequences without special hardware. The quality of the sequences depends on the performance of the complete system. See *Codec*, *Hardware codec*.

Still video: Still images (or “freeze-frames”) extracted from video.

S-VHS: Improved version of VHS using S-Video and metal particle tape to deliver higher luminance resolution, resulting in sharper pictures than VHS. See *VHS*, *S-Video*.

S-Video: With S-Video (Y/C) signals, the brightness (luminance or “Y”) and the color (chrominance or “C”) information are transferred separately using multiple wires, avoiding modulating and demodulating the video and the resulting loss of picture quality.

Timecode: Timecode identifies the position of each frame in a video sequence with respect to a starting point (normally the beginning of the shot). The usual format is H:M:S:F (hours, minutes, seconds, frames), e.g. “01:22:13:21”. Unlike a tape counter (which can be “zeroed” or reset at any point in a tape), timecode is an electronic signal written onto videotape, and is permanent once it is assigned.

Transition: A bridging effect between adjacent video or audio clips, ranging from a simple “cut” to a showy animated effect. Common transitions like cuts, fades, dissolves, wipes, slides and audio cross-fades are part of the language of film and video. They can convey passages of time and changes of viewpoint concisely – and often subliminally.

TrueColor: The name indicates an image with enough color resolution to appear “true to life”. In practice, TrueColor normally refers to 24-bit RGB color, which allows about 16.7 million combinations of the red, green and blue primary colors. See *Bit*, *HiColor*.

TWAIN driver: TWAIN is a standardized software interface allowing graphics and capture programs to communicate with devices that supply graphical data. If the TWAIN driver is installed, the capture function of a graphics application can be used to load images directly from your video source into the program. The driver supports 32-bit programs only and captures images in 24-bit mode.

VCR: “Video cassette recorder”.

VHS: “Video Home System” – Popular video standard for home VCRs. Half-inch tape is used to store “composite” signals incorporating both brightness and color information.

VISCA: Protocol used with certain devices for controlling external video sources from computers.

Video8: Analog video system using 8mm tape. Video8 recorders generate composite signals.

Video CD: CD-ROM standard that uses MPEG compressed videos.

Video decoder: Converts digital information into analog video signals.

Video encoder: Converts analog video signals into digital information.

Video for Windows: A Microsoft Windows system extension that can record digital video sequences to files on a hard drive and subsequently play them back.

Video scan rate: Frequency with which the video signal is scanned onto an image display. The higher the video scan rate, the higher the image quality and the less noticeable the flicker.

WAV: (File extension for) a popular file format for digitized audio signals.

White balance: In an electronic camera, this is the adjustment of the amplifiers for the three color channels (red, green and blue) so that white areas of the scene do not show a color cast.

Y/C: Y/C is a color signal with two components: brightness information (Y) and color information (C).

YUV: The color model of a video signal where Y delivers the brightness information and U and V the color information.



The tables below display the default hotkey assignments in Pinnacle Studio. Keys can be individually remapped in Setup. The defaults can also be restored there, either individually or for all the shortcuts at once. For more information, see “Keyboard” on page 374.

The terms Left, Right, Up and Down in the tables refer to the arrow (cursor) keys.

General shortcuts

Ctrl+1	Open Main Library tab
Ctrl+2	Open Movie tab
Ctrl+3	Open Disc tab
Ctrl+4	Close focused window
Ctrl+5	Open Title Editor (from Movie Editor)
Ctrl+6	Open Exporter
Ctrl+ I	Open Importer
Ctrl+S	Save project, title or menu
Alt+F4	Close application
Shift+F10	Access context menu
Ctrl+Z	Undo
Ctrl+Y	Redo
Ctrl+A	Select all
Shift+Ctrl+A	Deselect all

General shortcuts

Ctrl+C	Copy to clipboard
Ctrl+V	Paste from clipboard
Ctrl+X	Cut to clipboard
End	Go to end
Home	Go to beginning
Alt+Enter	Play using full screen
Esc	Exit full-screen viewing, or close panel
Delete	Delete without copying to clipboard
Double-click	Open appropriate editor (Media, Titler, Project, Montage etc.)
F1	Open context sensitive help

Library

Ctrl+N	New collection
Alt+Click	Play in thumbnail
Numbers 1-5	Rate selected clip(s)
Number 0	Remove rating from selected clip(s)
Page Up	Scroll up a page
Page Down	Scroll down a page
Right	Expand folder in tree
Left	Collapse folder in tree
Arrow keys	Navigate up, down, left, right
Delete	Delete selected clip and / or media
F7	Show / hide tagging interface

Playing and transport

Spacebar	Play and pause
Shift+Spacebar	Loop playback
Alt+Enter	Play using full screen
Esc	Exit full-screen viewing
Alt+Click	Play in thumbnail
J	Fast reverse (hit multiple times for faster playback)
K (or Shift K)	Pause playback
L	Fast forward (hit multiple times for faster playback)
Shift+L	Slow forward (hit multiple times for slower playback)
Shift+J	Slow reverse (hit multiple times for slower playback)
Right (or X)	Step forward 1 frame
Left (or Z)	Step back 1 frame
Shift+Right (or Shift+X)	Step forward 10 frames
Shift+Left (or Shift+Z)	Step backward 10 frames
D (or Page up) (or Ctrl+Left)	Jump backward to cut
F (or Page down) (or Ctrl+Right)	Jump forward to cut
Ctrl+I	Jump to mark in
Ctrl+O	Jump to mark out
. (period)	Jump to next marker
, (comma)	Jump to previous marker

Importer

Enter	Stop Motion: Capture Frame (when capture frame is open)
Right	Expand folder in tree
Left	Collapse folder in tree
Arrow keys	Navigate up, down, left, right
Ctrl+A	Check all
Ctrl+Shift+A	Uncheck all
F4	Start Import

Movie interface

A (or I)	Mark in
S (or O)	Mark out
Shift+I	Clear mark in
Shift+O	Clear mark out
Shift+U	Clear mark in and out
Scroll Lock	Audio Scrub On/Off
E (or Home)	Go to start
R (or End)	Go to end
P	Toggle Magnetic Snapping
; (semicolon)	Split clip(s) at scrubber position
M	Add/Delete marker
. (period)	Jump to next marker
, (comma)	Jump to previous marker
Ctrl+. (period)	Open Marker list panel

Movie interface

Delete	Delete selected clip(s) from timeline
Double-click on clip in timeline	Open media editor for clip
B	Send preview clip to the primary track on the timeline (at scrubber position)
H	Swap Preview between timeline and source
Ctrl+5	Open Title Editor
F5	Show/Hide Audio Mixer
F7	Create Song
Numeric pad +	Zoom in the timeline
Numeric pad -	Zoom out the timeline
[(left bracket)	Zoom out on the timeline
] (right bracket)	Zoom in on the timeline
Ctrl+[Fit timeline to window
Ctrl+]	Show every frame (zoom in)
Alt	Provides the alternate behavior when editing on the timeline (insert/overwrite)
T	Trim Mode On/Off
Right	Trim 1 frame right (with trim open)
Left	Trim 1 frame left (with trim open)
Shift+ Right	Trim 10 frames right (with trim open)
Shift+ Left	Trim 10 frames left (with trim open)
Ctrl+Click on trim	Add second trim point to the same track

Movie interface

Shift+Click on trim	Open similar trim point on all tracks
Tab	Cycle focus on open trim points

Media editors

Numbers 1-8	Choose a corrections or effects category
Double-click slider	Return slider to default
Ctrl+L	Rotate Photo Left
Ctrl+R	Rotate Photo Right
Alt+Enter	Play using full screen
Esc	Exit full-screen viewing

Title Editor

Shift+Left	Expand character selection left
Shift+Right	Expand character selection right
Shift+Ctrl+Left	Same as Shift+Left (expand by word)
Shift+Ctrl+Right	Same as Shift+Right (expand by word)
Ctrl+B	Toggle bold
Ctrl+I	Toggle italic
Ctrl+U	Toggle underline
Ctrl+A	Select all
Ctrl+D	Deselect all
Spacebar	With timeline area selected: Start and stop playback



The Pinnacle Studio Installation Manager looks after the job of installing Pinnacle Studio and any additional content included in your purchase of the application.

Before you begin

For a trouble-free installation of Pinnacle Studio, we recommend a number of preparatory steps.

Begin by confirming that your computer meets the minimum system requirements for the product. Note that some operations, such as AVCHD encoding, have more stringent requirements. For more information, see “System requirements” on page 456.

Next, ensure that your Studio serial number is available. For a downloaded copy of the application, you will find this information in your order confirmation mail; you can also retrieve it from your customer account. If you obtained your copy of Pinnacle Studio on disc, the serial number will be found on the DVD sleeve. We recommend that you keep a record of your serial number in a safe place.

On some systems, it may be advisable to disable antivirus protection before installing Pinnacle Studio.

Note: Pinnacle Studio can be installed on a system containing a previous Studio installation: both versions will coexist.

Upgrade Installation

If a qualifying previous version of the software is currently installed on the computer, the Installation Manager will automatically recognize its presence and permit the upgrade.

Qualifying versions include:

- Pinnacle Studio 10 to 18
- Avid Studio
- Avid Liquid 6 to 7

If none of these is currently installed on the machine, you will be prompted to provide instead the serial number of the previous product.

Launching the Installation Manager

If you bought Studio from an Internet store as a downloadable file, the Installation Manager will start when you run the executable program you downloaded. (Even before you do so, consider making a copy of the downloaded files to a back-up location like a DVD or an external hard drive.)

If you bought Studio on a DVD disc, the Installation Manager will autostart on most systems when that disc is inserted. If it does not launch automatically on your computer, please locate and run the file "Welcome.exe" in the root directory of the DVD.

Registration

Your first launch of the Installation Manager begins by displaying an input form for activating and registering your product. Although you are allowed to activate Pinnacle Studio (validating your user license)

without registering the product, registration is recommended. It makes it possible to streamline product support for problems like losing your serial number.

Supporting installations

The application requires a number of Windows software components, including the .NET Framework, to be present on your system. The Installation Manager determines automatically if the components are available, and installs them if necessary. Such supporting installations require additional time, but the main Pinnacle Studio installation will resume as soon as they have completed, even if the system was restarted in the process.

The Welcome Screen

The Welcome Screen lets you choose between two styles of installation:

Standard Installation installs the application and all available plug-ins. It is recommended for most users.

The Customized Installation option lets you choose to install only a subset of the add-ons available.

Common controls

Some controls are available under either installation method:

- The Change installer location button lets you specify the folder that contains the installation files you want the Installation Manager to handle. You will only need to use it if you have moved the installation files after first use. The button opens a folder

browser that lets you point the Installation Manager to the new location.

- The links provided under Learn while installing give access to information on just about any Studio-related topic.

Installing plugs-ins and bonus content

As described above, the Installation Manager can optionally install a rich variety of content in addition to the Pinnacle Studio application itself. In a Standard Installation, all available add-ons and plug-ins are installed. In a Customized Installation, you can choose exactly which items to install.

Even if you elect not to install particular content items during the initial installation of the application, you may return to the Installation Manager at any time to update your installation.

System requirements

In addition to your Pinnacle Studio software, an efficient editing system requires certain levels of system performance as noted below.

Remember too that while specifications are important, they do not tell the whole story. For instance, the proper functioning of hardware devices can also depend on manufacturer-supplied driver software. Checking the maker's web-site for driver updates and support information can often be helpful in solving problems with graphics cards, sound cards and other devices.

Operating system

A 64-bit operating system is recommended if you are planning to edit HD material.

RAM

The more RAM you have, the easier it is to work with Pinnacle Studio. You will need at least 1 GB of RAM to achieve satisfactory operation, and we highly recommend 2 GB (or more). If you work with HD or AVCHD video, the recommendation rises to 4 GB.

Motherboard

Intel Pentium or AMD Athlon 2.4 GHz or higher – the higher the better. AVCHD editing demands a more powerful CPU. The minimum recommendation ranges up to 2.66 GHz for editing 1920- pixel AVCHD video. A multi-core system like Core i7, Core i5 or Core i3 is recommended.

Graphics card

To run Studio, your DirectX-compatible graphics card needs:

- For typical use, at least 128 MB of onboard memory (256 MB preferred).
- For HD and AVCHD, at least 256 MB (512 MB preferred).

The hard drive

Your hard drive must be capable of sustained reading and writing at 4 MB/sec. Most drives are capable of this. The first time you capture, Studio will test your drive to make sure it is fast enough. Video files are often quite large, so you also need a good amount of available hard drive space. For instance, video in the DV format fills 3.6 MB of hard drive space per second of footage: a gigabyte every four and a half minutes.

For capture from video tape, we recommend using a separate hard drive to avoid competition between Pinnacle Studio and other software, including Windows, for use of the drive.

Video capture hardware

Studio can capture video from a variety of digital and analog sources:

- All types of auxiliary file-based storage media, including optical drives, memory cards and USB sticks.
- Files from drives connected to the computer.
- DV or HDV video cameras using an IEEE-1394 connection.
- Analog video cameras and recorders.
- DVD and Blu-ray discs.
- Digital still cameras.

Pinnacle Studio™ 20 User Guide

Copyright 2016 Corel Corporation. All rights reserved.

Product specifications, pricing, packaging, technical support and information (“specifications”) refer to the retail English version only. The specifications for all other versions (including other language versions) may vary.

Corel patent information: www.corel.com/patent

INFORMATION IS PROVIDED BY COREL ON AN “AS IS” BASIS, WITHOUT ANY OTHER WARRANTIES OR CONDITIONS, EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, WARRANTIES OF MERCHANTABILITY, SATISFACTORY QUALITY, MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, OR THOSE ARISING BY LAW, STATUTE, USAGE OF TRADE, COURSE OF DEALING OR OTHERWISE. THE ENTIRE RISK AS TO THE RESULTS OF THE INFORMATION PROVIDED OR ITS USE IS ASSUMED BY YOU. COREL SHALL HAVE NO LIABILITY TO YOU OR ANY OTHER PERSON OR ENTITY FOR ANY INDIRECT, INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES WHATSOEVER, INCLUDING, BUT NOT LIMITED TO, LOSS OF REVENUE OR PROFIT, LOST OR DAMAGED DATA OR OTHER COMMERCIAL OR ECONOMIC LOSS, EVEN IF COREL HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES, OR THEY ARE FORESEEABLE. COREL IS ALSO NOT LIABLE FOR ANY CLAIMS MADE BY ANY THIRD PARTY. COREL’S MAXIMUM AGGREGATE LIABILITY TO YOU SHALL NOT EXCEED THE COSTS PAID BY YOU TO PURCHASE THE MATERIALS. SOME STATES/COUNTRIES DO NOT ALLOW EXCLUSIONS OR LIMITATIONS OF LIABILITY FOR CONSEQUENTIAL OR INCIDENTAL DAMAGES, SO THE ABOVE LIMITATIONS MAY NOT APPLY TO YOU.

© 2016 Corel Corporation. All rights reserved. Corel, the Corel logo, the Corel Balloon logo, Pinnacle Studio, Dazzle, and MovieBox are trademarks or registered trademarks of Corel Corporation and/or its subsidiaries. All other product names and any registered and unregistered trademarks mentioned are used for identification purposes only and remain the exclusive property of their respective owners.

Please respect the Rights of Artists and Creators. Content such as music, photos, video and celebrity images are protected by the laws of many countries. You may not use other people's content unless you own the rights or have the permission of the owner.